




Woollahra Local Planning Panel (Electronic Meeting)

Thursday 18 July 2024
at the Conclusion of Public Meeting

Minutes



Woollahra Local Planning Panel (Electronic) Minutes

Thursday 18 July 2024

Table of Contents

Item	Subject	Pages
D1	DA364/2023/1 - 618-622 Old South Head Road, Rose Bay.....	4
D2	DA411/2023/1 - 54 Cranbrook Road Bellevue Hill	72
D3	DA28/2024/1 - 426-432 New South Head Road Double Bay	79
D4	DA354/2023/1 - 14 Manning Road Double Bay.....	85
D5	DA255/2023/1 - 374 Oxford Street Paddington.....	155

Woollahra Local Planning Panel (Electronic)

Minutes of the Meeting held on 18 July 2024 at the Conclusion of the Public Meeting

Present:	David Ryan	(Chair)
	Peter Brennan	(Expert)
	Larissa Ozog	(Expert)
	Malcolm Young	(Community Representative)
Staff:	George Fotis	(Team Leader)
	Carolyn Nurmi	(Governance Officer)
	Brett McIntyre	(Acting Team Leader)
	Thomas Wong	(Acting Manager Development Control)

Note: The Panel was briefed by Council staff on each Item prior to the meeting.
The Panel then deliberated and voted on each Item in a confidential meeting.
The decisions are recorded in these Minutes.

Leave of Absence and Apologies

Nil

Late Correspondence

Late correspondence was submitted to the Panel in relation to item D1

Declarations of Interest

Malcolm Young declared a Non Pecuniary, Non-Significant interest in Item D4 (14 Manning Road, Double Bay – DA354/2023/1) as some years ago Mr Young was on a residents' committee with Ms G Ettinger-Epstein. Mr Young noted Ms G Ettinger-Epstein's short objection seemed principally to relate to a possible condition or conditions of consent rather than whether consent should be granted. Mr Young further declared knowing Sacha Ettinger, Councillor Mark Silcocks and Katherine Grinberg from the Double Bay Residents Association, all of whom made submissions in the Late Correspondence. Mr Young remained in the meeting, participated in the debate and voted on the matter.

The Chair, David Ryan declared a Significant, Non-Pecuniary interest in Item D5 (374 Oxford Street, Paddington – DA255/2023/1) as Mr Ryan's company, Gyde has provided and continues to provide consultant town planning services for several development projects (not including the subject site) on behalf of entities associated with the applicant/owner (Hemmes). Mr Ryan left the meeting during this item, did not participate in the debate and did not vote on the matter.

ITEM No. D1
FILE No. DA364/2023/1
ADDRESS 618-622 Old South Head Road, Vaucluse
PROPOSAL Demolition of the existing buildings and construction of a new residential flat building containing 11 units, and associated landscaping works

Reasons for Decision

The Panel has undertaken a site inspection, considered any submissions and reviewed the assessment report prepared by Council officers that addresses the relevant matters detailed in Section 4.15 of the Environmental Planning and Assessment Act 1979.

For the reasons generally in the assessment report, the Panel is satisfied that the application can be approved.

Resolved: Pursuant to Section 4.16 of the Environmental Planning and Assessment Act 1979

THAT the Woollahra Local Planning Panel, exercising the functions of Council, as the consent authority, is satisfied that the written request from the applicant under Clause 4.6 of the Woollahra Local Environmental Plan 2014 to the height of buildings development standard under Clause 4.3 of the Woollahra LEP 2014 has adequately addressed the relevant matters under Clause 4.6 (3) and the proposed development will be in the public interest because it is consistent with the relevant objectives of the particular standard and the zone. The Panel assumes the concurrence of the Secretary, Department of Planning, Industry and Environment.

AND

THAT the Woollahra Local Planning Panel, exercising the functions of Council, as the consent authority, grant development consent to Development Application No. 364/2023/1 for demolition of the existing buildings and construction of a new residential flat building containing 11 units, and associated landscaping works on land at 620 Old South Head Road Rose Bay, subject to the following conditions:

A. GENERAL CONDITIONS

A. 1.	Conditions Consent is granted subject to the following conditions imposed under section 4.16 of the Environmental Planning and Assessment Act 1979 (“the Act”), and the provisions of the Environmental Planning and Assessment Regulation 2021 (“the Regulations”) and the provisions of the Environmental Planning and Assessment (Development Certification and Fire Safety) Regulation 2021 (“the Development Certification and Fire Safety Regulations”), such conditions being reasonable and relevant to the development as assessed under section 4.15 of the Act. Notes: <ul style="list-style-type: none">• Failure to comply with this development consent and any condition of this consent is a criminal offence. Failure to comply with other environmental laws is also a criminal offence.• Where there is any breach Council may without any further warning:<ul style="list-style-type: none">a) Issue Penalty Infringement Notices (On-the-spot fines);b) Issue notices and orders;c) Prosecute any person breaching this consent; and/ord) Seek injunctions/orders before the courts to restrain and remedy any breach.• Maximum penalties under NSW environmental laws include fines up to \$1.1 Million and/or custodial sentences for serious offences.
--------------	---

	<ul style="list-style-type: none"> • Should Council have to take any action to enforced compliance with this consent or other environmental laws Council's policy is to seek from the Court appropriate orders requiring the payments of its costs beyond any penalty or remedy the Court may order. • This consent and this specific advice will be tendered to the Court when seeking costs orders from the Court where Council is successful in any necessary enforcement action. • The payment of environmental penalty infringement notices does not result in any criminal offence being recorded. If a penalty infringement notice is challenged in Court and the person is found guilty of the offence by the Court, subject to section 10 of the Crimes (Sentencing Procedure) Act 1999, a criminal conviction is recorded. The effect of a criminal conviction beyond any fine is serious.
	<p>Condition Reason: To ensure all parties are aware of the relevant legislation that applies to the development.</p>
<p>A. 2.</p>	<p>Definitions</p> <p>Unless specified otherwise, words have the same meaning as defined by the <i>Act</i>, the <i>Regulations</i>, the <i>Development Certification and Fire Safety Regulations</i> and the <i>Interpretation Act 1987</i> as in force at the date of consent.</p> <p>Applicant means the applicant for this consent.</p> <p>Approved Plans mean the plans endorsed by Council referenced by this consent as amended by conditions of this consent.</p> <p>Local native plants means species of native plant endemic to Sydney's eastern suburbs.</p> <p>Owner-builder has the same meaning as in the <i>Home Building Act 1989</i>.</p> <p>PC means the Principal Certifier under the <i>Act</i>.</p> <p>Principal Contractor has the same meaning as in the <i>Act</i>, or where a Principal Contractor has not been appointed by the Owner of the land being developed Principal Contractor means the Owner of the land being developed.</p> <p>Professional engineer has the same meaning as in the <i>BCA</i>.</p> <p>Public place has the same meaning as in the <i>Local Government Act 1993</i>.</p> <p>Road has the same meaning as in the <i>Roads Act 1993</i>.</p> <p>SEE means the final version of the Statement of Environmental Effects lodged by the Applicant.</p> <p>Site means the land being developed subject to this consent.</p> <p>Site work means any work that is physically carried out on the land to which the development the subject of this development consent is to be carried out, including but not limited to building work, subdivision work, demolition work, clearing of vegetation or remediation work.</p> <p>Woollahra LEP means <i>Woollahra Local Environmental Plan 2014</i></p> <p>Woollahra DCP means <i>Woollahra Development Control Plan 2015</i></p> <p>Work for the purposes of this consent means:</p> <ul style="list-style-type: none"> • the use of land in connection with development,

	<ul style="list-style-type: none"> • the subdivision of land, • the erection of a building, • the carrying out of any work, • the use of any site crane, machine, article, material, or thing, • the storage of waste, materials, site crane, machine, article, material, or thing, • the demolition of a building, • the piling, piercing, cutting, boring, drilling, rock breaking, rock sawing or excavation of land, • the delivery to or removal from the <i>site</i> of any machine, article, material, or thing, or • the occupation of the <i>site</i> by any person unless authorised by an occupation certificate.
	<p>Condition Reason: To ensure all parties are aware of the relevant definitions.</p>
<p>A. 3.</p>	<p>Deferred Commencement - (section 4.16(3) of the Act, clause 76 of the Regulation)</p> <p>Development consent is granted subject that this consent is not to operate until the Applicant satisfies the Council, in accordance with the Regulations, as to all matters specified in this condition:</p> <p>a) The allotments 618, 620, and 622 Old South Head Road comprising Lot 56, Section B, in DP 4247, and Lots A and B in DP 415971, are to be consolidated to form one allotment. The plan of the consolidated allotments is to be prepared by a registered surveyor and registered with NSW Land Registry Services. Evidence of registration is to be submitted to Council’s satisfaction.</p> <p>The Applicant must produce evidence to Council sufficient enough to enable it to be satisfied as to those matters above within 365 days (1 year) of the date of determination.</p> <p>Clause 76(3) of the Regulation:</p> <p>“A consent authority may specify the period within which the applicant must produce sufficient evidence to the consent authority to enable it to be satisfied about the relevant matters”.</p> <p>If the evidence is not produced with within 365 days (1 year) of the date of determination this deferred commencement consent is of no effect, the consent does not operate and no Construction Certificate can be issued. No development can lawfully occur under this consent unless it operates.</p> <p>This consent does not operate until Council has acknowledged compliance with this condition in writing.</p> <p>Notes:</p> <ul style="list-style-type: none"> • Nothing in the Act prevents a person from doing such things as may be necessary to comply with this condition. (See section 4.16(3) of the Act). • Implementing the development prior to written confirmation of compliance may result in legal proceedings. If such proceedings are required Council will seek all costs associated with such proceedings as well as any penalty or order that the Court may impose. No Construction Certificate can be issued until all conditions including this condition required to be satisfied prior to the issue of any Construction Certificate have been satisfied. <p>Condition Reason: To ensure all parties are aware this consent does not operate until the Council is satisfied all relevant matters specified in this condition are addressed.</p>

A. 4. Approved Plans and Supporting Documents

Those with the benefit of this consent must carry out all work and maintain the use and works in accordance with both the architectural plans to which is affixed a Council stamp "Approved" and supporting documents listed below unless modified by any following condition.

Where the plans relate to alterations or additions only those works shown in colour or highlighted are approved.

Reference	Description	Author	Date
DA 1002 Rev C	Site & Roof Plan	MHND Union	8/04/2024
DA 2000 Rev C	Basement 2 Plan		
DA 2001 Rev C	Basement 1 Plan		
DA 2002 Rev C	Ground Floor Plan		
DA 2003 Rev C	Level 1 Floor Plan		
DA 2004 Rev C	Level 2 Floor Plan		
DA 2005 Rev C	Roof Plan		
DA 2006 Rev C	Rooftop Lobby Roof		
DA 3000 Rev C	Elevation North		
DA 3001 Rev C	Elevation South		
DA 3002 Rev C	Elevation East		
DA 3003 Rev C	Elevation West		
DA 3100 Rev C	Section A		
DA 3101 Rev C	Section B		
DA 3104 Rev C	Section C		
DA 3105 Rev C	Section D		
DA 3106 Rev C	Section E		
1418155M_02	BASIX Certificate	NSW Department of Planning and Environment	8/04/2024
2023-122	Geotechnical Report	Crozier Geotechnical Consultants	14/09/2023
2023-122	Infiltration Report	Crozier Geotechnical Consultants	31/10/2023
LPDA 23-291/1 LPDA 23-291/2 LPDA 23-291/3 LPDA 23-291/4 LPDA 23-291/5 LPDA 23-291/6 LPDA 23-291/7 LPDA 23-291/8	Landscape Plan (Rev H)	Conzept	21/03/2024
Ref.8796.1	Arboricultural Impact Assessment Report	Redgum	25/09/2023
Ref.8796.1	Tree Management Plan	Redgum	25/09/2023
230604 SW001-Issue B SW002-Issue B SW100-Issue B SW101-Issue B SW102-Issue C SW103-Issue B SW104-Issue B SW105-Issue C SW200-Issue B SW201-Issue B SW202-Issue B	Stormwater Management Plans	RTS Engineers	30/10/2023 30/10/2023 30/10/2023 30/10/2023 16/02/2024 30/10/2023 30/10/2023 05/04/2024 30/10/2023 30/10/2023 30/10/2023
23119 V02	Traffic Impact Assessment	TTPP	13/09/2023
23119	Traffic Letter in Response to Council RFI	TTPP	23/10/2023

Notes:

- Warning to Principal Certifier – You must always insist on sighting the original Council stamped approved plans. You must not rely solely upon the plan reference numbers in this condition. Should the Applicant not be able to provide you with the original copy Council will provide you with access to its files so you may review our original copy of the approved plans.

	<ul style="list-style-type: none"> • These plans and supporting documentation may be subject to conditions imposed under section 4.17(1)(g) of the Act modifying or amending the development.
	<p>Condition Reason: To ensure all parties are aware of the approved plans and supporting documentation that applies to the development.</p>
<p>A. 5.</p>	<p>Ancillary Aspects of Development (section 4.17(2) of the Act)</p> <p>The Owner must procure the repair, replacement or rebuilding of all road pavement, kerb, gutter, footway, footpaths adjoining the site or damaged as a result of work under this consent or as a consequence of work under this consent. Such work must be undertaken to Council's satisfaction in accordance with Council's Specification for Roadworks, Drainage and Miscellaneous Works (2012) unless expressly provided otherwise by these conditions at the Owner's expense.</p> <p>Notes:</p> <ul style="list-style-type: none"> • This condition does not affect the Principal Contractor's or any sub-contractors obligations to protect and preserve public infrastructure from damage or affect their liability for any damage that occurs. <p>Condition Reason: To ensure all parties are aware of works required to public infrastructure and to ensure payment for works.</p>
<p>A. 6.</p>	<p>Transport for NSW (TfNSW) concurrence under Section 138 of the <i>Roads Act 1993</i></p> <p>TfNSW has reviewed the application and grants concurrence to the proposed driveway under Section 138 of the <i>Roads Act 1993</i>, subject to the following conditions:</p> <ul style="list-style-type: none"> • In accordance with AS2890.1 -2004, the driveway shall be a minimum of 5.5 metres for a minimum distance of 6 metres within the subject site to allow for simultaneous vehicular entry and exit movements. • Redundant driveways on Old South Head Road shall be removed and replaced with kerb and gutter to match existing. • The proposed driveway including splays shall not be located any further north than the existing northern most driveway to ensure there is no impact on the existing pram ramp associated with the existing pedestrian refugee island on Old South Head. As such, any widening of the existing northern most driveway can only be accommodated to the south. • The design and construction of the proposed kerb and gutter works and proposed driveway on Old South Head Road shall be designed to meet TfNSW requirements and be endorsed by a suitably qualified practitioner. The design requirements shall be in accordance with Austroads and other Australian Codes of Practice. The certified copies of the civil design plans shall be submitted to TfNSW for consideration and approval prior to the release of the construction certificate by the Principal Certifying Authority and commencement of road works. Please send all documentation to development.sydney@transport.nsw.gov.au. • The developer is required to enter a Works Authorisation Deed (WAD) for the abovementioned works. • TfNSW fees for administration, plan checking, civil works inspections and project management shall be paid by the developer prior to the commencement of works. • Detailed design plans and hydraulic calculations of any changes to the stormwater drainage system on Old South Head Road are to be submitted to TfNSW for approval, prior to the commencement of any works. Please send all documentation to development.sydney@transport.nsw.gov.au.

- A plan checking fee will be payable, and a performance bond may be required before TfNSW approval is issued. The developer is to submit design drawings and documents relating to the excavation of the site and support structures to TfNSW for assessment, in accordance with Technical Direction GTD2020/001.

Condition Reason: To ensure all parties are aware of the general terms of approval.

A. 7. Tree Preservation and Landscaping Works

While site work is being carried out, all landscape works must be undertaken in accordance with the approved landscape plan, arborist report, tree management plan and transplant method statement as applicable.

a) The following trees must be retained:

- Trees on private land:

Council Ref No	Species	Location	Dimension (metres)
6	<i>Cupaniopsis anacardioides</i> (Tuckeroo)	Rear at 618 OSHR	7 x 5
8	<i>Syzygium</i> sp. (Lillypilly)	Rear at 620 OSHR	6 x 4
9	<i>Brachychiton acerifolius</i> (Illawarra Flame tree)	Rear at 622 OSHR	10 x 8
11	<i>Syzygium</i> sp. (Lillypilly)	Rear at 620 OSHR	7 x 6

- Trees on Council land:

Council Ref No	Species	Location	Dimension (metres)
1	<i>Angophora costata</i> (Sydney Red Gum)	Council verge	7 x 4
14	<i>Angophora costata</i> (Sydney Red Gum)	Council verge	6 x 2

The tree/s required to be retained must appear coloured green on the Construction Certificate plans.

b) The following trees may be removed:

Council Ref No	Species	Location	Dimension (metres)
2	<i>Dypsis lutescens</i> (Golden Cane palm)	Front at 618 OSHR	6 x 4
3	<i>Olea europea var. africana</i> (African Olive) *	Front at 618 OSHR	5 x 3
4	<i>Cordyline stricta</i> (Narrow Palm Lily)	Front at 618 OSHR	5 x 2
5	<i>Cupressocyparis leylandii</i> (Leyland Cypress) – hedge *	Front at 618 OSHR	7 x 5
10	<i>Celtis sinensis</i> (Chinese Nettle) *	Rear at 620 OSHR	10 x 10
12	<i>Magnolia grandiflora</i> (Bull Bay Magnolia)	Rear at 622 OSHR	8 x 6

	<p>The tree/s that may be removed must appear coloured red on the Construction Certificate plans.</p> <p>The species marked (*) is exempt from the WMC DCP 2015 and can be removed without requiring consent from Council.</p>
	<p>Condition Reason: To ensure all landscape works are undertaken in accordance with the approved plans and documents.</p>
A. 8.	<p>No Underpinning works</p>
	<p>This development consent does NOT give approval to any works outside the boundaries of the subject property including any underpinning works to any structures on adjoining properties.</p>
	<p>Condition Reason: To ensure all works are located within the boundaries of the site and to confirm that no consent is granted for underpinning works to any structures on adjoining properties.</p>

DEMOLITION WORK

B. BEFORE DEMOLITION WORK COMMENCES

B. 1.	<p>Construction Certificate Required Prior to Any Demolition</p>
	<p>Where demolition is associated with an altered portion of, or an extension to an existing building the demolition of any part of a building is "commencement of erection of building" under section 6.6 of the Act.</p> <p>In such circumstance all conditions included at the following development stages of this consent must be satisfied prior to any demolition work:</p> <ul style="list-style-type: none"> • Before issue of a construction certificate • Before building work commences <p>This includes, but is not limited to, the issue of a Construction Certificate, appointment of a Principal Certifier, and Notice of Commencement under the Act.</p> <p>Note:</p> <ul style="list-style-type: none"> • See Over our Dead Body Society Inc v Byron Bay Community Association Inc [2001] NSWLEC 125.
	<p>Condition Reason: To ensure appropriate conditions are complied with for development for the alteration and extension of an existing building.</p>
B. 2.	<p>Recording of Buildings with Little or No Heritage Significance that are to be Demolished</p>
	<p>Prior to any site works and prior to the issue of any Construction Certificate, a photographic archival record of the building and landscape elements to be demolished is to be submitted, to the satisfaction of Council's heritage officer.</p> <p>The photographic archival recording is to be submitted in a digital format and is to include the following:</p>

	<p>a) Site plan at a scale of 1:200 (or 1:500 if appropriate) of all structures and major landscape elements including their relationship to the street and adjoining properties and directional details of photographs taken.</p> <p>b) Coloured photographs of:</p> <ul style="list-style-type: none"> • each elevation, • each structure and landscape feature, and • views to the subject property from each street and laneway or public space. <p>Notes:</p> <ul style="list-style-type: none"> • Refer to the NSW Office of Environment and Heritage website for the free publication 'Photographic Recording of Heritage Items using Film or Digital Capture' available at https://www.environment.nsw.gov.au/-/media/OEH/Corporate-Site/Documents/Heritage/photographic-recording-of-heritage-items-using-film-or-digital-capture.pdf <p>Condition Reason: To ensure existing building and landscape elements are recorded.</p>
<p>B. 3.</p>	<p>Erosion and Sediment Controls – Installation</p> <p>Before any site work commences, water pollution, erosion and sedimentation controls must be installed and maintained in accordance with:</p> <p>a) “Do it Right On Site, Soil and Water Management for the Construction Industry” and accompanying factsheets published by the Southern Sydney Regional Organisation of Councils, and</p> <p>b) “Managing Urban Stormwater - Soils and Construction” 2004 published by the NSW Government (The Blue Book).</p> <p>Where there is any conflict The Blue Book takes precedence.</p> <p>Notes:</p> <ul style="list-style-type: none"> • The “Do it Right On Site, Soil and Water Management for the Construction Industry” publication and accompanying factsheets can be downloaded from www.woollahra.nsw.gov.au and The Blue Book is available at www.environment.nsw.gov.au • A failure to comply with this condition may result in penalty infringement notices, prosecution, notices and orders under the Act and/or the Protection of the Environment Operations Act 1997 without any further warning. It is a criminal offence to cause, permit or allow pollution. • Section 257 of the Protection of the Environment Operations Act 1997 provides inter alia that “the occupier of premises at or from which any pollution occurs is taken to have caused the pollution”. • Warning: Irrespective of this condition any person occupying the site may be subject to proceedings under the Protection of the Environment Operations Act 1997 where pollution is caused, permitted or allowed as the result of their occupation of the land being developed. <p>Condition Reason: To prevent potential water pollution and dust nuisance.</p>
<p>B. 4.</p>	<p>Establishment Tree Protection Measures within the Tree Protection Zones (TPZ)</p> <p>Prior to any site works, tree protection measures must be established around all trees to be retained in accordance with Section 4 of the Australian Standard Protection of Trees on Development Sites (AS 4970).</p> <p>The Tree Protection Zones must be calculated in accordance with Section 3 of the Australian Standard Protection of Trees on Development Sites (AS 4970).</p>

A Construction Site Management Plan, which clearly details the tree protection measures, must be prepared before the issue of a construction certificate. The tree protection measures must comply with the following requirements;

a) Tree Protection Fencing:

Council Ref No	Species	Tree Location	Fence Radius from Centre of Trunk (Metres)*
6	<i>Cupaniopsis anacardioides</i> (Tuckeroo)	Rear at 618 OSHR	As per Arboricultural Impact Assessment Report & Tree Management Plan Ref.8796.1 written by Redgum, dated 25/09/2023
8	<i>Syzygium</i> sp. (Lillypilly)	Rear at 620 OSHR	
9	<i>Brachychiton acerifolius</i> (Illawarra Flame tree)	Rear at 622 OSHR	
11	<i>Syzygium</i> sp. (Lillypilly)	Rear at 620 OSHR	
13	<i>Cupressocyparis leylandii</i> (Leyland Cypress)	Rear at 624 OSHR	

Where this condition relates to street trees, and the fence cannot be placed at the specified radius, the fencing is to be positioned so that the entire verge (nature strip) area in front of the subject property, excluding existing driveways and footpaths, and bus stops is protected.

Where this condition relates to trees on private property, the radial distance of fencing must be positioned only within the subject property relating to the development consent.

b) Tree Protection Zones must be fenced with a 1.8 metre high chainmesh or weldmesh fence and secured to restrict access. The fence must be established prior to any materials being brought onto the site and before the commencement of works including demolition. The area within the fence must be mulched and the mulch layer maintained to a depth of 75mm. The soil within the TPZ area must be kept in a moist condition for the duration of the construction works. Unless approved by the site arborist there must be no access within the TPZ area.

c) Trunk protection must be installed around the trunks of the following trees:

Council Ref No	Species
1	<i>Angophora costata</i> (Sydney Red Gum)
14	<i>Angophora costata</i> (Sydney Red Gum)

Trunk protection must consist of a padding material such as hessian or thick carpet underlay wrapped around the trunk. Hardwood planks (50mm x100mm or similar) must be placed over the padding and around the trunk of the tree at 150mm centres. The planks must be secured with 8 gauge wire at 300mm spacing. Trunk protection must extend a minimum height of 2 metres or to the maximum possible length permitted by the first branches.

d) Signs identifying the Tree Protection Zone area must be erected on each side of the protection fence indicating the existence of a TPZ area. Signage must be visible from within the development site.

e) No excavation, construction activity, grade changes, storage of materials, stockpiling, siting of works sheds, preparation of mixes or cleaning of tools is permitted within Tree Protection Zones, unless specified in this consent.

	<p>f) Temporary access within the TPZ area for pedestrian and machinery movements must only be permitted with the approval of the site arborist or unless specified in this consent.</p> <p>g) The site supervisor must be made aware of all tree protection requirements associated with these conditions of consent by the project arborist. Any subsequent site personnel and contractors to the site must be made aware of all tree protection requirements by the site foreman.</p> <p>h) The project arborist must provide written certification of compliance to the Principal Certifier with the above conditions.</p>
	<p>Condition Reason: To ensure the protection of existing trees</p>
<p>B. 5.</p>	<p>Identification of Hazardous Material</p> <p>Prior to any site works, and in accordance with Australian Standard AS2601: The Demolition of Structures, all hazardous substances located on the site must be identified, including asbestos, polychlorinated biphenyls (PCBs), lead paint, underground storage tanks, chemicals, etc.</p> <p>In this regard, prior to any site works, Council must be provided with a written report prepared by a suitably qualified competent person detailing:</p> <ul style="list-style-type: none"> • all hazardous materials identified on the site, • the specific location of all hazardous materials identified, • whether the hazardous materials are to be removed from the site as part of the works to be undertaken, and • safety measures to be put in place. <p>Condition Reason: To protect the health and safety of all persons while works are being undertaken and to ensure all safety measures have been identified and are in place to protect all parties in the immediate vicinity of the site.</p>
<p>B. 6.</p>	<p>Public Road Assets Prior to Any Work/Demolition</p> <p>Prior to any site works, a full record of the condition of the public infrastructure on public land adjacent to the development site must be submitted to Council.</p> <p>The report must include photographs and/or CCTV footage showing the current condition and any existing damage fronting and adjoining the site to the:</p> <ul style="list-style-type: none"> • road pavement, • street signage including street lights, • kerb and gutter, • footway including pedestrian crossings, footpath, and driveways, • retaining walls, or other significant structures, • Heritage Items, including street name inlays, • utility service items including historical utility covers, and • drainage structures/pits/pipes (CCTV footage). <p>The reports are to be supplied in electronic format in Word and if applicable accompanied by CCTV footage. Photographs are to be in colour, digital and date stamped.</p> <p>If the required report is not submitted then Council will assume there was no damage to any infrastructure in the immediate vicinity of the site prior to the commencement of any site works under this consent.</p>

	<p>Condition Reason: To clarify the condition of the existing public infrastructure prior to the commencement of any site works.</p>
<p>B. 7.</p>	<p>Skeletal Remains</p> <p>While site work is being carried out, if any skeletal remains suspected of being human are found, work must cease immediately and no further disturbance of the site must occur. The following must be notified:</p> <ul style="list-style-type: none"> a) NSW Police, and b) The person who is the authority for the protection of Aboriginal objects under the National Parks and Wildlife Act 1974, section 85. <p>Details of the remains and their precise location are to be provided.</p> <p>Site work may recommence at a time confirmed in writing by the NSW Police and the person who is the authority for the protection of Aboriginal objects under the National Parks and Wildlife Act 1974, section 85.</p>
	<p>Condition Reason: To ensure the appropriate management of skeletal remains.</p>
<p>B. 8.</p>	<p>Aboriginal Objects – Unexpected Findings</p> <p>While site work is being carried out, if unexpected Aboriginal objects or bones are found, you must:</p> <ul style="list-style-type: none"> a) Not further disturb or move these objects or bones. b) Immediately cease all work at the particular location. c) In the case of suspected human remains, notify NSW Police. d) Notify the Heritage NSW Environment Line on 131 555 and the La Perouse Land Council (LALC) on (02) 9311 4282 as soon as practicable and provide available details of the objects or remains and their location. e) Notify the person who is the authority for the protection of Aboriginal objects under the National Parks and Wildlife Act 1974, section 85. f) Not recommence any work at the particular location unless authorised in writing by the police (in the case of human remains) and the person who is the authority for the protection of Aboriginal objects under the National Parks and Wildlife Act 1974, section 85. Additional assessment and approval under the National Parks and Wildlife Act 1974 may be required prior to works continuing in the affected area(s) based on the nature of the discovery. <p>Notes:</p> <ul style="list-style-type: none"> • The Definition of Aboriginal object, as per the National Parks & Wildlife Act 1974, is any deposit, object or other material evidence (not being a handicraft made for sale) relating to the Aboriginal habitation of an area of New South Wales, being habitation before or concurrent with (or both) the occupation of that area by persons of non-Aboriginal extraction, and includes Aboriginal remains. <p>Condition Reason: To protect Aboriginal objects</p>

B. 9.	Aboriginal Heritage – Induction																							
	Prior to any site works, all construction staff and contractors must be made aware of their statutory obligations for Aboriginal heritage under the National Parks and Wildlife Act 1974. This must be implemented as a heritage induction programme provided by a heritage consultant with Aboriginal heritage expertise.																							
	Condition Reason: To protect Aboriginal heritage.																							
B. 10.	Aboriginal Heritage Due Diligence Responsibilities																							
	While site work is being carried out, nothing in this approval allows to cause harm to an Aboriginal object as defined in the National Parks & Wildlife Act 1974. Under the National Parks & Wildlife Act 1974, it is an offence to harm Aboriginal ‘objects’ (consisting of any material evidence of the Aboriginal occupation of NSW) without a valid Aboriginal Heritage Impact Permit under Section 90 of the Act. This applies whether the harm occurs either knowingly [s86(1)] or unknowingly [s86(2)].																							
	It is a defence to the strict liability offence of harm to an Aboriginal object under s86(2) if a process of Due Diligence was followed which reasonably determined that the proposed activity would not harm an Aboriginal object.																							
	Condition Reason: To protect Aboriginal heritage.																							
B. 11.	Payment of Security and Fees																							
	Prior to any site works, the following security and fees must be paid in full:																							
	<table border="1"> <thead> <tr> <th>Description</th> <th>Amount</th> <th>Indexed</th> <th>Council Fee Code</th> </tr> </thead> <tbody> <tr> <td colspan="4">SECURITY under section 4.17(6) of the <i>Environmental Planning and Assessment Act 1979</i></td> </tr> <tr> <td>Property Damage Security Deposit -making good any damage caused to any property of the Council</td> <td>\$174,375.00</td> <td>No</td> <td>T115</td> </tr> <tr> <td>Security Deposit Administration Fee</td> <td>\$225.00</td> <td>No</td> <td>T16</td> </tr> <tr> <td>TOTAL SECURITY AND FEES</td> <td>\$174,600.00</td> <td></td> <td></td> </tr> </tbody> </table>				Description	Amount	Indexed	Council Fee Code	SECURITY under section 4.17(6) of the <i>Environmental Planning and Assessment Act 1979</i>				Property Damage Security Deposit -making good any damage caused to any property of the Council	\$174,375.00	No	T115	Security Deposit Administration Fee	\$225.00	No	T16	TOTAL SECURITY AND FEES	\$174,600.00		
Description	Amount	Indexed	Council Fee Code																					
SECURITY under section 4.17(6) of the <i>Environmental Planning and Assessment Act 1979</i>																								
Property Damage Security Deposit -making good any damage caused to any property of the Council	\$174,375.00	No	T115																					
Security Deposit Administration Fee	\$225.00	No	T16																					
TOTAL SECURITY AND FEES	\$174,600.00																							
	<p>How must the payments be made? Payments must be made by:</p> <ul style="list-style-type: none"> • cash deposit with Council, • credit card payment with Council, or • bank cheque made payable to Woollahra Municipal Council. <p>The payment of a security may be made by a bank guarantee where:</p> <ul style="list-style-type: none"> • the guarantee is by an Australian bank for the amount of the total outstanding contribution, • the bank unconditionally agrees to pay the guaranteed sum to the Council on written request by Council on completion of the development or no earlier than 12 months from the provision of the guarantee whichever occurs first [NOTE: a time limited bank guarantee or a bank guarantee with an expiry date is not acceptable], 																							

	<ul style="list-style-type: none"> • the bank agrees to pay the guaranteed sum without reference to the Applicant or landowner or other person who provided the guarantee and without regard to any dispute, controversy, issue or other matter relating to the development consent or the carrying out of development in accordance with the development consent, • the bank guarantee is lodged with the Council prior to any site works being undertaken, and • the bank’s obligations are discharged when payment to the Council is made in accordance with the guarantee or when Council notifies the bank in writing that the guarantee is no longer required. <p>Notes:</p> <ul style="list-style-type: none"> • An application must be made to Council by the person who paid the security for release of the securities held under section 4.17 of the Act. • The securities will not be released until the Occupation Certificate has been lodged with Council, Council has inspected the site and Council is satisfied that the public works have been carried out to Council’s requirements. Council may use part or all of the security to complete the works to its satisfaction if the works do not meet Council’s requirements. • Council will only release the security upon being satisfied that all damage or all works, the purpose for which the security has been held have been remedied or completed to Council’s satisfaction as the case may be. • Council may retain a portion of the security to remedy any defects in any such public work that arise within 6 months after the work is completed. • Upon completion of each section of road, drainage and landscape work to Council’s satisfaction, 90% of the bond monies held by Council for these works will be released upon application. 10% may be retained by Council for a further 6 month period and may be used by Council to repair or rectify any defects or temporary works during the 6 month period. • The Refund of Security Bond Application form can be downloaded from www.woollahra.nsw.gov.au <p>Condition Reason: To ensure any relevant security and fees are paid.</p>
<p>B. 12.</p>	<p>Dilapidation Reports for Existing Buildings</p> <p>Before any site work commences, dilapidation surveys and dilapidation reports must be conducted and prepared by a professional structural engineer for all buildings and/or structures that are located within the likely “zone of influence” of any excavation, dewatering and/or construction induced vibration as determined applicable by the structural engineer.</p> <p>These properties must include (but is not limited to):</p> <ol style="list-style-type: none"> a) 616 Old South Head Road, Rose Bay b) 624 Old South Head Road, Rose Bay <p>Where access is not granted to any adjoining properties to prepare the dilapidation report, the report must be based on a survey of what can be observed externally and it must be demonstrated, in writing, to the satisfaction of the Principal Certifier, that all reasonable steps were taken to obtain access.</p> <p>The completed dilapidation reports must be submitted to the Principal Certifier for approval, and an approved copy of the reports must be submitted to Council with the Notice of Commencement prior to the commencement of any development work.</p> <p>No less than two (2) days before any site work commences, neighbouring building owner(s) must be provided with a copy of the dilapidation report for their property(ies).</p>

	<p>Notes:</p> <ul style="list-style-type: none"> • The dilapidation report will be made available to affected property owners on request and may be used by them in the event of a dispute relating to damage allegedly caused by the carrying out of the development. • This condition cannot prevent neighbouring buildings being damaged by the carrying out of the development. • Council will not be held responsible for any damage which may be caused to adjoining buildings as a consequence of the development being carried out. • Council will not become directly involved in disputes between the developer, its contractors and the owners of neighbouring buildings. <p>Condition Reason: To establish and document the structural condition of adjoining properties for comparison as site work progresses and is completed and ensure neighbours and Council are provided with the dilapidation report.</p>
<p>B. 13.</p>	<p>Dilapidation Reports for Public Infrastructure</p> <p>Before any site work commences, to clarify the existing state of public infrastructure prior to the commencement of the development (including prior to any demolition), a dilapidation report, prepared by a chartered professional engineer, on Council's infrastructure within and near the development site must be prepared.</p> <p>The dilapidation report must be submitted to Council prior to the commencement of any site work and include:</p> <ol style="list-style-type: none"> a) photographs showing any existing damage to the road pavement fronting the site, b) photographs showing any existing damage to the kerb and gutter fronting the site, c) photographs showing any existing damage to the footway including footpath pavement fronting the site, d) photographs showing any existing damage to retaining walls within the footway or road, e) closed circuit television/video inspection (in DVD format) and report of the public stormwater drainage system traversing/adjoining the site, and f) the full name and signature of the Chartered Professional Engineer. <p>The report is to be supplied in both paper copy and electronic format in PDF. Photographs are to be in colour, digital, and date stamped.</p> <p>The dilapidation report must specify (with supporting photographic/DVD evidence) the exact location and extent of any damaged or defective public infrastructure prior to the commencement of any site work. If the required report is not submitted, Council will assume there was no damage to any infrastructure in the immediate vicinity of the site prior to the commencement of any site work under this consent.</p> <p>Notes:</p> <ul style="list-style-type: none"> • If a dilapidation report is not submitted as required by this condition, and damage is occasioned to public assets, which adjoin the site, Council will deduct from security any costs associated with remedying, repairing or replacing damaged public infrastructure. • Nothing in this condition prevents Council making any claim against security held for this purpose. <p>Condition Reason: To establish and document the structural condition of public land for comparison as site work progresses and is completed and ensure Council is provided with the dilapidation report.</p>

B. 14.	<p>Adjoining Buildings Founded on Loose Foundation Materials</p> <p>Before any site work commences, a professional engineer must determine the possibility of any adjoining buildings founded on loose foundation materials being affected by piling, piers or excavation. The professional engineer (geotechnical consultant) must assess the requirements for underpinning any adjoining or adjacent buildings founded on such soil on a case by case basis, and any reasonable direction of the professional engineer must be complied with.</p> <p>Notes:</p> <ul style="list-style-type: none">• A failure to adequately assess and seek professional engineering (geotechnical) advice to ensure that appropriate underpinning and support to adjoining land is maintained prior to commencement may result in damage to adjoining land and buildings.• The person with the benefit of this consent is likely to be held responsible for any damages arising from the removal of any support to supported land as defined by section 177 of the Conveyancing Act 1919. <p>Condition Reason: To ensure professional engineering advice is obtained to confirm that appropriate underpinning and support to adjoining land is maintained.</p>
B. 15.	<p>Construction Management Plan</p> <p>Before any site work commences, and as a result of the site constraints, limited space and access, a Construction Management Plan (CMP) is to be submitted to Council for approval. Also, due to lack of on-street parking a Work Zone may be required during construction.</p> <p>An application for the CMP must be submitted for approval, and all associated application fees must be paid.</p> <p>The CMP must be submitted as a self-contained document that outlines the nature of the construction project and as applicable, include the following information:</p> <ol style="list-style-type: none">a) Detail the scope of the works to be completed including details of the various stages, e.g. demolition, excavation, construction etc. and the duration of each stage.b) Identify local traffic routes to be used by construction vehicles.c) Identify ways to manage construction works to address impacts on local traffic routes.d) Identify other developments that may be occurring in the area and identify ways to minimise the cumulative traffic impact of these developments. Should other developments be occurring in close proximity (500m or in the same street) to the subject site, the developer/builder is to liaise fortnightly with the other developers/builders undertaking work in the area in order to minimise the cumulative traffic and parking impacts of the developments.e) Detail how construction workers will travel to and from the site and parking arrangements for those that drive.f) Identify any proposed road closures, temporary traffic routes, loss of pedestrian or cyclist access, or reversing manoeuvres onto a public road, and provide Traffic Control Plans (TCPs) prepared by an accredited RMS Red or Orange card holder to manage these temporary changes.g) Detail the size (including dimensions), numbers and frequency of arrival of the construction vehicles that will service the site for each stage of works.h) Provide for the standing of vehicles during construction.

	<p>i) If construction vehicles are to be accommodated on the site, provide a scaled drawing showing where these vehicles will stand and the vehicle swept path to show that these vehicles can access and egress the site in a forward direction (including dimensions and all adjacent traffic control devices, such as parking restrictions, pedestrian facilities, kerb extensions, etc.).</p> <p>j) If trucks are to be accommodated on Council property, provide a scaled drawing showing the location of any proposed Works Zone (including dimensions and all adjacent traffic control devices, such as parking restrictions, pedestrian facilities, kerb extensions, etc.).</p> <p>k) Show the location of any site sheds and any anticipated use of cranes and concrete pumps and identify the relevant permits that will be required.</p> <p>l) If a crane/s are to be accommodated on site, detail how the crane/s will be erected and removed, including the location, number and size of vehicles involved in the erection/removal of the crane/s, the duration of the operation and the proposed day and times, any full or partial road closures required to erect or remove the crane/s and appropriate Traffic Control Plans (TCPs) prepared by an approved RMS Red or Orange Card holder.</p> <p>m) Make provision for all materials, plant, etc. to be stored within the development site at all times during construction.</p> <p>n) State that any oversized vehicles proposed to operate on Council property (including Council approved Works Zones) will attain a Permit to Stand Plant on each occasion (Note: oversized vehicles are vehicles longer than 7.5m or heavier than 4.5T.)</p> <p>o) Show the location of any proposed excavation and estimated volumes.</p> <p>p) When demolition, excavation and construction works are to be undertaken on school days, all vehicular movements associated with this work must only be undertaken between the hours of 9.30am and 2.30pm, in order to minimise disruption to the traffic network during school pick up and drop off times.</p> <p>q) Show the location of all Tree Protection (Exclusion) zones (Note: storage of building materials or access through Reserve will not be permitted without prior approval by Council).</p> <p>Notes:</p> <ul style="list-style-type: none"> • A minimum of eight weeks will be required for assessment. Site work must not commence until the Construction Management Plan is approved. • Failure to comply with this condition may result in fines and proceedings to stop work. • Council and NSW Police approval is required prior to a partial or full temporary road closure. If you are seeking a partial or full temporary road closure you must comply with the relevant conditions of this consent and you must also gain the approval of the Eastern Suburbs Police Area Command. • If you partial or full close a road without compliance with Council and NSW Police requirements Council Rangers or the Police can issue Penalty Infringement Notices or Court Attendance Notices leading to prosecution. • Traffic Supervisors at the Eastern Suburbs Police Area Command can be contacted on eastsubtraffic@police.nsw.gov <p>Condition Reason: To facilitate the efficient operation of construction projects, minimise traffic disruption, and protect the public, and the surrounding environment, during site works and construction.</p>
<p>B. 16.</p>	<p>Works (Construction) Zone – Approval and Implementation</p> <p>If the Construction Management Plan relies upon a Works Zone, before any site work commences, a Works Zone application must be made.</p> <p>If the works zone is approved, all fees for the Works Zone must be paid before it can be installed.</p>

All Works Zone signs must have been erected by Council to permit enforcement of the Works Zone by Council's Rangers and NSW Police before commencement of any site work. Signs are not erected until full payment of Works Zone fees is made.


Notes:

- A minimum of four to six weeks must be allowed (for routine applications) from the date of making an application to the Traffic Committee (Woollahra Local Traffic Committee) constituted under clause 20 of the Transport Administration (General) Regulation 2018 to exercise those functions delegated by Transport for New South Wales under section 31(3) of the Transport Administration Act 1988.
- The enforcement of the Works Zone is at the discretion of Council's Rangers and the NSW Police Service. Any breach of the Works Zone must be reported to either Council or the NSW Police Service.

Condition Reason: To facilitate the efficient operation of construction projects and to minimise traffic disruption.


B. 17. Security Fencing, Hoarding (including 'Creative Hoardings') and Overhead Protection

Before any site work commences, security fencing must be provided around the perimeter of the development site, including any additional precautionary measures taken to prevent unauthorised entry to the site at all times during the demolition, excavation and construction period. Security fencing must be the equivalent 1.8m high chain wire as specified in AS 1725.



Type A Hoarding

Where the development site adjoins a public thoroughfare, the common boundary between them must be fenced for its full length with a hoarding, unless the least horizontal distance between the common boundary and the nearest parts of the structure is greater than twice the height of the structure. The hoarding must be constructed of solid materials (chain wire or the like is not acceptable) to a height of not less than 1.8m adjacent to the thoroughfare.




Type B Hoarding

Where a development site adjoins a public thoroughfare with a footpath alongside the common boundary then, in addition to the hoarding required above, the footpath must be covered by an overhead protective structure and the facing facade protected by heavy-duty scaffolding, unless either:

- a) the vertical height above footpath level of the structure being demolished is less than 4.0m; or
- b) the least horizontal distance between footpath and the nearest part of the structure is greater than half the height of the structure.

The overhead structure must consist of a horizontal platform of solid construction and vertical supports, and the platform must:

- a) extend from the common boundary to 200mm from the edge of the carriageway for the full length of the boundary,
- b) have a clear height above the footpath of not less than 2.1m,
- c) terminate 200mm from the edge of the carriageway (clearance to be left to prevent impact from passing vehicles) with a continuous solid upstand projecting not less than 0.5m above the platform surface, and
- d) together with its supports, be designed for a uniformly distributed live load of not less than 7 kPa.



The overhead protective structures must be installed and maintained in accordance with the NSW "Code of Practice - Overhead Protective Structures 1995". This is code available at www.safework.nsw.gov.au/__data/assets/pdf_file/0008/52883/Overhead-protective-structures-Code-of-practice.pdf

All Hoardings

Security fencing, hoarding and overhead protective structure must not obstruct access to utilities services including but not limited to man holes, pits, stop valves, fire hydrants or the like.

Hoardings on Public Land including 'Creative Hoardings'

All fees associated with the application and occupation and use of the road (footway) for required hoarding or overhead protection must be paid in full.

A creative hoarding (i.e. an approved artwork or historic image affixed to the hoarding) is required if the hoarding meets the criteria in Council's Creative Hoardings Policy (adopted March 2020). The cost of printing and affixing the creative hoarding is the responsibility of the person with the benefit of this consent. The Creative Hoardings Policy can be downloaded from Council's website www.woollahra.nsw.gov.au

Notes:

- A minimum of two (2) weeks from the date of making a hoarding application to determination must be allowed. Any approval for a hoarding or overhead protection under the Roads Act 1993 will be subject to its own conditions and fees.
- Council seeks to increase public art in the public domain by requiring artwork or historic images on hoardings located on public land. Under the Creative Hoardings Policy an application for a hoarding proposed on public land will require an approved artwork or historic image affixed to the hoarding if the hoarding meets the criteria in section 3 of the Policy:
 - A. Hoardings proposed on land zoned E1 Local Centre, or MU1 Mixed Use, or SP2 Infrastructure under Woollahra Local Environmental Plan 2014 AND erected for 8 weeks or more
OR
 - B. Hoardings proposed on land located along a State classified road (regardless of the zone) AND erected for 8 weeks or more
OR
 - C. Hoardings proposed in any other location than that referred to in A. and B. above AND erected for 12 weeks or more, except where:

	<ol style="list-style-type: none"> 1. the capital investment value of the work to which the hoarding relates is less than \$1 million, or 2. the land is zoned R2 Low Density Residential, or 3. the land is zoned R3 Medium Density Residential and the hoarding is located in a lane or street that does not have through traffic (e.g. a cul-de-sac or no through road). <ul style="list-style-type: none"> • Artwork and historic images for the hoardings are assessed and approved in accordance with the Creative Hoardings Policy. Details of the artwork or images proposed to be affixed to the hoardings must be submitted with Council's form "Application for a permit to use a footpath for the erection of a hoarding/scaffolding". The Creative Hoardings Policy can be downloaded from www.woollahra.nsw.gov.au <p>Condition Reason: To ensure public safety.</p>
<p>B. 18.</p>	<p>Site Signs</p> <p>Before any site work commences, the sign/s required by clauses 70 of the Regulation and 75 of the Development Certification and Fire Safety Regulation must be erected and maintained at all times.</p> <p>Clause 70 of the Regulation provides:</p> <p>Erection of signs</p> <ul style="list-style-type: none"> • For the purposes of section 4.17(11) of the Act, the requirements of subclauses (2) and (3) are prescribed as conditions of a development consent for development that involves any building work, subdivision work or demolition work. • A sign must be erected in a prominent position on any site on which building work, subdivision work or demolition work is being carried out: <ol style="list-style-type: none"> a) showing the name, address and telephone number of the principal certifier for the work, and b) showing the name of the principal contractor (if any) for any building work and a telephone number on which that person may be contacted outside working hours, and c) stating that unauthorised entry to the work site is prohibited. • Any such sign is to be maintained while the building work, subdivision work or demolition work is being carried out, but must be removed when the work has been completed. • This clause does not apply in relation to building work, subdivision work or demolition work that is carried out inside an existing building that does not affect the external walls of the building. • This clause does not apply in relation to Crown building work that is certified, in accordance with section 6.28 of the Act, to comply with the Building Code of Australia. <p>Clause 75 of the Development Certification and Fire Safety Regulation provides:</p> <p>Signs on development sites</p> <p>If there is a person who is the Principal Certifier or the Principal Contractor for any building work, subdivision work or demolition work authorised to be carried out on a site by a development consent or complying development certificate:</p> <ul style="list-style-type: none"> • Each such person MUST ensure that a rigid and durable sign showing the person's identifying particulars so that they can be read easily by anyone in any public road or other public place adjacent to the site is erected in a prominent position on the site before the commencement of work, and is maintained on the site at all times while this clause applies until the work has been carried out.

	<p>Notes:</p> <ul style="list-style-type: none"> • Clause 75 of the Development Certification and Fire Safety Regulations imposes a maximum penalty of 55 penalty units if these requirements are not complied with. • If Council is appointed as the Principal Certifier it will provide the sign to the Principal Contractor or Owner-builder who must ensure that the sign is erected and maintained as required by clause 70 of the Regulation and clause 75 of the Development Certification and Fire Safety Regulation. <p>Condition Reason: To ensure that contact details for the principal certifier and principal contractor are provided on a sign at the development site.</p>
<p>B. 19.</p>	<p>Toilet Facilities</p> <p>Before any site work commences, toilet facilities are to be provided, at or in the vicinity of the work site on which work involved in the erection or demolition of a building is being carried out, at the rate of one toilet for every 20 persons or part of 20 persons employed at the site.</p> <p>Each toilet provided:</p> <ol style="list-style-type: none"> must be a standard flushing toilet, and must be connected to a public sewer, or if connection to a public sewer is not practicable, to an accredited sewage management facility approved by the Council, or if connection to a public sewer or an accredited sewage management facility is not practicable, to some other sewage management facility approved by the Council. <p>The provision of toilet facilities in accordance with this condition must be completed before any other work is commenced.</p> <p>Notes:</p> <ul style="list-style-type: none"> • In this condition 'sewage management facility' and 'public sewer' are as defined by clause 25 of the Local Government (Approvals) Regulation 1999. • This condition does not set aside the requirement to comply with SafeWork NSW requirements. <p>Condition Reason: To ensure toilet facilities are provided for workers at the work site.</p>
<p>B. 20.</p>	<p>Establishment of Boundary Location, Building Location and Datum</p> <p>Before any site work commences, a surveyor registered under the Surveying and Spatial Information Act 2002 must:</p> <ol style="list-style-type: none"> set out the boundaries of the site by permanent marks (including permanent recovery points), set out the location and level of foundation excavations, footings, walls and slabs by permanent marks, pegs or profiles relative to the boundaries of the land and relative to Australian Height Datum (AHD) in compliance with the approved plans, establish a permanent datum point (bench mark) within the boundaries of the site relative to AHD, and provide a copy of a survey report, prepared by the registered surveyor, detailing the title boundaries, pegs/profiles, recovery points and bench mark locations as established under this condition to the Principal Certifier.

	<p>Notes:</p> <ul style="list-style-type: none"> Where there is any discrepancy between the approved development consent and the Construction Certificate, especially in relation to the height, location or external configuration of the building (but not limited to these issues) the site works must not proceed until the variations as shown are consistent with the consent. Failure to do so may result in a breach of development consent. On larger developments, or where boundary redefinition is required, the placement of new State Survey Marks as permanent marks must be considered by the registered surveyor. <p>Condition Reason: To ensure that the boundary locations, building location, and a datum point is established by a surveyor.</p>
<p>B. 21.</p>	<p>Compliance with Australian Standard for Demolition</p> <p>While site work is being carried out, the demolition of buildings and structures must comply with Australian Standard AS 2601—2001: The Demolition of Structures.</p> <p>Condition Reason To control the risks of demolition work.</p>
<p>B. 22.</p>	<p>Construction Management Plan Arborist Review</p> <p>Prior to any site works, the Construction Management Plan must be reviewed and certified by the Project Arborist confirming that appropriate tree protection measures are implemented. The Construction Management Plan must be prepared in accordance with all tree protection measures specified within this consent.</p> <p>The plan must address:</p> <ol style="list-style-type: none"> Drawings and method statement showing details and the location of hoarding and scaffold and any pruning required to accommodate the hoarding and scaffolding; The movement and positioning of heavy machinery, lifting cranes, pier drilling gantry etc.; Site construction access, temporary crossings and movement corridors on the site defined; Contractors car parking; Phasing of construction works; The space needed for all foundation excavations and construction works; All changes in ground level; Space for site sheds and other temporary structures such as toilets; Space for sorting and storing materials (short or long term), spoil and fuel and the mixing of cement and concrete; and The effects of slope on the movement of potentially harmful liquid spillages towards or into tree protection areas. <p>Condition Reason To ensure the Construction Management Plan incorporates measures for the protection of existing trees.</p>
<p>B. 23.</p>	<p>Arborists Documentation and Compliance Checklist</p> <p>Prior to any site works, the project arborist must provide written certification that all tree protection measures and construction techniques relevant to this consent are implemented. Documentation for each site visit must include:</p> <ul style="list-style-type: none"> A record of the condition of trees to be retained prior to and throughout development.

- Recommended actions to improve site conditions and rectification of non-compliance.
- Recommendations for future works which may impact the trees.

All compliance certification documents must be kept on site.

As a minimum the following intervals of site inspections must be made:

Stage of arboricultural inspection and supervision	Compliance documentation and photos must include
Prior to any site works	<ul style="list-style-type: none"> • Project Arborist to hold pre construction site meeting with the principal contractor to discuss methods and importance of tree protection measures and resolve any issues in relation to feasibility of tree protection requirements that may arise. Project Arborist to mark all trees approved for removal under DA consent. • The project arborist must install or supervise the installation of tree protection fencing, trunk protection, ground protection and traffic height control beam.

Inspections and compliance documentation must be made by an arborist with AQF Level 5 qualifications.

Additional site visits must be made when required by the site arborist and/or site foreman for ongoing monitoring/supervisory work.

Condition Reason To ensure that written certification that all tree protection measures and construction techniques relevant to this consent have been implemented.

B. 24. Permissible work within Tree Protection Zones

Prior to any site works, the following works are permissible within the Tree Protection Zone:

Council Ref No	Species	Approved works
6	<i>Cupaniopsis anacardioides</i> (Tuckeroo)	Boundary fence, stormwater and landscape works
7	<i>Araucaria heterophylla</i> (Norfolk Island pine)	Landscape works
8	<i>Syzygium</i> sp. (Lillypilly)	Boundary fence, stormwater and landscape works
9	<i>Brachychiton acerifolius</i> (Illawarra Flame tree)	Boundary fence and landscape works
11	<i>Syzygium</i> sp. (Lillypilly)	New retaining wall, paving and landscape works
13	<i>Cupressocyparis leylandii</i> (Leyland Cypress)	Landscape works

The project arborist must provide written certification of compliance to the Principal Certifier with the above condition.

Condition Reason To establish the works which are permissible within the Tree Protection Zones.

REMEDIATION WORK

C. ON COMPLETION OF REMEDIATION WORK

Nil

BUILDING WORK

D. BEFORE ISSUE OF A CONSTRUCTION CERTIFICATE

D. 1.	Modification of Details of the Development (section 4.17(1)(g) of the Act
	<p>Before the issue of any construction certificate, the approved plans and the construction certificate plans and specification, required to be submitted to the Principal Certifier under clause 7 of the Development Certification and Fire Safety Regulations, must detail the following amendments:</p> <p>a) In order to maintain visual privacy to the neighbouring dwellings to the north and south of the subject site, the following habitable room awning windows are required to be fitted with translucent glazing to a height of 1.5m above the finished floor level of the room and fitted with a winder mechanism to control the maximum angle of the window opening:</p> <ul style="list-style-type: none">• 1-W01• 1-W02• 1-W03• 1-W04• 1-W11• 1-W14• 2-W01• 2-W02• 2-W03• 2-W04• 2-W11• 2-W14 <p>b) In order to maintain visual privacy to the neighbouring properties to the north, windows 1-W05 and 2-W05 are required to feature fixed external privacy screening that obscures sightlines towards the south-facing windows of the dwellings at No. 624 Old South Head Road, to a height of 1.5m above the finished floor level.</p> <p>c) An amended Landscape plan must be prepared showing:</p> <ul style="list-style-type: none">i) Existing crossovers to 618 & 620 Old South Head Road demolished and replaced with a continuous typical council verge with turf to allow for future street tree planting by Council.ii) Clarified final levels at rear within the TPZ of trees to be retained. The plans shall be consistent with the conditions of consent maintaining existing levels within a certain distance to minimise root damage. <p>Notes:</p> <ul style="list-style-type: none">• Clause 20 of the Development Certification and Fire Safety Regulations prohibits the issue of any construction certificate subject to this condition unless the Principal Certifier is satisfied that the condition has been complied with.• Clause 19 of the Development Certification and Fire Safety Regulations prohibits the issue of any construction certificate that is inconsistent with this consent.

	<p>Condition Reason: To require design changes and/or further information to be provided to address specific issues identified during the assessment under section 4.15 of the Act.</p>												
D. 2.	<p>Payment of Long Service Levy</p> <p>Before the issue of any construction certificate, the original receipt(s) for the payment of the following levy must be provided to the Principal Certifier:</p> <table border="1"> <thead> <tr> <th>Description</th> <th>Amount</th> <th>Indexed</th> <th>Council Fee Code</th> </tr> </thead> <tbody> <tr> <td colspan="4">LONG SERVICE LEVY under <i>Building and Construction Industry Long Service Payments Act 1986</i></td> </tr> <tr> <td> Long Service Levy www.longservice.nsw.gov.au/bci/levy/other-information/levy-calculator </td> <td>Contact LSL Corporation or use online calculator</td> <td>No</td> <td></td> </tr> </tbody> </table> <p>Building and Construction Industry Long Service Payment The long service levy under section 34 of the Building and Construction Industry Long Service Payment Act 1986, must be paid and proof of payment provided to the Principal Certifier prior to the issue of any construction certificate. The levy can be paid directly to the Long Service Corporation or to Council. Further information can be obtained from the Long Service Corporation website www.longservice.nsw.gov.au or the Long Service Corporation on 131 441.</p> <p>How must the payments be made? Payments must be made by:</p> <ul style="list-style-type: none"> • cash deposit with Council, • credit card payment with Council, or • bank cheque made payable to Woollahra Municipal Council. <p>Condition Reason: To ensure any relevant levy is paid.</p>	Description	Amount	Indexed	Council Fee Code	LONG SERVICE LEVY under <i>Building and Construction Industry Long Service Payments Act 1986</i>				Long Service Levy www.longservice.nsw.gov.au/bci/levy/other-information/levy-calculator	Contact LSL Corporation or use online calculator	No	
Description	Amount	Indexed	Council Fee Code										
LONG SERVICE LEVY under <i>Building and Construction Industry Long Service Payments Act 1986</i>													
Long Service Levy www.longservice.nsw.gov.au/bci/levy/other-information/levy-calculator	Contact LSL Corporation or use online calculator	No											
D. 3.	<p>BASIX Commitments</p> <p>Before the issue of any construction certificate, BASIX Certificate No. 1418155M_02 must be submitted to the Principal Certifier with any application for a construction certificate.</p> <p>All commitments in the BASIX Certificate must be shown on the construction certificate plans and specifications prior to the issue of any construction certificate.</p> <p>Notes:</p> <ul style="list-style-type: none"> • Where there is any proposed change in the BASIX commitments the Applicant must submit a new BASIX Certificate to the Principal Certifier and Council. If any proposed change in the BASIX commitments are inconsistent with development consent (see: clauses 19 and 20 of the Development Certification and Fire Safety Regulation) the Applicant will be required to submit an amended development application to Council under section 4.55 of the Act. • Clause 19(1)(a) of the Development Certification and Fire Safety Regulation 2021 provides: a certifier must not issue a construction certificate for building work unless: the relevant building work plans and specifications include the matters required by a relevant BASIX certificate, if any. <p>Condition Reason: To ensure all commitments in the BASIX Certificate are incorporated into the development.</p>												

<p>D. 4.</p>	<p>State Environmental Planning Policy (Housing) 2021 – Design Verification Statement</p> <p>Before the issue of any construction certificate, as required under clause 15 of the Development Certification and Fire Safety Regulation, a statement by a qualified designer verifying that the relevant building work plans and specifications achieve or improve the design quality of the development for which development consent was granted, having regard to the design quality principle in State Environmental Planning Policy (Housing) 2021: Chapter 4 —Design of Residential Apartment Development must be provided to the Principal Certifier.</p> <p>Notes:</p> <ul style="list-style-type: none"> • Although a Principal Certifier may under clause 73(2)(b) of the Development Certification and Fire Safety Regulation be satisfied to any matter that relates to the external finish of a building the specific provisions of clause 15 of the Development Certification and Fire Safety Regulation overrides the Principal Certifier’s powers under clause 73(2)(b). No Principal Certifier can set aside this requirement. • Qualified designer means a person registered as an architect in accordance with the Architects Act 2003. • There are several methods of verifying the status of an individual or corporation or firm offering architectural services. Ask the individual for their four digit NSW Architects Registration Number, ask a corporation or firm for the name and registration number of their “nominated architect”, check to see whether an individual is listed on the NSW Register of Architects or the corporation or firm is listed on the list of architect corporations and firms on the Board’s website www.architects.nsw.gov.au or call the NSW Architects Registration Board on 9241 4033 to check the status of an individual or corporation or firm. <p>Condition Reason: To ensure a design verification statement from a qualified designer is provided for the development.</p>
<p>D. 5.</p>	<p>Road and Public Domain Works</p> <p>Before the issue of any construction certificate, a separate application under Section 138 of the Roads Act 1993 is to be made to, and be approved by Council, for the following infrastructure works. The infrastructure works must be carried out at the applicant's expense:</p> <ol style="list-style-type: none"> a) The removal of all redundant vehicular crossings including layback and gutter and reinstatement into Transport for NSW (TfNSW)’s standard kerb and gutter, Council’s standard footpath and nature strip in accordance with Council’s Specification for Roadworks, Drainage and Miscellaneous Works and to the satisfaction of Council’s Assets Engineers, b) The construction of a new 6.685 metres wide vehicular crossing including the removal of the existing gutter to Council’s and TfNSW’s Specification. The layback and gutter must be designed in accordance with TfNSW’s specification. The vehicular crossing must be designed in accordance with Council’s Crossing Specification, standard driveway drawing RF2_D and to the satisfaction of Council’s Assets Engineers. The new vehicular crossing must be constructed at a right angle to the street kerb in plain concrete where the edge of the new crossing must be located a minimum distance of 1m from the existing power pole. This distance is to be measured between the outer diameter of the power pole. Design longitudinal surface profiles along each side/edge for the proposed driveway, starting from the road centreline to the parking slab must be submitted for assessment.

- c) The installation of stormwater outlet pipe across the nature strip must be made by using 150mm x 75mm galvanised rectangular hollow section (RHS) in accordance with Council's Specification for Roadworks, Drainage and Miscellaneous Works and to the satisfaction of Council's Assets Engineers.

Note: All below ground structures are to be fully tanked such that subsoil drainage/seepage water is NOT discharged to the kerb and gutter to comply with Chapter E2.2.5 of Council's DCP,

- d) In light of paragraphs (a), (b) and (c) above, approval must be sought from TfNSW for the above infrastructure works. A copy of the approved civil drawings from TfNSW must be submitted with this application.

Note: Transport for NSW may have additional design requirements and/or specifications regarding these infrastructure works, and these may supersede Council's specifications,

- e) The reconstruction of the existing 1.8 metres wide concrete footpath for the full frontage of the site in accordance with Council's Specification, Council's standard drawing RF3 and to the satisfaction of Council's Assets Engineers. A maximum cross-fall of 3% must be provided for the footpath, graded from the property boundary towards the top of kerb. A design longitudinal surface profile (scale 1:100) and cross sections (scale 1:50) at every 5 metres interval must be submitted for assessment,

- f) The reinstatement of all damaged kerb and gutter and road pavement to Council's Specification for Roadworks, Drainage and Miscellaneous Works and to the satisfaction of Council's Assets Engineers. Note: damaged kerb and gutter and road pavement on Old South Head Road must be reinstated to TfNSW's Specification and to the satisfaction of TfNSW,

- g) Where a grass verge exists, the balance of the area between the footpath and the kerb over the full frontage of the proposed development must be turfed. The grass verge must be constructed to contain a uniform minimum 75mm of friable growing medium and have a total cover of Couch turf.

Before the issue of any construction certificate, the principal certifier must be provided with the original receipt(s) for the payment of all of the following security bonds and fees:

Description	Amount	Indexed	Council Fee Code
SECURITY under section 4.17(6) of the <i>Environmental Planning and Assessment Act 1979</i>			
Infrastructure Works Bond - completing any public work required in connection with the consent.	\$26,235	No	T113
Infrastructure Works Bond – remedying any defects in any public work that arise within 6 months after the work is completed	Nil	No	T113

INSPECTION FEES under section 608 of the <i>Local Government Act 1993</i>			
Public Road and Footpath Infrastructure Inspection Fee	\$645	No	T45
TOTAL SECURITY AND FEES	\$26,880		

How must the payments be made?

Payments must be made by:

- cash deposit with Council,
- credit card payment with Council, or
- bank cheque made payable to Woollahra Municipal Council.

The payment of a security may be made by a bank guarantee where:

- the guarantee is by an Australian bank for the amount of the total outstanding contribution,
- the bank unconditionally agrees to pay the guaranteed sum to the Council on written request by Council on completion of the development or no earlier than 12 months from the provision of the guarantee whichever occurs first [NOTE: a time limited bank guarantee or a bank guarantee with an expiry date is not acceptable],
- the bank agrees to pay the guaranteed sum without reference to the Applicant or landowner or other person who provided the guarantee and without regard to any dispute, controversy, issue or other matter relating to the development consent or the carrying out of development in accordance with the development consent,
- the bank guarantee is lodged with the Council prior to any site works being undertaken, and
- the bank’s obligations are discharged when payment to the Council is made in accordance with the guarantee or when Council notifies the bank in writing that the guarantee is no longer required.

Notes:

- **Road** has the same meaning as in the Roads Act 1993.
- Changes in levels may arise from the detailed design of buildings, road, footpath, driveway crossing grades and stormwater. Changes required under Roads Act 1993 approvals may necessitate design and levels changes under this consent. This may in turn require the Applicant to seek to amend this consent.
- Works or structures over, on or under public roads or footpaths are subject to sections 138, 139 and 218 of the Roads Act 1993 and specifically:
 - Construction of driveways and/or new or alterations to footpath paving
 - Alteration and/or extension to Council drainage infrastructure
 - Alteration and/or addition of retaining walls
 - Pumping of water to Council’s below ground stormwater system
 - Installation of soil/rock anchors under the roadway
 - Installation of Stormwater outlet pipes across the nature strip
- An “Application to Carry Out Works in a Public Road” form must be completed and lodged, with the application fee, at Council’s Customer Services. Detailed plans and specifications of all works (including but not limited to structures, road works, driveway crossings, footpaths and stormwater drainage etc) within existing roads, must be attached, submitted to and approved by Council under section 138 of the Roads Act 1993, before the issue of any construction certificate.
- Detailed engineering plans and specifications of the works required by this condition must accompany the application form. The plans must clearly show the following:
 - Engineering drawings (plan, sections and elevation views) and specifications of the footpath, driveways, kerb and gutter, new gully pit showing clearly the connection point of site outlet pipe(s). The connection drainage lines must be as direct as possible and generally run perpendicular to the kerb alignment.
 - Engineering drawings of the new drainage line to be constructed joining the new and existing drainage pits including services.

	<ul style="list-style-type: none"> • All driveways must include a design longitudinal surface profile for the proposed driveway for assessment. The driveway profile is to start from the road centreline and be along the worst case edge of the proposed driveway. Gradients and transitions must be in accordance with clause 2.5.3, 2.6 of AS 2890.1 – 2004, Part 1 – Off-street car parking. The driveway profile submitted to Council must be to (1:25) scale (for template checking purposes) and contain all relevant details: reduced levels, proposed grades and distances. • The existing footpath level and grade at the street alignment of the property must be maintained unless otherwise specified by Council. Your driveway levels are to comply with AS2890.1 and Council's Standard Drawings. There may be occasions where these requirements conflict with your development and you are required to carefully check the driveway/garage slab and footpath levels for any variations. • Any adjustments required from the garage slab and the street levels are to be carried out internally on private property • Drainage design works must comply with the Woollahra DCP 2015 Chapter E2 – Stormwater and Flood Risk Management. • Temporary ground anchors may be permitted, in accordance with Council's "Rock Anchor Policy". • Services: Prior to any excavation works, the location and depth of all public utility services (telephone, cable TV, electricity, gas, water, sewer, drainage, etc.) must be ascertained. The Applicant must be responsible for all public utility adjustment/relocation works, necessitated by the development work and as required by the various public utility authorities and/or their agents. • All public domain works must comply with the latest version of Council's "Specification for Roadworks, Drainage and Miscellaneous Works" unless expressly provided otherwise by these conditions. This specification and the application form can be downloaded from www.woollahra.nsw.gov.au. • When an application under the Roads Act is required, then four (4) weeks is to be allowed for assessment. • An application must be made to Council by the person who paid the security for release of the securities held under section 4.17 of the Act. • The securities will not be released until the Occupation Certificate has been lodged with Council, Council has inspected the site and Council is satisfied that the public works have been carried out to Council's requirements. Council may use part or all of the security to complete the works to its satisfaction if the works do not meet Council's requirements. • Council will only release the security upon being satisfied that all damage or all works, the purpose for which the security has been held have been remedied or completed to Council's satisfaction as the case may be. • When determining whether the works within public land are satisfactory, Council will consider the ownership, construction quality, maintenance, operations, and public utility of such item/s. • Upon completion of each section of road, drainage and landscape work to Council's satisfaction, 90% of the bond monies held by Council for these works will be released upon application. 10% may be retained by Council for a further 6 month period and may be used by Council to repair or rectify any defects or temporary works during the 6 month period.
	<p>Condition Reason: To ensure the design of the road, footpaths, driveway crossings and public stormwater drainage works are detailed and approved under section 138 of the Roads Act 1993 and to ensure the works are completed to Council's satisfaction.</p>
<p>D. 6.</p>	<p>Provision for Energy Supplies</p> <p>Before the issue of any construction certificate:</p> <ol style="list-style-type: none"> a) A survey is to be carried out of all utility services within and adjacent to the site. If necessary, this shall include relevant information from utility authorities and excavation, to determine the position and level of services. b) The applicant is to obtain written approval from Ausgrid for the relocation, adjustment or installation of new services, or existing services affected by, or required for the development.

- c) The applicant shall provide to the Principal Certifier a true copy of the plans developed by the applicant's Accredited Service Provider outlining the design and requirements for network modification and customer connection for the proposed development. The plans must have been reviewed and certified by Ausgrid to be deemed compliant of meeting this requirement.

Any required substation must be located within the boundaries of the site. Where an electricity substation is required, but no provision has been made to place it within the building and such substation has not been detailed upon the approved development consent plans an application under section 4.55 of the Act is required to be submitted to Council.

The design and location of any substation should have regard to the electrical substation provisions within the Woollahra Development Control Plan 2015, which require substations to be located and/or concealed so they are not visible from the street. The design and placement of electrical substations shall comply with Ausgrid's relevant Network Standards and will prioritise the placement of the substation at the front of the property.

Where an electrical pillar is required, the electrical designer must consider the impact of all existing and proposed work when preparing their connection or relocation design. Site specific conditions such as existing/proposed property boundaries, building setbacks, other street furniture, street trees and pedestrian pathways will all be taken into account when specifying the final location of the pillar. The design should be compliant with Ausgrid's Network Standards and satisfy Council's objective to maintain a safe and accessible public domain for pedestrians:

- a) The design and location of underground and aboveground utility infrastructure shall consider the finished streetscape and not adversely impact existing pedestrian footpath, or, where the only permissible location for aboveground infrastructure will impact the footpath, the applicant shall widen the footpath to meet minimum accessibility requirements.

The construction certificate plans and specifications, required to be submitted under clause 7 of the Development Certification and Fire Safety Regulation, must detail provisions to meet the requirements of Ausgrid.

Where an electricity pillar and/or substation is required, the construction certificate plans and specifications must provide:

- a) The substation shall be located or concealed so not visible from the street.
b) A setback not less than 3m from any side or rear site boundary (or fire source feature) and not within the areas required to be kept clear of obstructions to vehicle visibility under clause 3.2.4 of AS2890.1 (See: Figures 3.2 and 3.3).
c) That vegetation does not overhang or encroach within the substation site.
d) That the substation is installed outside of the mature growth root zone of any trees to be retained, or proposed to be planted, to prevent root damage to underground cables. A setback not less than the 10m from any NSW Fire Brigade booster connection as prescribed by clause 5.6.3(d)(iii) of AS 2419.1 or be separated from any booster connections by a construction with a fire resistance rating of not less than FRL 90/90/90 for a distance of not less than 2 m each side of and 3 m above the upper hose connections in the booster assembly under clause 5.6.3(c)(ii) of AS 2419.1, and
e) The Owner must dedicate to the appropriate energy authority, free of cost, an area of land adjoining the street alignment to enable a substation to be established, if required.

The size and location of the substation is to be in accordance with the requirements of the appropriate energy authority and Council. The opening of any access doors must not intrude onto the public road reserve.

Notes:


- If the substation is not located within the building its location, all screen walls or fire separating walls must have been approved by the grant of development consent or amended development consent prior to the issue of any construction certificate for those works. Documentary evidence of compliance, including correspondence from the energy authority is to be provided to the Principal Certifier prior to issue of the construction certificate. The Principal Certifier must be satisfied that the requirements of the energy authority have been met prior to issue of the construction certificate.
- Where it is proposed to shield any booster connection or any building from any electricity pillar and/or substation under clause 5.6.3(c)(ii) of AS 2419.1 or by fire resisting construction under the BCA respectively and this construction has not been detailed upon the approved development consent plans such works should be considered inconsistent with consent under clause 19 of the Development Certification and Fire Safety Regulation. The Applicant must lodge with Council details for any such construction under section 4.55 of the Act to allow assessment under section 4.15 of the Act.
- Electricity pillar and/or Substations must not be located within the minimum sight distance at driveway entrances under Australian Standard AS/NZS 2890 (Set) Parking Facilities Set whether such driveways service the site or any adjoining land.

Condition Reason: To ensure the adequate provision of energy supply, and to ensure that any proposed electricity substation or the like does not compromise the design quality of the development.


D. 7. Water and Waste Water - section 73 Developers Certificate and Upgrading of Existing System

Prior to the issue of any construction certificate, a Compliance Certificate must be obtained from Sydney Water under section 73 of the Sydney Water Act 1994. Sydney Water's assessment will determine the availability of water and sewer services, which may require extension, adjustment or connection to their mains.


The construction certificate plans and specifications, required to be submitted to the Principal Certifier under clause 7 of the Development Certification and Fire Safety Regulation, must detail the replacement of all private sewer pipes between all sanitary fixtures and Sydney Water's sewer main where they are not found by inspection to be sewer grade UPVC or copper with continuously welded joints.




Cracked pipes



Broken pipes




Damaged or low-lying gullies



Direct stormwater connections



Hidden or damaged maintenance holes



Hidden or damaged inspection points

	<p>Notes:</p> <ul style="list-style-type: none"> • Sydney Water will assess the development and if required will issue a ‘Notice of Requirements’ letter detailing all requirements that must be met. Applications can be made either directly to Sydney Water or through a Sydney Water accredited Water Servicing Coordinator (WSC). Please make early contact with Sydney Water or a WSC, since building of water/sewer extensions can be time consuming and may impact on other services and building, driveway or landscape design. • For more information go to www.sydneywater.com.au/section73 or call 1300 082 746 to learn more about applying through an authorised WSC or Sydney Water. • Where private sewer pipes are old, may leak or may be subject to root invasion (whether from existing or proposed private or public landscaping) that existing cast iron, concrete, earthenware or terracotta systems are replaced with new UPVC or copper continuously welded pipes between all sanitary fixtures and Sydney Waters sewer main as part of the development. Leaking sewer pipes are a potential source of water pollution, unsafe and unhealthy conditions which must be remedied in the public interest. <p>Condition Reason: To ensure that private sewer pipes are upgraded where required to prevent water pollution, and unsafe and unhealthy conditions.</p>
<p>D. 8.</p>	<p>Erosion and Sediment Control Plan – Submission and Approval</p> <p>Before the issue of any construction certificate, an erosion and sediment control plan, prepared by a suitably qualified person in accordance with the following documents, must be submitted to the Principal Certifier. The erosion and sediment control plan must comply with:</p> <ol style="list-style-type: none"> a) “Do it Right On Site, Soil and Water Management for the Construction Industry” and the accompanying factsheets published by the Southern Sydney Regional Organisation of Councils; and b) “Managing Urban Stormwater - Soils and Construction” 2004 published by the NSW Government (The Blue Book). <p>Where there is any conflict The Blue Book takes precedence.</p> <p>The Principal Certifier must be satisfied that the erosion and sediment control plan complies with the publications above prior to issuing any construction certificate.</p> <p>Notes:</p> <ul style="list-style-type: none"> • The International Erosion Control Association – Australasia www.austieca.com.au lists consultant experts who can assist in ensuring compliance with this condition. Where erosion and sedimentation plans are required for larger projects it is recommended that expert consultants produce these plans. • The “Do it Right On Site, Soil and Water Management for the Construction Industry” publication and accompanying factsheets can be downloaded from www.woollahra.nsw.gov.au, and The Blue Book is available at www.environment.nsw.gov.au • Under clause 73(2)(a)(v) of the Development Certification and Fire Safety Regulation an Accredited Certifier may be satisfied as to this matter. <p>Condition Reason: To prevent potential water pollution and dust nuisance.</p>
<p>D. 9.</p>	<p>Tree Protection Plan and Specification</p> <p>Before the issue of any construction certificate, the Principal Certifier must ensure the measures for tree protection detailed in this consent are in place. The construction certificate plans and specifications must show the following information:</p>

	<p>a) Trees to be numbered and coloured in accordance with these conditions:</p> <ul style="list-style-type: none"> • shaded green where required to be retained and protected • shaded red where authorised to be removed • shaded yellow where required to be transplanted • shaded blue where required to be pruned <p>b) Tree Protection Plan and Specification prepared by an arborist with a minimum qualification of AQF 5 including the following:</p> <ul style="list-style-type: none"> • Tree Location Plan (to scale) based on/overlaid with the approved plans, indicating trees to be retained, removed or transplanted, and the location of tree protection zones (TPZ) and structural root zones (SRZ) of trees to be retained and protected. • The plan must also include site specific tree protection recommendations such as fencing, ground and trunk protection and other protection devices. • Tree Protection Specification (written document) with tree protection requirements included from this consent and in accordance with sections 4 & 5 of AS4970, providing guidance for the implementation of tree protection methods. • To minimise construction damage, the plan must show specific areas requiring works to be done under direct supervision of the project arborist. <p>c) References to applicable tree management plan, arborists report or transplant method statement.</p> <p>This plan must be kept on site until the issue of the occupation certificate for the whole building.</p> <p>Condition Reason: To ensure the construction certificate includes the approved tree management details, and all measures are implemented.</p>
<p>D. 10.</p>	<p>Professional Engineering Details</p> <p>Before the issue of any construction certificate, the construction certificate plans and specifications, required under clause 7 of the Development Certification and Fire Safety Regulation, must include detailed professional engineering plans and/or specifications for all structural, electrical, hydraulic, hydrogeological, geotechnical, mechanical and civil work complying with this consent, approved plans, and supporting documentation.</p> <p>Detailed professional engineering plans and/or specifications must be submitted to the Principal Certifier with the application for any construction certificate.</p> <p>Notes:</p> <ul style="list-style-type: none"> • This does not affect the right of the developer to seek staged construction certificates. <p>Condition Reason: To ensure professional engineering details and technical specifications are provided.</p>

<p>D. 11.</p>	<p>Engineer Certification</p> <p>Before the issue of any construction certificate, engineer certification must be submitted to the Principal Certifier confirming that the structural design does not incorporate any temporary or permanent underpinning works or ground anchors, bolts, etc. which encroach outside the boundaries of the subject property.</p> <p>This development consent does NOT give approval to any works outside the boundaries of the subject property including any underpinning works to any structures on adjoining properties and Council's property.</p> <p>Condition Reason: To ensure certification is provided that demonstrates all structural works are located within the boundaries of the site and do not include underpinning works to any structures on adjoining properties.</p>
<p>D. 12.</p>	<p>Geotechnical and Hydrogeological Design, Certification and Monitoring</p> <p>Before the issue of the construction certificate, the applicant must submit, for approval by the Principal Certifier, a detailed geotechnical report prepared by a Geotechnical Engineer with National Engineering Register (NER) credentials in accordance with Chapter E2 of Council's DCP and Council's document "Guidelines for Preparation of Geotechnical and Hydrogeological Reports". The report must include a Geotechnical / Hydrogeological Monitoring Program together with civil and structural engineering details for foundation retaining walls, footings, basement tanking, and subsoil drainage systems, as applicable, prepared by a professional engineer, who is suitably qualified and experienced in geotechnical and hydrogeological engineering.</p> <p>These details must be certified by the professional engineer to:</p> <ol style="list-style-type: none"> a) Provide appropriate support and retention to ensure there will be no ground settlement or movement, during excavation or after construction, sufficient to cause an adverse impact on adjoining property or public infrastructure. b) Provide appropriate support and retention to ensure there will be no adverse impact on surrounding property or infrastructure as a result of changes in local hydrogeology (behaviour of groundwater). c) Provide foundation tanking prior to excavation such that any temporary changes to the groundwater level, during construction, will be kept within the historical range of natural groundwater fluctuations. Where the historical range of natural groundwater fluctuations is unknown, the design must demonstrate that changes in the level of the natural water table, due to construction, will not exceed <#m> at any time. d) Provide tanking to below ground structures to prevent the entry of seepage water such that subsoil drainage/ seepage water is NOT collected and discharged to the kerb and gutter. e) Provide a Geotechnical and Hydrogeological Monitoring Program that: <ul style="list-style-type: none"> • will detect any settlement associated with temporary and permanent works and structures, • will detect deflection or movement of temporary and permanent retaining structures (foundation walls, shoring bracing or the like), • will detect vibration in accordance with AS 2187.2 Appendix J including acceptable velocity of vibration (peak particle velocity), • will detect groundwater changes calibrated against natural groundwater variations, • details the location and type of monitoring systems to be utilised, • details the pre-set acceptable limits for peak particle velocity and ground water fluctuations,

	<ul style="list-style-type: none"> • details recommended hold points to allow for the inspection and certification of geotechnical and hydrogeological measures by the professional engineer, and • details a contingency plan. <p>Condition Reason: To ensure that geotechnical and hydrogeological impacts are appropriately managed.</p>
<p>D. 13.</p>	<p>Ground Anchors</p> <p>This development consent does NOT give approval to works or structures over, on or under adjoining properties, public roads and/or footpaths.</p> <p>Before the issue of any construction certificate, if ground anchors are proposed:</p> <ol style="list-style-type: none"> a) Prior written consent must be obtained from all relevant adjoining property owner(s) for the use of any ground anchors extending beyond the boundaries of the subject property. b) The use of permanent ground anchors under Council land is not permitted. Temporary ground anchors under Council's land may be permitted, in accordance with Council's "Rock Anchor Policy", where alternative methods of stabilisation would not be practicable or viable, and where there would be benefits in terms of reduced community impact due to a shorter construction period, reduced disruption to pedestrian and vehicular traffic on adjacent public roads, and a safer working environment. c) If temporary ground anchors under Council land are proposed, a separate application, including payment of fees, must be made to Council under Section 138 of the Roads Act 1993. Application forms and Council's "Rock Anchor Policy" are available from Council's website. Approval may be granted subject to conditions of consent. A minimum of four weeks should be allowed for assessment. <p>Notes:</p> <ul style="list-style-type: none"> • To ensure that this work is completed to Council's satisfaction, this consent by separate condition, may impose one or more Infrastructure Works Bonds. • Road has the same meaning as in the Roads Act 1993. • Clause 17 of the Roads (General) Regulation 2018 prohibits excavation in the vicinity of roads as follows: "Excavations adjacent to road - A person must not excavate land in the vicinity of a road if the excavation is capable of causing damage to the road (such as by way of subsidence) or to any work or structure on the road." Separate approval is required under the Roads Act 1993 for any underpinning, shoring, soil anchoring (temporary) or the like within or under any road. Council will not give approval to permanent underpinning, shoring, soil anchoring within or under any road. <p>Condition Reason: To ensure the relevant approval is gained for any temporary ground anchors.</p>
<p>D. 14.</p>	<p>Parking Facilities</p> <p>Before the issue of any construction certificate, the construction certificate plans and specifications required under clause 7 of the Development Certification and Fire Safety Regulation, must include detailed plans and specifications for all bicycle, car and commercial vehicle parking in compliance with AS/NZS 2890.1: Parking Facilities - Off-Street Car Parking.</p> <p>The plans must satisfy the following requirement(s):</p>

	<p>a) Sight distance requirements must comply with Clause 3.2.4 and Figure 3.3 of AS2890.1:2004;</p> <p>b) Convex mirror be installed wholly within property boundary at vehicle access point to assist with visibility of vehicles leaving the site;</p> <p>c) A STOP sign, a STOP line and a rubber speed hump or its equivalent be installed on the ramp, prior to the car exit point to slow the vehicles exiting the driveway to improve traffic safety on the frontage road adjacent to the proposed driveway access. The rubber speed hump or its equivalent shall be installed across the entire width of the ramp (5.2 metres), at 6.0 metres prior to the boundary line. This should be clearly depicted on the architectural plans.</p> <p>Access levels and grades must comply with access levels and grades required by Council under the Roads Act 1993.</p> <p>The Principal Certifier has no discretion to reduce or increase the number or area of car parking or commercial parking spaces required to be provided and maintained by this consent.</p>
	<p>Condition Reason: To ensure parking facilities are designed in accordance with the Australian Standard.</p>
<p>D. 15.</p>	<p>Stormwater Management Plan</p> <p>Before the issue of any construction certificate, the applicant must submit, for approval by the Principal Certifier, detailed stormwater management plans prepared and certified by a chartered professional civil engineer, which detail the following:</p> <p>a) General design in accordance with stormwater management plans, referenced 230604-Issue C, prepared by RTS Engineers, dated 05/04/2024, other than amended by this and other conditions,</p> <p>b) All below ground structures are to be fully tanked such that subsoil drainage/seepage water is NOT collected and discharged to the kerb and gutter to comply with Chapter E2.2.5 of Council's DCP. Notation to this requirement must be clearly depicted on the drawings,</p> <p>c) The discharge of stormwater from the site, by direct connection, to the street kerb. The stormwater outlet pipe and the kerb discharge must be located within the frontage of the site. Only one stormwater outlet with a maximum discharge rate of 20 l/s in the 1% AEP storm event will be permitted. Full supporting calculations must be included in the stormwater management plans,</p> <p>d) A minimum 600mm x 600mm boundary junction pit must be provided prior to discharging stormwater from the site to the street drainage system. The stormwater outlet pipe across the Council's property must have a minimum grade of 1% to comply with Council's DCP and AS3500.3,</p> <p>e) The installation of rainwater retention and reuse system (RWT) with a minimum storage volume of 90m³ to comply with Chapter E2.2.9 of the Council's DCP. Runoff from all roof areas must be collected and directed to the required RWT for non-potable uses such as toilet flushing, laundry devices and garden irrigation etc. Details including notation to this requirement must be clearly depicted on the drawings. Overflow from the RWT must be directed to a minimum 600mm x 600mm boundary junction pit prior to discharging to the street kerb by gravity,</p> <p>f) The installation of a pumpout system with minimum storage capacity of 10m³. The pump system and storage well capacity must be designed in accordance with AS3500.3,</p>

- g) The provision of stormwater treatment system including but not limited to 90m³ rainwater tank (RWT), SPEL Stormsacks, 3 x SPELFilter full height SF.30-EMC by Spel Stormwater to meet the water quality targets stipulated in Chapter E2.2.3 of Council's DCP. Stormwater runoff from min. 556m² roof area must be directed to the 90m³ RWT for reuse purposes to comply with the MUSIC model,
- h) The storage capacity of the proposed on-site absorption system must be designed based on the catchment area and for the 5% AEP storm event. Full supporting calculations must be included in the stormwater management plans. The absorption system must be located at a minimum distance of 3 metres from any property boundary and the footing of any structures,
- i) Internal stormwater drainage including but not limited to gutters and downpipes, pipes and pits are to be designed for rainfall intensities up to and including the 1% AEP event if an unimpeded overland flow path to the street drainage system is not available. Design details and calculations must be included in the stormwater management plans,
- j) Interceptor drain(s) at the site boundary to prevent stormwater flows from the site crossing the footpath,
- k) Dimensions of all drainage pits and access grates must comply with AS3500.3,
- l) Compliance with the objectives and performance requirements of the BCA,
- m) General compliance with the Council's Woollahra DCP 2015 Chapter E2 – Stormwater and Flood Risk Management.

Rainwater Tank (RWT) Requirements

The minimum storage volume for the required rainwater tank (RWT) must be 90m³.

The Stormwater Management Plan must also include the following specific requirements:

Layout plan

A detailed drainage plan at a scale of 1:100 based on drainage calculations prepared in accordance with the Australian Government publication, Australian Rainfall and Run-off, 2019 edition or most current version thereof. It must include:

- a) All pipe layouts, dimensions, grades, lengths and material specification.
- b) Location of proposed rainwater tanks.
- c) All invert levels reduced to Australian Height Datum (AHD).
- d) Location and dimensions of all drainage pits.
- e) Point and method of connection to Councils drainage infrastructure.
- f) Overland flow paths over impervious areas.

Rainwater Reuse System details:

- a) Any potential conflict between existing and proposed trees and vegetation.
- b) Internal dimensions and volume of the proposed rainwater storage.
- c) Plans, elevations and sections showing the rainwater tanks, finished surface level and adjacent structures.
- d) Details of access and maintenance facilities.
- e) Construction and structural details of all tanks and pits and/or manufacturer's specifications for proprietary products.
- f) Details of the emergency overland flow-path (to an approved Council drainage point) in the event of a blockage to the rainwater tanks

For Stormwater Drainage works on Council's property, separate approval under Section 138 of the Roads Act 1993 must be obtained from Council for those works before the issue of any construction certificate.

All Stormwater Drainage System work within any road or public place must comply with Woollahra Municipal Council's Specification for Roadworks, Drainage and Miscellaneous Works (2012).

	<p>Notes:</p> <ul style="list-style-type: none"> The collection, storage and use of rainwater is to be in accordance with Standards Australia HB230 "Rainwater Tank Design and Installation Handbook". <p>Condition Reason: To ensure that site stormwater is disposed of in a controlled and sustainable manner.</p>
<p>D. 16.</p>	<p>Non-Gravity Drainage Systems</p> <p>Before the issue of any construction certificate, the construction certificate plans and specifications required under clause 7 of the Development Certification and Fire Safety Regulation, must include a Stormwater Management Plan for the site.</p> <p>The Stormwater Management Plan must detail the non-gravity drainage systems (charged, siphon, pump/sump systems) being designed in accordance with Woollahra DCP 2015 Chapter E2 – Stormwater and Flood Risk Management.</p> <p>Notes: The Woollahra DCP is available from Council's website www.woollahra.nsw.gov.au</p> <p>Condition Reason: To ensure that site stormwater is disposed of in a controlled and sustainable manner.</p>
<p>D. 17.</p>	<p>Stormwater Infiltration Systems</p> <p>Before the issue of any construction certificate, the construction certificate plans and specifications required under clause 7 of the Development Certification and Fire Safety Regulation, must include a Stormwater Management Plan for the site and must detail:</p> <ol style="list-style-type: none"> the soil permeability coefficient and estimate of mean water table level using field observations, how the system will disperse a 1 in 20 years average recurrence interval storm, how the system will cater for a 1 in 100 years average recurrence interval storm event by overland flow paths, and general compliance with Woollahra DCP 2015 Chapter E2 – Stormwater and Flood Risk Management. <p>Condition Reason: To ensure that site stormwater is disposed of in a controlled and sustainable manner.</p>
<p>D. 18.</p>	<p>Electric vehicle circuitry and electric vehicle charging point requirements</p> <p>Before the issue of any construction certificate, the construction certificate plans and specifications required under clause 7 of the Development Certification and Fire Safety Regulation, must include an accurate electrical plan and specifications for all off-street car parking, prepared by a suitably qualified person, demonstrating the following;</p> <ol style="list-style-type: none"> That each off-street car parking space will be provided with electrical circuitry to support the installation of a Level 2 electric vehicle charger point. The construction certificate plans are to: <ul style="list-style-type: none"> Identify the power capacity to each car parking space. Identify the load management system on each level of parking such as a distribution board.

	<ul style="list-style-type: none"> • Identify the conduit system to allow each car space to install an electric vehicle charger point - such as cable trays and/or buried cables underground. This system must allow future installation of cabling to power electric vehicle charger points and allow internet access (run Ethernet cable or install 4G modem). <p>b) A minimum of one Level 2 electric charger must be provided and Level 2 chargers must be provided to not less than 10% of all car parking spaces. The location of all electric vehicle chargers must be shown on the construction certificate plans.</p> <p>c) The Principal Certifier must be satisfied that the electrical plans and specifications are consistent with (a) and (b) prior to the issue of the construction certificate.</p> <p>Notes:</p> <ul style="list-style-type: none"> • The minimum electric circuitry requirements for ‘Level 2’ electric vehicle charging points are: <ul style="list-style-type: none"> - Privately available spaces including visitor spaces: ‘Level 2’ slow – single phase 7kW power; and - Publicly available spaces: ‘Level 2’ fast – three-phase 11-22kW power. <p>Condition Reason: To ensure the provision of electric vehicle circuitry to enable the future installation of electric vehicle charging point(s).</p>
<p>D. 19.</p>	<p>Acoustic Certification of Mechanical Plant and Equipment</p> <p>Before the issue of any construction certificate, the construction certificate plans and specifications required under clause 7 of the Development Certification and Fire Safety Regulation, must be accompanied by a certificate from a professional acoustic engineer certifying that the noise level measured at any boundary of the site at any time while the proposed mechanical plant and equipment is operating will not exceed the background noise level. Where noise sensitive receivers are located within the site, the noise level is measured from the nearest strata, stratum or community title land and must not exceed background noise level, at any time.</p> <p>The background noise level is the underlying level present in the ambient noise, excluding the subject noise source, when extraneous noise is removed. For assessment purposes the background noise level is the LA90, 15 minute level measured by a sound level meter.</p> <p>Where sound attenuation is required this must be detailed.</p> <p>Notes:</p> <ul style="list-style-type: none"> • Further information including lists of Acoustic Engineers can be obtained from: <ul style="list-style-type: none"> - Australian Acoustical Society - professional society of noise-related professional www.acoustics.asn.au - Association of Australian Acoustical Consultant - professional society of noise related professionals www.aaac.org.au <p>Condition Reason: To ensure the development does not result in any unreasonable acoustic impacts.</p>
<p>D. 20.</p>	<p>Submission of a Site Waste Minimisation and Management Plan</p> <p>Before the issue of any construction certificate, a Site Waste Minimisation and Management Plan, prepared in accordance with Woollahra Development Control Plan 2015 Chapter E5 – Waste Management, is to be submitted to Council for approval.</p>

Notes:

- The site waste minimisation and management is not listed under clause 73 of the Development Certification and Fire Safety Regulation as a matter that a Principal Certifier may certify. Hence, the Site Waste Minimisation and Management Plan must be referred to Council for its approval prior to the issue of any construction certificate for such works.
- It is estimated that building waste, including disposable materials, resulting from demolition, excavation, construction and renovation, accounts for almost 70% of landfill. Such waste is also a problem in the generation of dust and the pollution of stormwater. Council encourages the recycling of demolition and building materials.

Condition Reason: To ensure that the Waste Minimisation and Management Plan is assessed and approved by Council.

D 21. Payment of S7.12 Contributions Levy

A payment of a levy authorised by section 7.12 of the Environmental Planning and Assessment Act 1979 must be paid prior to the issue of any Construction Certificate or Subdivision Works Certificate. The Principal Certifier is to be provided with the original receipt for payment under the Woollahra Section 7.12 Development Contributions Plan 2022.

A cost estimate report, no more than 3 months old, demonstrating the proposed cost of carrying out the development must be completed and submitted to Council for determination of the costs of work. This report must incorporate all approved modification applications. The costs and expenses of the proposed cost of development must be established in accordance with clause 208 of the Environmental Planning and Assessment Regulation 2021.

The cost estimate report must be in the form of:

- A cost summary report, prepared by the applicant or a suitably qualified person for a development up to \$749,999; or
- A quantity surveyor's report, for development over \$750,000.

The applicable levy rate is to be calculated using the summary schedule below.

Summary Schedule	
Development Cost	Levy Rate
• Up to and including \$100,000	Nil
• More than \$100,000 and up to and including \$200,000	0.5% of the cost
• More than \$200,000	1% of the cost

How must the payments be made?

Payments must be made by:

- Cash deposit with Council,
- Credit card payment with Council, or
- Bank cheque made payable to Woollahra Municipal Council.

Deferred or periodic payment of section 7.12 levy

Where the Applicant makes a written request supported by reasons for payment of the section 7.12 levy other than as required by clause 2.9, the Council may accept deferred or periodic payment. The decision to accept a deferred or periodic payment is at the sole discretion of the Council, which will consider:

- the reasons given,
- whether any prejudice will be caused to the community deriving benefit from the public facilities,

	<ul style="list-style-type: none"> • whether any prejudice will be caused to the efficacy and operation of the Plan, and • whether the provision of public facilities in accordance with the adopted works schedule will be adversely affected. <p>Council may, as a condition of accepting deferred or periodic payment, require the provision of a bank guarantee where:</p> <ul style="list-style-type: none"> • the guarantee is by an Australian bank for the amount of the total outstanding contribution, • the bank unconditionally and irrevocably agrees to pay the guaranteed sum to the Council on written request by Council prior to the issue of an occupation certificate, • a time limited bank guarantee or a bank guarantee with an expiry date is not acceptable, • the bank agrees to pay the guaranteed sum without recourse to the applicant or landowner or other person who provided the guarantee and without regard to any dispute, controversy, issue or other matter relating to the development consent or the carrying out of development in accordance with the development consent, and • the bank’s obligations are discharged when payment to the Council is made in accordance with the guarantee or when Council notifies the bank in writing that the guarantee is no longer required. <p>Any deferred or periodic payment of the section 7.12 levy will be adjusted in accordance with clause 2.12 of the Plan. The Applicant will be required to pay any charges associated with establishing or operating the bank guarantee. Council will not cancel the bank guarantee until the outstanding contribution as indexed and any accrued charges are paid.</p> <p>Do you need HELP indexing the levy? Please contact Council’s Customer Service Team on 02 9391 7000. Failure to correctly calculate the adjusted development levy will delay the issue of any certificate issued under section 6.4 of the Act and could void any such certificate (e.g. construction certificate, subdivision certificate, or occupation certificate).</p> <p>Condition Reason: To ensure any relevant contributions are paid.</p>
--	--

E. BEFORE BUILDING WORK COMMENCES

E. 1.	<p>Compliance with Building Code of Australia and insurance requirements under the Home Building Act 1989</p> <p>Before any building work commences, and under section 4.17(11) of the Act, the following conditions are prescribed in relation to a development consent for development that involves any building work:</p> <ol style="list-style-type: none"> a) that the work must be carried out in accordance with the requirements of the Building Code of Australia, b) in the case of residential building work for which the Home Building Act 1989 requires there to be a contract of insurance in force in accordance with Part 6 of that Act, that such a contract of insurance is in force before any building work authorised to be carried out by the consent commences. <p>This condition does not apply:</p> <ol style="list-style-type: none"> a) to the extent to which an exemption is in force under the Home Building Regulation 2014, or b) to the erection of a temporary building.
--------------	---

	<p>In this condition, a reference to the BCA is a reference to that code as in force on the date the application for the relevant Construction Certificate is made.</p> <p>Notes:</p> <ul style="list-style-type: none"> • This condition must be satisfied prior to commencement of any work in relation to the contract of insurance under the Home Building Act 1989. This condition also has effect during the carrying out of all building work with respect to compliance with the Building Code of Australia. • All new guttering is to comply with the provisions of AS3500. <p>Condition Reason: To ensure that works are carried out in accordance with the Building Code of Australia and any required contract of insurance is in force.</p>
<p>E. 2.</p>	<p>Erosion and Sediment Controls – Installation</p> <p>Before any building work commences, water pollution, erosion and sedimentation controls must be installed and maintained in accordance with:</p> <ol style="list-style-type: none"> a) The Soil and Water Management Plan if required under this consent; b) “Do it Right On Site, Soil and Water Management for the Construction Industry” and accompanying factsheets published by the Southern Sydney Regional Organisation of Councils, and c) “Managing Urban Stormwater - Soils and Construction” 2004 published by the NSW Government (The Blue Book). <p>Where there is any conflict The Blue Book takes precedence.</p> <p>Notes:</p> <ul style="list-style-type: none"> • The International Erosion Control Association – Australasia (www.austieca.com.au/) lists consultant experts who can assist in ensuring compliance with this condition. • Where Soil and Water Management Plan is required for larger projects it is recommended that this be produced by a member of the International Erosion Control Association – Australasia. • The “Do it Right On Site, Soil and Water Management for the Construction Industry” publication and the accompanying factsheets can be downloaded from www.woollahra.nsw.gov.au and The Blue Book is available at www.environment.nsw.gov.au • A failure to comply with this condition may result in penalty infringement notices, prosecution, notices and orders under the Act and/or the Protection of the Environment Operations Act 1997 without any further warning. It is a criminal offence to cause, permit or allow pollution. • Section 257 of the Protection of the Environment Operations Act 1997 provides inter alia that “the occupier of premises at or from which any pollution occurs is taken to have caused the pollution”. • Warning: Irrespective of this condition any person occupying the site may be subject to proceedings under the Protection of the Environment Operations Act 1997 where pollution is caused, permitted or allowed as the result of their occupation of the land being. <p>Condition Reason: To prevent potential water pollution and dust nuisance.</p>
<p>E. 3.</p>	<p>Building - Construction Certificate, Appointment of Principal Certifier, Appointment of Principal Contractor and Notice of Commencement (Part 6, Division 6.3 of the Act)</p> <p>Building work must not commence, until:</p> <ol style="list-style-type: none"> a) A construction certificate for the building work has been issued by the consent authority, the Council (if the Council is not the consent authority) or an accredited Certifier, and b) The person having the benefit of the development consent has: <ul style="list-style-type: none"> • appointed a Principal Certifier for the building work, and

	<ul style="list-style-type: none"> • notified the Principal Certifier that the person will carry out the building work as an Owner-builder, if that is the case, and <p>c) The Principal Certifier has, no later than 2 days before the building work commences:</p> <ul style="list-style-type: none"> • notified the consent authority and the Council (if the Council is not the consent authority) of his or her appointment, and • notified the person having the benefit of the development consent of any critical stage inspections and other inspections that are to be carried out in respect of the building work, and <p>d) The person having the benefit of the development consent, if not carrying out the work as an Owner-builder, has:</p> <ul style="list-style-type: none"> • appointed a Principal Contractor for the building work who must be the holder of a contractor licence if any residential building work is involved, and • notified the Principal Certifier of any such appointment, and • unless that person is the Principal Contractor, notified the Principal Contractor of any critical stage inspections and other inspections that are to be carried out in respect of the building work, and • given at least 2 days' notice to the Council of the person's intention to commence the erection of the building. <p>Notes:</p> <ul style="list-style-type: none"> • Building has the same meaning as in section 1.4 of the Act and includes part of a building and any structure or part of a structure. • New building has the same meaning as in section 6.1 of the Act and includes an altered portion of, or an extension to, an existing building. • The commencement of demolition works associated with an altered portion of, or an extension to, an existing building is considered to be the commencement of building work requiring compliance with section 6.6(2) of the Act (including the need for a Construction Certificate) prior to any demolition work. See: <i>Over our Dead Body Society Inc v Byron Bay Community Association Inc</i> [2001] NSWLEC 125. • Construction Certificate Application, PC Service Agreement and Notice of Commencement forms can be downloaded from Council's website www.woollahra.nsw.gov.au • It is an offence for any person to carry out the erection of a building in breach of this condition and in breach of section 6.6(2) of the Act. • Under the Home Building Act 1989 any property owner who intends undertaking construction work to a dwelling house or dual occupancy to the value of \$12,000 or over must complete an approved education course and obtain an owner-builder permit from NSW Fair Trading.
	<p>Condition Reason: To ensure a construction certificate has been issued, a Principal Certifier is appointed, a Principal Contractor (if applicable) is appointed, and a notice of commencement has been submitted.</p>
<p>E. 4.</p>	<p>Notification of Home Building Act 1989 requirements</p> <p>Residential building work within the meaning of the Home Building Act 1989 must not be carried out unless the Principal Certifier for the development to which the work relates (not being the Council) has given the Council written notice of the following information:</p> <p>a) In the case of work for which a Principal Contractor is required to be appointed:</p> <ul style="list-style-type: none"> • the name and licence number of the Principal Contractor, and • the name of the insurer by which the work is insured under Part 6 of that Act, <p>b) In the case of work to be done by an Owner-builder:</p> <ul style="list-style-type: none"> • the name of the Owner-builder, and • if the Owner-builder is required to hold an Owner-builder permit under that Act, the number of the Owner-builder permit.

	<p>If arrangements for doing the residential building work are changed while the work is in progress so that the information notified under subclause (2) becomes out of date, further work must not be carried out unless the Principal Certifier for the development to which the work relates (not being the Council) has given the Council written notice of the updated information.</p> <p>This clause does not apply in relation to Crown building work that is certified, in accordance with section 6.28 of the Act, to comply with the Building Code of Australia.</p> <p>For the purposes of section 4.17(11) of the Act, the requirements of this condition are prescribed as conditions of a development consent for development that involves any residential building work within the meaning of the Home Building Act 1989.</p>
	<p>Condition Reason: To ensure Council is notified of the Home Building Acts 1989 requirements.</p>

F. DURING BUILDING WORK

F. 1.	<p>Compliance with BCA and Insurance Requirements under the Home Building Act 1989</p> <p>While site work is being carried out:</p> <ul style="list-style-type: none"> a) work must be carried out in accordance with the requirements of the Building Code of Australia (BCA), b) in the case of residential building work for which the Home Building Act 1989 requires there to be a contract of insurance in force in accordance with Part 6 of that Act, that such a contract of insurance is in force before any building work authorised to be carried out by the consent commences. <p>This condition does not apply:</p> <ul style="list-style-type: none"> a) to the extent to which an exemption is in force under the Development Certification and Fire Safety Regulations, or b) to the erection of a temporary building. <p>In this clause, a reference to the BCA is a reference to that Code as in force on the date the application for the relevant construction certificate is made.</p> <p>For the purposes of section 4.17(11) of the Act, the above condition is prescribed in relation to a development consent for development that involves any building work.</p> <p>Notes:</p> <ul style="list-style-type: none"> • All new guttering is to comply with the provisions of AS 3500.
	<p>Condition Reason: To ensure compliance with the BCA and Home building Act 1989.</p>
F. 2.	<p>Compliance with Construction Management Plan</p> <p>While site work is being carried out, all development activities and traffic movements must be carried out in accordance with the approved Construction Management Plan (CMP). All controls in the CMP must be maintained at all times. A copy of the CMP must be kept on-site at all times and made available to the Principal Certifier on request.</p> <p>Notes:</p> <ul style="list-style-type: none"> • Irrespective of the provisions of the Construction Management Plan the provisions of traffic and parking legislation prevails.

	<p>Condition Reason: To ensure compliance with the Construction Management Plan.</p>
F. 3.	<p>Requirement to Notify about New Evidence</p> <p>While site work is being carried out, any new information that comes to light, which has the potential to alter previous conclusions about site contamination, heritage significance, threatened species or other relevant matters must be immediately notified to Council and the Principal Certifier.</p> <p>Condition Reason: To ensure Council and the Principal Certifier are made aware of new information.</p>
F. 4.	<p>Critical Stage Inspections</p> <p>While site work is being carried out, critical stage inspections must be called for by the Principal Contractor or Owner-builder as required by the Principal Certifier, any PC service agreement, the Act, the Development Certification and Fire Safety Regulation, and the Regulation.</p> <p>Work must not proceed beyond each critical stage until the Principal Certifier is satisfied that work is proceeding in accordance with this consent, the construction certificate(s) and the Act.</p> <p>Critical stage inspections means the inspections prescribed by the Development Certification and Fire Safety Regulations, and Regulations for the purposes of section 6.5 of the Act or as required by the Principal Certifier and any PC Service Agreement.</p> <p>Notes:</p> <ul style="list-style-type: none"> • The Principal Certifier may require inspections beyond mandatory critical stage inspections in order that the Principal Certifier be satisfied that work is proceeding in accordance with this consent. • The Principal Certifier may, in addition to inspections, require the submission of Compliance Certificates, survey reports or evidence of suitability in accordance with Part A2G2 of the BCA in relation to any matter relevant to the development. <p>Condition Reason: To ensure that building work progresses in accordance with the approved plans, conditions of consent, and requirements of the act.</p>
F. 5.	<p>Hours of Work –Amenity of the Neighbourhood</p> <p>While site work is being carried out:</p> <ol style="list-style-type: none"> a) No work must take place on any Sunday or public holiday. b) No work must take place before 7am or after 5pm any weekday. c) No work must take place before 7am or after 1pm any Saturday. d) The following work must not take place before 9am or after 4pm any weekday, or before 9am or after 1pm any Saturday or at any time on a Sunday or public holiday: <ol style="list-style-type: none"> i. piling, ii. piling, iii. rock or concrete cutting, boring or drilling, iv. rock breaking, v. rock sawing, vi. jack hammering, or vii. machine excavation.

- e) No loading or unloading of material or equipment associated with the activities listed in part d) above must take place before 9am or after 4pm any weekday, or before 9am or after 1pm any Saturday or at any time on a Sunday or public holiday.
- f) No operation of any equipment associated with the activities listed in part d) above must take place before 9am or after 4pm any weekday, or before 9am or after 1pm any Saturday or at any time on a Sunday or public holiday.
- g) No rock excavation being cutting, boring, drilling, breaking, sawing, jack hammering or bulk excavation of rock, must occur without a 15 minute interval break within every hour.

Notes:

- The use of noise and vibration generating plant and equipment and vehicular traffic, including trucks in particular, significantly degrade the amenity of neighbourhoods and more onerous restrictions apply to these activities. This more invasive work generally occurs during the foundation and bulk excavation stages of development. If you are in doubt as to whether or not a particular activity is considered to be subject to the more onerous requirement (9am to 4pm weekdays and 9am to 1pm Saturdays) please consult with Council.
- Each and every breach of this condition by any person may be subject to a separate penalty infringement notice or prosecution.
- The delivery and removal of plant, equipment and machinery associated with wide loads subject to Transport for NSW and NSW Police restrictions on their movement outside the approved hours of work will be considered on a case by case basis.
- Compliance with these hours of work does not affect the rights of any person to seek a remedy to offensive noise as defined by the Protection of the Environment Operations Act 1997, the Protection of the Environment Operations (Noise Control) Regulation 2017.
- NSW EPA Noise Guide is available at www.epa.nsw.gov.au/noise/nqlq.htm

Condition Reason: To mitigate the impact of work upon the amenity of the neighbourhood.

F. 6. Public Footpaths – Safety, Access and Maintenance

While site work is being carried out, any person acting with the benefit of this consent must:

- a) Not erect or maintain any gate or fence that swings out, or encroaches upon the road or the footway.
- b) Not use the road or footway for the storage of any article, material, matter, waste or thing.
- c) Not use the road or footway for any work.
- d) Keep the road and footway in good repair free of any trip hazard or obstruction.
- e) Any damage caused to the road, footway, vehicular crossing, nature strip or any public place must be immediately made safe and then repaired, to the satisfaction of Council.
- f) Not stand any plant and equipment upon the road or footway.
- g) If it is proposed to locate any site fencing, hoardings, skip bins or other articles upon any part of the footpath, nature strip or any public place, or operate a crane, hoist or concrete pump on or over Council land, an application must be submitted to and approved by Council beforehand.
- h) Provide a clear safe pedestrian route a minimum of 1.5m wide.
- i) Protect heritage listed street name inlays located in the footpath, kerb and gutter, and any other structure, to ensure they are not removed or damaged during development.

This condition does not apply to the extent that a permit or approval exists under the section 148B of the Road Transport Act 2013, section 138 of the Roads Act 1993 or section 68 of the Local Government Act 1993 except that at all time compliance is required with:

- a) Australian Standard AS 1742 (Set): Manual of uniform traffic control devices and all relevant parts of this set of standards.
- b) Australian Road Rules.

Notes:

- Section 148B of the Road Transport Act 2013 allows the NSW Police to close any road or road related area to traffic during any temporary obstruction or danger to traffic or for any temporary purpose.
- Section 138 of the Roads Act 1993 provides that a person must not:
 - erect a structure or carry out a work in, on or over a public road, or
 - dig up or disturb the surface of a public road, or
 - remove or interfere with a structure, work or tree on a public road, or
 - pump water into a public road from any land adjoining the road, or
 - connect a road (whether public or private) to a classified road, or
 - otherwise than with the consent of the appropriate roads authority.
- Section 68 of the Local Government Act 1993 provides that a person may carry out certain activities only with the prior approval of the Council including:
 - Part C Management of waste:
 - a) For fee or reward, transport waste over or under a public place
 - b) Place waste in a public place
 - c) Place a waste storage container in a public place.
 - Part E Public roads:
 - a) Swing or hoist goods across or over any part of a public road by means of a lift, hoist or tackle projecting over the footway
 - b) Expose or allow to be exposed (whether for sale or otherwise) any article in or on or so as to overhang any part of the road or outside a shop window or doorway abutting the road, or hang an article beneath an awning over the road.

Condition Reason: To ensure safe access is maintained to footpaths and roads during building works.

F. 7. Tree Preservation

While site work is being carried out, all persons must comply with Chapter E.3 – *Tree Management* of Council’s Development Control Plan (DCP) 2015, other than where varied by this consent. The DCP applies to any tree with a height greater than 5 metres or a diameter spread of branches greater than 3 metres.

General Protection Requirements:

- a) The tree protection measures must be maintained during all development work unless otherwise specified within these conditions of consent.
- b) Excavation must cease where tree roots with a diameter exceeding 50mm are exposed. The principal contractor must procure an inspection of the exposed tree roots by an arborist with a minimum AQF Level 5 qualification. Excavation must only recommence with the implementation of the recommendations of the arborist.
- c) Where there is damage to any part of a tree the principal contractor must procure an inspection of the tree by a qualified arborist immediately. The principal contractor must immediately implement treatment as directed by the arborist. The arborist is to supply a detailed report to the appointed certifier.

Trees must be pruned in accordance with Australian Standard AS 4373 “Pruning of Amenity Trees” and WorkCover NSW Code of Practice Amenity Tree Industry.

	<p>Condition Reason: To protect trees during the carrying out of sitework.</p>
F. 8.	<p>Maintenance of Environmental Controls</p>
	<p>While site work is being carried out, the following monitoring, measures and controls must be maintained:</p> <ul style="list-style-type: none"> a) erosion and sediment controls, b) dust controls, c) dewatering discharges, d) noise controls, e) vibration monitoring and controls, and f) ablutions.
	<p>Condition Reason: To ensure that environmental controls are maintained during building works to protect the public and surrounding environment.</p>
F. 9.	<p>Compliance with Geotechnical / Hydrogeological Monitoring Program</p>
	<p>While site work is being carried out, excavation must be undertaken in accordance with the recommendations of the Geotechnical / Hydrogeological Monitoring Program and any oral or written direction of the supervising professional engineer.</p> <p>The Principal Contractor and any sub-contractor must strictly follow the Geotechnical / Hydrogeological Monitoring Program for the development including, but not limited to:</p> <ul style="list-style-type: none"> a) the location and type of monitoring systems to be utilised, b) recommended hold points to allow for inspection and certification of geotechnical and hydrogeological measures by the professional engineer, and c) the contingency plan. <p>Notes:</p> <ul style="list-style-type: none"> • The consent authority cannot require that the author of the geotechnical/hydrogeological report submitted with the development application to be appointed as the professional engineer supervising the work however, it is the Council's recommendation that the author of the report be retained during the construction stage.
	<p>Condition Reason: To ensure the geotechnical and/or hydrogeological impacts of the development are appropriately managed.</p>
F. 10.	<p>Support of Adjoining Land and Buildings</p>
	<p>While site work is being carried out, a person must not to do anything on or in relation to the site (the supporting land) that removes the support provided by the supporting land to any other land (the supported land) or building (the supported building).</p> <p>For the purposes of this condition, supporting land includes the natural surface of the site, the subsoil of the site, any water beneath the site, and any part of the site that has been reclaimed.</p> <p>Notes:</p> <ul style="list-style-type: none"> • This condition does not authorise any trespass or encroachment upon any adjoining or supported land or building whether private or public. Where any underpinning, shoring, soil anchoring (temporary or permanent) or the like is considered necessary upon any adjoining or supported land by any person the Principal Contractor or Owner-builder must obtain: <ul style="list-style-type: none"> - the consent of the owners of such adjoining or supported land to trespass or encroach, or - an access order under the Access to Neighbouring Land Act 2000, or - an easement under section 88K of the Conveyancing Act 1919, or

	<ul style="list-style-type: none"> - an easement under section 40 of the Land and Environment Court Act 1979 as appropriate. • Section 177 of the Conveyancing Act 1919 creates a statutory duty of care in relation to support of land. Accordingly, a person has a duty of care not to do anything on or in relation to land being developed (the supporting land) that removes the support provided by the supporting land to any other adjoining land (the supported land). • Clause 17 of the Roads Regulation 2018 prohibits excavation in the vicinity of roads as follows: “Excavations adjacent to road - A person must not excavate land in the vicinity of a road if the excavation is capable of causing damage to the road (such as by way of subsidence) or to any work or structure on the road.” Separate approval is required under the Roads Act 1993 for any underpinning, shoring, soil anchoring (temporary) or the like within or under any road. Council will not give approval to permanent underpinning, shoring, soil anchoring within or under any road. • The encroachment of work or the like is a civil matter of trespass or encroachment and Council does not adjudicate or regulate such trespasses or encroachments except in relation to encroachments upon any road, public place, Crown land under Council’s care control or management, or any community or operational land as defined by the Local Government Act 1993. <p>Condition Reason: To ensure that the support of adjoining land is not removed.</p>
<p>F. 11.</p>	<p>Vibration Monitoring</p> <p>While site work is being carried out, vibration monitoring equipment must be installed and maintained, under the supervision of a professional engineer with expertise and experience in geotechnical engineering, between any potential source of vibration and any building identified by the professional engineer as being potentially at risk of movement or damage from settlement and/or vibration during the excavation and during the removal of any excavated material from the land being developed.</p> <p>If vibration monitoring equipment detects any vibration at the level of the footings of any adjacent building exceeding the peak particle velocity adopted by the professional engineer as the maximum acceptable peak particle velocity an audible alarm must activate such that the Principal Contractor and any sub-contractor are easily alerted to the event.</p> <p>Where any such alarm triggers all excavation works must cease immediately. Prior to the vibration monitoring equipment being reset by the professional engineer and any further work recommencing the event must be recorded and the cause of the event identified and documented by the professional engineer.</p> <p>Where the event requires, in the opinion of the professional engineer, any change in work practices to ensure that vibration at the level of the footings of any adjacent building does not exceed the peak particle velocity adopted by the professional engineer as the maximum acceptable peak particle velocity these changes in work practices must be documented and a written direction given by the professional engineer to the Principal Contractor and any sub-contractor clearly setting out required work practice.</p> <p>The Principal Contractor and any sub-contractor must comply with all work directions, verbal or written, given by the professional engineer.</p> <p>A copy of any written direction required by this condition must be provided to the Principal Certifier within 24 hours of any event.</p>

	<p>Where there is any movement in foundations such that damaged is occasioned to any adjoining building or such that there is any removal of support to supported land the professional engineer, Principal Contractor and any sub-contractor responsible for such work must immediately cease all work, inform the owner of that supported land and take immediate action under the direction of the professional engineer to prevent any further damage and restore support to the supported land.</p> <p>Notes:</p> <ul style="list-style-type: none"> • Professional engineer has the same mean as in Schedule 1 of the BCA. • Building has the same meaning as in section 1.4 of the Act i.e. “building includes part of a building and any structure or part of a structure....” • Supported land has the same meaning as in the Conveyancing Act 1919.
	<p>Condition Reason: To monitor and manage vibration impacts from development.</p>
<p>F. 12.</p>	<p>Erosion and Sediment Controls – Maintenance</p> <p>While site work is being carried out, water pollution, erosion, and sedimentation controls must be maintained in accordance with:</p> <ol style="list-style-type: none"> a) the Soil and Water Management Plan required under this consent, b) “Do it Right On Site, Soil and Water Management for the Construction Industry” and the accompanying factsheets published by the Southern Sydney Regional Organisation of Councils, and c) “Managing Urban Stormwater - Soils and Construction” 2004 published by the NSW Government (The Blue Book). <p>Where there is any conflict The Blue Book takes precedence.</p> <p>Notes:</p> <ul style="list-style-type: none"> • A failure to comply with this condition may result in penalty infringement notices, prosecution, notices and orders under the Act and/or the Protection of the Environment Operations Act 1997 without any further warning. It is a criminal offence to cause, permit or allow pollution. • Section 257 of the Protection of the Environment Operations Act 1997 provides that “the occupier of premises at or from which any pollution occurs is taken to have caused the pollution”. • Warning: Irrespective of this condition any person occupying the site may be subject to proceedings under the Protection of the Environment Operations Act 1997 where pollution is caused, permitted or allowed as the result of the occupation of the land being developed whether or not they actually cause the pollution. <p>Condition Reason: To prevent potential water pollution and dust nuisance.</p>
<p>F. 13.</p>	<p>Disposal of Site Water During Construction</p> <p>While site work is being carried out:</p> <ol style="list-style-type: none"> a) Prior to pumping any water into the road or public stormwater system, approval must be obtained from Council under section 138(1)(d) of the Roads Act 1993. b) Water pollution, as defined by the Protection of the Environment Operations Act 1997, must not occur as the result of the discharge to the road, public stormwater system or other place of any site water. c) That stormwater from any roof or other impervious areas is linked, via temporary downpipes and stormwater pipes, to a Council approved stormwater disposal system immediately upon completion of the roof installation or work creating other impervious areas.

	<p>Condition Reason: To ensure that adjoining and neighbouring land is not adversely affected by unreasonable overland flows of stormwater and that site water does not cause erosion and water pollution.</p>
<p>F. 14.</p>	<p>Site Cranes</p> <p>While site work is being carried out, site crane(s) and hoist(s) may be erected within the boundary of the land being developed subject to compliance with Australian Standards AS 1418, AS 2549 and AS 2550 and all relevant parts to these standards.</p> <p>Cranes must not swing or hoist over any public place unless the relevant approvals have been obtained under the Local Government Act 1993, Crown Lands Act 1989 or Roads Act 1993.</p> <p>The crane must not be illuminated outside approved working hours other than in relation to safety beacons required by the Civil Aviation Safety Authority under the Civil Aviation Act 1988 (Cth).</p> <p>No illuminated sign(s) must be erected upon or displayed upon any site crane.</p> <p>Notes:</p> <ul style="list-style-type: none"> • Where it is proposed to swing a crane over a public place a separate application to Council must be made under section 68 of the Local Government Act 1993 and obtain activity approval from Council prior to swinging or hoisting over the public place. • Where it is proposed to swing a crane over private land the consent of the owner of that private land is required. Alternatively, an access order under the Access to Neighbouring Land Act 2000 or easement under section 88K of the Conveyancing Act 1919 or section 40 of the Land and Environment Court Act 1979 as appropriate must be obtained. The encroachment of cranes or the like is a civil matter of trespass and encroachment. Council does not adjudicate or regulate such trespasses or encroachments. <p>Condition Reason: To ensure site cranes are used safely with the relevant approvals.</p>
<p>F. 15.</p>	<p>Check Surveys - boundary location, building location, building height, stormwater drainage system and flood protection measures relative to Australian Height Datum</p> <p>While site work is being carried out, a registered surveyor must carry out check surveys and provide survey certificates confirming the location of the building(s), ancillary works, flood protection works and the stormwater drainage system relative to the boundaries of the site and that the height of buildings, ancillary works, flood protection works and the stormwater drainage system relative to Australian Height Datum complies with this consent at the following critical stages.</p> <p>Work must not proceed beyond each of the following critical stages until compliance has been demonstrated to the Principal Certifier's satisfaction:</p> <ol style="list-style-type: none"> a) Upon the completion of foundation walls prior to the laying of any floor or the pouring of any floor slab and generally at damp proof course level. b) Upon the completion of formwork for floor slabs prior to the laying of any floor or the pouring of any concrete and generally at each storey. c) Upon the completion of formwork or framework for the roof(s) prior to the laying of any roofing or the pouring of any concrete roof. d) Upon the completion of formwork and steel fixing prior to pouring of any concrete for any ancillary structure, flood protection work, swimming pool or spa pool or the like.

	<p>e) Upon the completion of formwork and steel fixing prior to pouring of any concrete for driveways showing transitions and crest thresholds confirming that driveway levels match Council approved driveway crossing levels and minimum flood levels.</p> <p>f) Stormwater drainage Systems are in place prior to back filling over pipes confirming location, height and capacity of works.</p> <p>g) Flood protection measures are in place confirming location, height and capacity.</p> <p>Condition Reason: To ensure that development occurs in the location and at the height approved under this consent, which is critical to ensure that buildings are constructed to minimum heights for flood protection and maximum heights to protect views and the amenity of neighbours.</p>
<p>F. 16.</p>	<p>Placement and Use of Skip Bins</p> <p>While site work is being carried out, all waste storage containers, including but not limited to skip bins, must be stored within the site unless:</p> <p>a) Activity Approval has been issued by Council under section 68 of the Local Government Act 1993 to place the waste storage container in a public place; and</p> <p>b) where located on the road it is located only in a positions where a vehicle may lawfully park in accordance with the Australian Road Rules.</p> <p>Notes:</p> <ul style="list-style-type: none"> Waste storage containers must not be located on the footpath without a site specific activity approval. Where such site specific activity approval is granted a 1.5m wide clear path of travel is maintained free of any trip hazards. <p>Condition Reason: To ensure waste storage containers are appropriately located.</p>
<p>F. 17.</p>	<p>Prohibition of Burning</p> <p>While site work is being carried out, there must be no burning of any waste or other materials. The burning of copper chrome arsenate (CCA) or pentachlorophenol (PCP) treated timber is prohibited in all parts of NSW. All burning is prohibited in the Woollahra local government area.</p> <p>Notes:</p> <ul style="list-style-type: none"> Under the Protection of the Environment Operations (Clean Air) Regulation 2021 all burning (including burning of vegetation and domestic waste) is prohibited except with approval. No approval is granted under this consent for any burning. <p>Condition Reason: To ensure no burning of waste occurs.</p>
<p>F. 18.</p>	<p>Dust Mitigation</p> <p>While site work is being carried out, dust mitigation must be implemented in accordance with “Dust Control - Do it right on site” and the accompanying facts sheets published by the Southern Sydney Regional Organisation of Councils.</p> <p>This generally requires:</p> <p>a) Dust screens to all hoardings and site fences.</p> <p>b) All stockpiles or loose materials to be covered when not being used.</p> <p>c) All equipment, where capable, being fitted with dust catchers.</p> <p>d) All loose materials being placed bags before placing into waste or skip bins.</p> <p>e) All waste and skip bins being kept covered when not being filled or emptied.</p> <p>f) The surface of excavation work being kept wet to minimise dust.</p>

	<p>g) Landscaping incorporating trees, dense shrubs and grass being implemented as soon as practically possible to minimise dust.</p> <p>Notes:</p> <ul style="list-style-type: none"> • “Dust Control - Do it right on site” and the accompanying factsheets can be downloaded from Council’s website www.woollahra.nsw.gov.au • Special precautions must be taken when removing asbestos or lead materials from development sites. Additional information can be obtained from www.safework.nsw.gov.au and www.epa.nsw.gov.au. Other specific conditions and advice may apply. • Demolition and construction activities may affect local air quality and contribute to urban air pollution. The causes are dust, smoke and fumes coming from equipment or activities, and airborne chemicals when spraying for pest management. Precautions must be taken to prevent air pollution. <p>Condition Reason: To mitigate the impact of dust upon the amenity of the neighbourhood and prevent water pollution.</p>
<p>F. 19.</p>	<p>Compliance with Council’s Specification for Roadworks, Drainage and Miscellaneous Works, Road Works and, Work within the Road and Footway</p> <p>While site work is being carried out, all work carried out on assets which are under Council ownership or will revert to the ownership, care, control or management of Council in connection with the development to which this consent relates must comply with Council’s Specification for Roadworks, Drainage and Miscellaneous Works (2012).</p> <p>The person with the benefit of this consent must meet all costs associated with such works.</p> <p>This condition does not set aside the need to obtain relevant approvals under the Roads Act 1993 or Local Government Act 1993 for works within roads and other public places.</p> <p>Notes:</p> <ul style="list-style-type: none"> • A copy of Council’s Specification for Roadworks, Drainage and Miscellaneous Works can be downloaded from Council’s website www.woollahra.nsw.gov.au <p>Condition Reason: To ensure that any road, drainage, or miscellaneous works comply with Council’s specifications.</p>
<p>F. 20.</p>	<p>Site Waste Minimisation and Management – Demolition</p> <p>While site work is being carried out, in order to maximise resource recovery and minimise residual waste from demolition activities:</p> <ol style="list-style-type: none"> a) the provisions of the Site Waste Minimisation and Management Plan (SWMMP) are to be implemented at all times during the course of the work, b) an area is to be allocated for the storage of materials for use, recycling and disposal (giving consideration to slope, drainage, location of waterways, stormwater outlets, vegetation and access and handling requirements), c) separate collection bins and/or areas for the storage of residual waste are to be provided, d) the purpose and content of the bins and/or storage areas are to be clearly ‘signposted’, e) measures to prevent damage by the elements, odour, health risks and windborne litter are to be implemented, and f) site disturbance must be minimised, and unnecessary excavation limited.

	<p>When implementing the SWMMP the Applicant must ensure:</p> <ol style="list-style-type: none"> a) footpaths, public reserves and street gutters are not used as places to store demolition waste or materials of any kind without Council approval, b) any material moved offsite is transported in accordance with the requirements of the Protection of the Environment Operations Act 1997, c) waste is only transported to a place that can lawfully be used as a waste facility, d) generation, storage, treatment and disposal of hazardous waste and special waste (including asbestos) is conducted in accordance with relevant waste legislation administered by the NSW Environment Protection Authority, and relevant occupational health and safety legislation administered by SafeWork NSW, and e) evidence such as weighbridge dockets and invoices for waste disposal or recycling services are retained. <p>Notes:</p> <ul style="list-style-type: none"> • Materials that have an existing reuse or recycling market must not be disposed of in a land fill. Reuse and recycling opportunities are decreased when asbestos is not carefully removed and segregated from other waste streams. <p>Condition Reason: To maximise resource recovery and minimise residual waste from demolition activities.</p>
<p>F. 21.</p>	<p>Site Waste Minimisation and Management – Construction</p> <p>While site work is being carried out, in order to maximise resource recovery and minimise residual waste from construction activities:</p> <ol style="list-style-type: none"> a) the provisions of the Site Waste Minimisation and Management Plan (SWMMP) are to be implemented at all times during the course of the work, b) deliveries of materials must be arranged so that materials are delivered ‘as needed’ to prevent the degradation of materials through weathering and moisture damage, c) consideration must be given to returning excess materials to the supplier or manufacturer, d) an area must be allocated for the storage of materials for use, recycling and disposal (considering slope, drainage, location of waterways, stormwater outlets and vegetation), e) the purpose and content of the storage areas must be clearly ‘signposted’, f) contractors must be arranged for the transport, processing and disposal of waste and recycling and all contractors must be aware of the legal requirements for disposing of waste, g) separate collection bins or areas for the storage of residual waste must be promoted, h) measures to prevent damage by the elements, odour and health risks, and windborne litter must be implemented, i) site disturbance must be minimised and unnecessary excavation limited, j) all waste must be transported to a place that can lawfully be used as a waste facility, and k) records demonstrating lawful disposal of waste must be retained and kept readily accessible for inspection by regulatory authorities such as Council, the NSW EPA or SafeWork NSW. <p>Condition Reason: To maximise resource recovery and minimise residual waste from construction activities.</p>

F. 22.	<p>Shoring and Adequacy of Adjoining Property</p> <p>While site work is being carried out, the person having the benefit of the development consent must, at the person’s own expense:</p> <p>a) protect and support the adjoining premises from possible damage from the excavation</p> <p>For the purposes of section 4.17(11) of the Act, the following condition is prescribed in relation to a development consent for development that involves an excavation that extends below the level of the base of the footings of a building on adjoining land.</p> <p>Notes:</p> <ul style="list-style-type: none"> This condition does not apply if the person having the benefit of the development consent owns the adjoining land or the owner of the adjoining land has given consent in writing to that condition not applying. <p>Condition Reason: To protect and support the adjoining premises from possible damage from the excavation.</p>
F. 23.	<p>Asbestos Removal</p> <p>While site work is being carried out, all asbestos removal work must be carried out safely according to NSW work health and safety legislation.</p> <p>Where hazardous material, including bonded or friable asbestos has been identified in accordance with the conditions in Section B above, and such material must be demolished, disturbed and subsequently removed, all such works must comply with the following criteria:</p> <p>a) Be undertaken by contractors who hold a current SafeWork NSW “demolition licence” and a current SafeWork NSW “Class A licence” for friable asbestos removal.</p> <p>b) Be carried out in accordance with the relevant SafeWork NSW codes of practice.</p> <p>c) No asbestos products may be reused on the site.</p> <p>d) No asbestos laden skip or bins must be left in any public place.</p> <p>Notes:</p> <ul style="list-style-type: none"> Before starting work, a work site-specific permit approving each asbestos project must be obtained from SafeWork NSW. A permit will not be granted without a current SafeWork licence. All removal, repair or disturbance of or to asbestos material must comply with: <ul style="list-style-type: none"> Work Health and Safety Act 2011, Work Health and Safety Regulation 2017, SafeWork NSW “Code of Practice: How to Safely Remove Asbestos” (2016), and SafeWork NSW “Code of Practice: How to Manage and Control Asbestos in the Workplace” (2016). For more information go to the SafeWork NSW website on asbestos www.safework.nsw.gov.au/health-and-safety/safety-topics-a-z/asbestos, and www.safework.nsw.gov.au/law-and-policy/legislation-and-codes/codes-of-practice or call 131 050 <p>Condition Reason: To ensure the safe removal of asbestos and protect the health and safety of persons working on the site and the public.</p>

<p>F. 24.</p>	<p>Classification of Hazardous Waste</p> <p>While site work is being carried out, and prior to the exportation of hazardous waste (including hazardous fill or soil) from the site, the waste materials must be classified in accordance with the provision of the Protection of the Environment Operations Act 1997 and the NSW EPA Waste Classification Guidelines, Part1: Classifying Waste, 2014.</p> <p>Condition Reason: To ensure that where hazardous waste will be removed from a site an asbestos licensed contractor can definitively determine where the waste may be legally taken for disposal.</p>
<p>F. 25.</p>	<p>Disposal of Asbestos and Hazardous Waste</p> <p>While site work is being carried out, asbestos and hazardous waste, once classified in accordance with the hazardous waste classification condition must only be transported to waste facilities licensed to accept asbestos and appropriate classifications of hazardous waste.</p> <p>Condition Reason: To ensure that asbestos and other hazardous waste is disposed of lawfully under the Protection of the Environment Operations Act 1997 and relevant NSW EPA requirements.</p>
<p>F. 26.</p>	<p>Asbestos Removal Signage</p> <p>While site work is being carried out and when asbestos is being removed, standard commercially manufactured signs containing the words "DANGER ASBESTOS REMOVAL IN PROGRESS" measuring not less than 400mm x 300mm are to be erected in prominent visible positions on the site.</p> <p>Condition Reason: To ensure awareness of any hazard to the health and safety of persons working on the site and public.</p>
<p>F. 27.</p>	<p>Notification of Asbestos Removal</p> <p>While site work is being carried out, in addition to the requirements for licensed asbestos removalists to give written notice to SafeWork NSW, all adjoining properties and those opposite the development site must be notified in writing of the dates and times when asbestos removal is to be conducted.</p> <p>The notification is to identify the licensed asbestos removal contractor and include a contact person for the site together with telephone and facsimile numbers and email addresses.</p> <p>Condition Reason: To ensure that local residents are informed and have adequate contact details for incidents of asbestos removal.</p>
<p>F. 28.</p>	<p>Arborists Documentation and Compliance Checklist</p> <p>While site work is being carried out, the project arborist must provide written certification that all tree protection measures and construction techniques relevant to this consent have been implemented. Documentation for each site visit must include:</p> <p>a) a record of the condition of trees to be retained prior to and throughout development,</p>

- b) recommended actions to improve site conditions and rectification of non-compliance, and
- c) recommendations for future works which may impact the trees.

All compliance certification documents must be kept on site by the site Supervisor.

As a minimum the following intervals of site inspections must be made:

Stage of arboricultural inspection and supervision	Compliance documentation and photos must include
While site work is carried out	<ul style="list-style-type: none"> • The project arborist must supervise all demolition and excavation works within the Tree Protection Zones or specified distances of nominated trees listed in this consent. • New retaining wall within the TPZ of Tree No.11 shall be constructed as per 14.7 of the Arboricultural Impact Assessment Report & Tree Management Plan Ref.8796.1 written by Redgum, dated 25/09/2023. • Project Arborist to approve relocation of tree protection for landscaping. All landscaping works within the TPZ of trees to be retained are to be undertaken in consultation with the project Arborist to minimise the impact to trees. • Regular inspections as indicated in the Tree Management Plan.

Inspections and compliance documentation must be made by an arborist with AQF Level 5 qualifications.

Additional site visits must be made when required by site arborist and/or site foreman for ongoing monitoring/supervisory work.

Condition Reason: To ensure that all tree protection measures and construction techniques relevant to this consent have been implemented.

F. 29. Replacement/Supplementary trees which must be planted

While site work is being carried out, any replacement or supplementary tree must be grown in accordance with Tree stock for landscape use (AS 2303). The following replacement tree/s must be planted in deep soil landscaped area and maintained in a healthy and vigorous condition. If the replacement tree is found to be faulty, damaged, dying or dead before it attains a size whereby it becomes a prescribed tree in accordance with Chapter E.3 of Council's Development Control Plan, it must be replaced with another of the same species, which complies with the criteria outlined below.

Species/Type	Planting Location	Container Size/ Size of Tree (at planting)	Minimum Dimensions at Maturity (metres)
2 x <i>Lagerstroemia indica</i> (Crepe Myrtle)	Front	75L	8 x 5
4 x <i>Waterhousia floribunda</i> (Weeping Lillypilly)	Rear	75L	10 x 8

The project arborist must document compliance with the above condition.

	Condition Reason: To ensure the provision of appropriate replacement planting.		
F. 30.	Level changes in the vicinity of trees		
	While site work is being carried out, no level changes must occur within the specified radius from the trunks of the following trees.		
	Council Ref No	Species	Location
			Radius from centre of trunk (metres)
	6	<i>Cupaniopsis anacardioides</i> (Tuckeroo)	Rear at 618 OSHR
8	<i>Syzygium</i> sp. (Lillypilly)	Rear at 620 OSHR	
9	<i>Brachychiton acerifolius</i> (Illawarra Flame tree)	Rear at 622 OSHR	
11	<i>Syzygium</i> sp. (Lillypilly)	Rear at 620 OSHR	
13	<i>Cupressocyparis leylandii</i> (Leyland Cypress)	Rear at 624 OSHR	
	The project arborist must document compliance with the above condition.		
	Condition Reason: To ensure level changes would not adversely impact upon the health of existing trees.		
F. 31.	Hand excavation within tree root zones		
	While site work is being carried out, demolition of underground structures such as existing footings and approved excavation undertaken within the specified radius from the trunks of the following trees must be carried out by hand.		
	Council Ref No	Species	Location
			Radius from centre of trunk (metres)
	6	<i>Cupaniopsis anacardioides</i> (Tuckeroo)	Rear at 618 OSHR
8	<i>Syzygium</i> sp. (Lillypilly)	Rear at 620 OSHR	
9	<i>Brachychiton acerifolius</i> (Illawarra Flame tree)	Rear at 622 OSHR	
11	<i>Syzygium</i> sp. (Lillypilly)	Rear at 620 OSHR	
13	<i>Cupressocyparis leylandii</i> (Leyland Cypress)	Rear at 624 OSHR	
	Small hand tools such as mattocks or using compressed air or water jetting only must be used. Roots with a diameter equal to or in excess of 50mm must not be severed or damaged unless approved in writing and documented by the project arborist.		
	Mechanical excavation is permitted beyond this radius when root pruning by hand along the hand excavated perimeter line is completed. Exposed roots to be retained must be covered with mulch or a geotextile fabric and kept in a moist condition and prevented from drying out.		
	All root pruning must be undertaken in accordance with the Australian Standard 4373 "Pruning of Amenity Trees" and carried out by a qualified Arborist (minimum qualification of Australian Qualification Framework Level 5 or recognised equivalent).		
	The project arborist must document compliance with the above condition.		

	<p>Condition Reason: To ensure demolition and excavation works would not adversely impact upon the health of existing trees.</p>								
F. 32.	<p>Installation of stormwater pipes and pits in the vicinity of trees</p> <p>While site work is being carried out, excavation for the installation of stormwater pipes and pits within the specified radius from the trunks of the following trees must be carried out by hand.</p> <table border="1"> <thead> <tr> <th>Council Ref No</th> <th>Species</th> <th>Location</th> <th>Radius from centre of trunk (metres)</th> </tr> </thead> <tbody> <tr> <td>6</td> <td><i>Cupaniopsis anacardioides</i> (Tuckeroo)</td> <td>Rear at 618 OSHR</td> <td>2.5</td> </tr> </tbody> </table> <p>Any roots equal to or greater than 50mm diameter uncovered for the installation of stormwater pipes and pits must not be severed and remain in situ bridging across the excavated trench. Pipes must be guided under any roots equal to or greater than 50mm bridging across excavated trenches. Stormwater pits must be positioned so that no roots equal to or greater than 50mm diameter are severed.</p> <p>The project arborist must document compliance with the above condition.</p> <p>Condition Reason: To ensure the installation of the stormwater works would not adversely impact upon the health of existing trees.</p>	Council Ref No	Species	Location	Radius from centre of trunk (metres)	6	<i>Cupaniopsis anacardioides</i> (Tuckeroo)	Rear at 618 OSHR	2.5
Council Ref No	Species	Location	Radius from centre of trunk (metres)						
6	<i>Cupaniopsis anacardioides</i> (Tuckeroo)	Rear at 618 OSHR	2.5						

G. BEFORE ISSUE OF AN OCCUPATION CERTIFICATE

G. 1.	<p>Occupation Certificate (section 6.9 of the Act)</p> <p>A person must not commence occupation or use of the whole or any part of a new building (within the meaning of section 6.10 of the Act) unless an occupation certificate has been issued in relation to the building or part.</p> <p>Notes:</p> <ul style="list-style-type: none"> New building includes an altered portion of, or an extension to, an existing building. <p>Condition Reason: To ensure the building is suitable to occupy.</p>
G. 2.	<p>Amenity Landscaping</p> <p>Before the issue of any occupation certificate, all approved amenity landscaping (screen planting, soil stabilisation planting, etc.) and replacement/supplementary tree planting must be installed in accordance with the approved plans and documents and any relevant conditions of consent.</p> <p>Condition Reason: To ensure that the environmental impacts of the development are mitigated by approved landscaping prior to the occupation of the development.</p>

<p>G. 3.</p>	<p>Commissioning and Certification of Systems and Works</p> <p>Before the issue of any occupation certificate, works-as-executed (WAE) plans prepared by a registered surveyor, compliance certificates, and evidence of suitability in accordance with Part A5G1 of the BCA confirming that the works, as executed and as detailed, comply with the requirement of this consent, the Act, the Regulations, any relevant construction certificate, the BCA and relevant Australian Standards must be submitted to the satisfaction of the Principal Certifier.</p> <p>Works-as-executed plans, compliance certificates, and evidence of suitability in accordance with Part A5G1 of the BCA must include, but may not be limited to:</p> <ol style="list-style-type: none"> a) Certification from the supervising professional engineer that the requirement of the Geotechnical/Hydrogeological conditions and report recommendations were implemented and satisfied during development work. b) All flood protection measures. c) All garage/car park/basement car park, driveways and access ramps comply with Australian Standard AS 2890.1: Off-Street car parking. d) All stormwater drainage and storage systems. e) All mechanical ventilation systems. f) All hydraulic systems. g) All structural work. h) All acoustic attenuation work. i) All waterproofing. j) Such further matters as the Principal Certifier may require. <p>Notes:</p> <ul style="list-style-type: none"> • The PC may require any number of WAE plans, certificates, or other evidence of suitability as necessary to confirm compliance with the Act, Regulation, development standards, BCA, and relevant Australia Standards. As a minimum WAE plans and certification is required for stormwater drainage and detention, mechanical ventilation work, hydraulic services (including but not limited to fire services). • The PC must submit to Council, with any occupation certificate, copies of WAE plans, compliance certificates and evidence of suitability in accordance with Part A5G1 of the BCA upon which the PC has relied in issuing any occupation certificate. <p>Condition Reason: To ensure that systems and works as completed meet development standards as defined by the Act, comply with the BCA, and this consent, and to ensure a public record of works as executed is maintained.</p>
<p>G. 4.</p>	<p>Commissioning and Certification of Public Infrastructure Works</p> <p>Before the issue of any occupation certificate, certification from a professional engineer that all public infrastructure works have been executed in compliance with this consent and with Council’s Specification for Roadworks, Drainage and Miscellaneous Works (2012) must be submitted to the satisfaction of Council, and the Principal Certifier must be provided with correspondence from Council to this effect.</p> <p>The certification must be supported with works-as-executed engineering plans and a survey report detailing all finished reduced levels.</p> <p>Condition Reason: To ensure that any road, drainage, or miscellaneous works have been completed in accordance with Council’s specifications to the satisfaction of Council.</p>

<p>G. 5.</p>	<p>State Environmental Planning Policy (Housing) 2021 – Design Verification Statement</p> <p>Before the issue of any occupation certificate, as required under clause 43 of the Development Certification and Fire Safety Regulation, the Principal Certifier must have received a design statement from a qualified designer.</p> <p>A design statement means a statement by a qualified designer verifying that the development achieves the design quality shown in the plans and specifications for which the construction certificate was issued, having regard to the design quality principles in State Environmental Planning Policy (Housing) 2021: Chapter 4—Design of Residential Apartment Development.</p> <p>Notes:</p> <ul style="list-style-type: none"> • Although a Principal Certifier may under clause 73 of the Development Certification and Fire Safety Regulation be satisfied to any matter that relates to the external finish of a building, clause 43 of the Development Certification and Fire Safety Regulation overrides the Principal Certifier’s powers under clause 73. • Qualified designer means a person registered as an architect in accordance with the Architects Act 2003. <p>Condition Reason: To ensure residential flat building development achieves the required quality of design.</p>
<p>G. 6.</p>	<p>Certification of Electric Vehicle Charging System</p> <p>Before the issue of any occupation certificate, certification by a suitably qualified person that the electric vehicle charger points and/or electric vehicle circuitry, has been installed in accordance with the construction certificate plans and specifications as required by Condition D.18 must be submitted to the satisfaction of the Principal Certifier.</p> <p>Condition Reason: To ensure the certification of the electric vehicle charging system.</p>
<p>G. 7.</p>	<p>Fulfilment of BASIX Commitments – Clause 44 of the Development Certification and Fire Safety Regulation</p> <p>Before the issue of any occupation certificate, all BASIX commitments must be effected in accordance with the BASIX certificate No. 1418155M_02.</p> <p>Notes:</p> <ul style="list-style-type: none"> • Clause 44 of the Development Certification and Fire Safety Regulation applies to an occupation certificate if a relevant BASIX certificate requires a certifier to monitor fulfilment of a commitment listed in the certificate in relation to a building. The certifier must not issue an occupation certificate for the building unless the commitment has been fulfilled. <p>Condition Reason: To ensure that sustainable building commitments, to reduce water and energy consumption, are fulfilled prior to the occupation.</p>
<p>G. 8.</p>	<p>Landscaping</p> <p>Before the issue of any occupation certificate, the Principal Certifier and Council must be provided with a works-as-executed landscape plan and certification from a qualified landscape architect/designer, horticulturist and/or arborist as applicable to the effect that the landscaping and replacement/supplementary tree planting works comply with this consent.</p>

	<p>Condition Reason: To ensure that all landscaping work is completed prior to occupation.</p>
G. 9.	<p>Removal of Ancillary Works and Structures</p>
	<p>Before the issue of any occupation certificate for the whole of the building, The following articles must be removed from the land and any adjoining public place:</p> <ul style="list-style-type: none"> a) the site sign, b) ablutions, c) hoarding, d) scaffolding, and e) waste materials, matter, article or thing.
	<p>Condition Reason: To ensure that all ancillary matter is removed prior to occupation.</p>
G. 10.	<p>Works within Public Land (including Council, State or Federal owned land or property)</p>
	<p>Before the issue of any occupation certificate, the following works within public land, whether new/existing/renewed must be completed to the satisfaction of Council, in compliance with Council's Specification for Roadworks, Drainage and Miscellaneous Works (2012) unless expressly provided otherwise by these conditions at the person with the benefit of this consents expense:</p> <ul style="list-style-type: none"> a) stormwater pipes, pits, structures and connections to public stormwater systems within the road, b) driveways and vehicular crossings, c) renew/new retaining structures, d) overhang structures, e) encroachments or occupation or alienation of public land or property, f) removal of redundant driveways and any other structure, g) new footpaths, pathways, walkways, or dunny lanes, h) relocation of existing power/light pole, if applicable, i) relocation/provision of street signs, if applicable, j) new or replacement street trees, if applicable, k) verge landscape items, where a grass verge exists, the balance of the area between the footpath and the kerb or site boundary over the full frontage of the proposed development must be turfed. The grass verge must be constructed to contain a uniform minimum 75mm of friable growing medium and have a total cover of turf predominant within the street, l) new or reinstated kerb and guttering within the road, and m) new or reinstated road surface pavement within the road. <p>Notes:</p> <ul style="list-style-type: none"> • When determining whether the works within public land are satisfactory, Council will consider the ownership, construction quality, maintenance, operations, and public utility of such item/s. • Security held by Council under section 4.17(6) of the Act will not be released until compliance has been achieved with this condition. An application for the refund of security must be submitted with the occupation certificate to Council. This form can be downloaded from Council's website www.woollahra.nsw.gov.au or obtained from Council's customer service centre.
	<p>Condition Reason: To ensure road, drainage and miscellaneous works are completed to the satisfaction of Council prior to occupation.</p>

<p>G. 11.</p>	<p>Dilapidation Report for Public Infrastructure Works</p>
	<p>Before the issue of an occupation certificate for the whole of the building, a follow up dilapidation report, prepared by a chartered professional engineer, on Council’s infrastructure within and near the development site upon completion of the work must be submitted to Council.</p> <p>The dilapidation report must include:</p> <ol style="list-style-type: none"> a) photographs showing any existing damage to the road pavement fronting the site, b) photographs showing any existing damage to the kerb and gutter fronting the site, c) photographs showing any existing damage to the footway including footpath pavement fronting the site, d) photographs showing any existing damage to retaining walls within the footway or road, e) photographs showing any existing damage to street signs, heritage name plates, and historical items, f) the full name and signature of the professional engineer. <p>The reports are to be supplied in both paper copy and electronic format in PDF. Photographs are to be in colour, digital and date stamped.</p> <p>Before the issue of an occupation certificate for the whole building, written correspondence must be obtained from Council attesting to this condition being appropriately satisfied, and be provided to the Principal Certifier.</p> <p>Notes:</p> <ul style="list-style-type: none"> • If the dilapidation report required by this condition is not provided and damage is occasioned to public assets adjoining the site Council will deduct from security any costs associated with remedying, repairing or replacing damaged public infrastructure. Nothing in this condition prevents Council making any claim against security held for this purpose.
	<p>Condition Reason: To ensure that any damage to public infrastructure is identified and rectified prior to the occupation of the whole building.</p>
<p>G. 12.</p>	<p>Positive Covenant and Works-As-Executed Certification of Stormwater Systems</p>
	<p>Before the issue of an occupation certificate for the whole of the building, and on the completion of construction work, stormwater drainage works are to be certified by a professional engineer with works-as-executed drawings supplied to the Principal Certifier detailing:</p> <ol style="list-style-type: none"> a) compliance with conditions of development consent relating to stormwater, b) the structural adequacy of the rainwater retention and reuse system, c) that all below ground structures are fully tanked and subsoil drainage/seepage water is NOT collected and discharged into the kerb and gutter in accordance with the approved stormwater drawings, d) that a rainwater tank with minimum storage of 90m³ has been constructed in accordance with the approved stormwater plans, e) that a pumpout system has been constructed in accordance with the approved stormwater plans, f) that the as-built rainwater retention and reuse system has been plumbed into all toilet, laundry and garden irrigation etc., g) that the storage capacity of the on-site absorption systems have been designed based on the catchment area and for the 5% AEP storm event, h) that a pump out system with minimum storage capacity has been installed to comply with AS3500.3,

- i) that any required stormwater treatment systems have been constructed in accordance with the approved construction stormwater plans and that the system meets the water quality targets stipulated in the Council's DCP,
- j) that all charged systems have been constructed in accordance with the approved stormwater drawings,
- k) that only one stormwater outlet pipe has been constructed in accordance with the approved stormwater plans,
- l) that the works have been constructed in accordance with the approved design and will provide the retention storage volume and attenuation in accordance with the submitted calculations,
- m) pipe invert levels and surface levels to Australian Height Datum, and
- n) contours indicating the direction in which water will flow over land should the capacity of the pit be exceeded in a storm event exceeding design limits.

A positive covenant under section 88E of the Conveyancing Act 1919 must be created on the title of the subject property, providing for the on-going maintenance of the rainwater retention and reuse system, on-site absorption systems, stormwater treatment systems, charged systems and including any pumps and sumps incorporated in the development.

The wording of the Instrument must be in accordance with Council's standard format and the Instrument must be registered with the NSW Land Registry Services. The person with the benefit of this consent must reimburse Council's reasonable expenses incurred in the drafting, negotiation and registration of the covenant

Notes:

- The required wording of the Instrument can be downloaded from Council's website www.woollahra.nsw.gov.au. The PC must supply a copy of the Works As Executed plans to Council together with the occupation certificate.
- The occupation certificate for the whole of the building must not be issued until this condition has been satisfied.

Condition Reason: To ensure the certification and ongoing maintenance of the stormwater system prior to the occupation of the whole building.

G. 13. Arborists Documentation and Compliance Checklist – Prior to any occupation certificate

Before the issue of any occupation certificate, the project arborist must provide written certification that all tree protection measures and construction techniques relevant to this consent have been implemented. Documentation for each site visit must include:

- a) A record of the condition of trees to be retained prior to and throughout development.
- b) Recommended actions to improve site conditions and rectification of non-compliance.
- c) Recommendations for future works which may impact the trees.

All compliance certification documents must be kept on site by the site Supervisor.

As a minimum the following intervals of site inspections must be made:

Stage of arboricultural inspection and supervision	Compliance documentation and photos must include
Prior to the issue of any occupation certificate	Ensure all trees conditioned to be planted as part of this consent have been planted in accordance with the details prescribed in this consent.

	<p>Inspections and compliance documentation must be made by an arborist with AQF Level 5 qualifications.</p> <p>Additional site visits must be made when required by site arborist and/or site foreman for ongoing monitoring/supervisory work.</p> <p>Condition Reason: To ensure that all tree protection measures and construction techniques relevant to this consent are implemented.</p>				
<p>G. 14.</p>	<p>Arborists Documentation and Compliance Checklist – Prior to an occupation certificate for the whole building</p> <p>Before the issue of any occupation certificate for the whole of the building, the project arborist must provide written certification that all tree protection measures and construction techniques relevant to this consent have been implemented. Documentation for each site visit must include:</p> <ol style="list-style-type: none"> a) A record of the condition of trees to be retained prior to and throughout development. b) Recommended actions to improve site conditions and rectification of non-compliance. c) Recommendations for future works which may impact the trees. <p>All compliance certification documents must be kept on site.</p> <p>As a minimum the following intervals of site inspections must be made:</p> <table border="1" data-bbox="316 1052 1461 1456"> <thead> <tr> <th data-bbox="316 1052 662 1142">Stage of arboricultural inspection and supervision</th> <th data-bbox="662 1052 1461 1142">Compliance documentation and photos must include</th> </tr> </thead> <tbody> <tr> <td data-bbox="316 1142 662 1456"> Before the issue of any occupation certificate for the whole of the building </td> <td data-bbox="662 1142 1461 1456"> <ul style="list-style-type: none"> • The project arborist must supervise the dismantling of tree protection measures • After all demolition, construction and landscaping works are complete the project Arborist must assess that the subject trees have been retained in the same condition and vigour. If changes to condition are identified the project Arborist must provide recommendations for remediation. </td> </tr> </tbody> </table> <p>Inspections and compliance documentation must be made by an arborist with AQF Level 5 qualifications.</p> <p>Additional site visits must be made when required by site arborist and/or site foreman for ongoing monitoring/supervisory work.</p> <p>Condition Reason: To ensure that all tree protection measures and construction techniques relevant to this consent are implemented.</p>	Stage of arboricultural inspection and supervision	Compliance documentation and photos must include	Before the issue of any occupation certificate for the whole of the building	<ul style="list-style-type: none"> • The project arborist must supervise the dismantling of tree protection measures • After all demolition, construction and landscaping works are complete the project Arborist must assess that the subject trees have been retained in the same condition and vigour. If changes to condition are identified the project Arborist must provide recommendations for remediation.
Stage of arboricultural inspection and supervision	Compliance documentation and photos must include				
Before the issue of any occupation certificate for the whole of the building	<ul style="list-style-type: none"> • The project arborist must supervise the dismantling of tree protection measures • After all demolition, construction and landscaping works are complete the project Arborist must assess that the subject trees have been retained in the same condition and vigour. If changes to condition are identified the project Arborist must provide recommendations for remediation. 				

H. OCCUPATION AND ONGOING USE

<p>H. 1.</p>	<p>Provision of Off-street Public and Visitor Parking</p> <p>During the occupation and ongoing use, in compliance with AS 2890.1: Parking facilities - Off-street car parking, unimpeded public access to off-street parking must be maintained as follows:</p>
---------------------	--

	<table border="1" data-bbox="316 197 1305 371"> <thead> <tr> <th data-bbox="316 197 879 232">Use</th> <th data-bbox="879 197 1305 232">Number of spaces</th> </tr> </thead> <tbody> <tr> <td data-bbox="316 232 879 268">Car Parking (residents)</td> <td data-bbox="879 232 1305 268">16</td> </tr> <tr> <td data-bbox="316 268 879 304">Car Parking (residents)</td> <td data-bbox="879 268 1305 304">2</td> </tr> <tr> <td data-bbox="316 304 879 340">Bicycle Parking</td> <td data-bbox="879 304 1305 340">12</td> </tr> <tr> <td data-bbox="316 340 879 371">Motorbike Parking</td> <td data-bbox="879 340 1305 371">2</td> </tr> </tbody> </table> <p data-bbox="316 407 400 439">Notes:</p> <ul data-bbox="316 439 1437 629" style="list-style-type: none"> • Where there is a potential for the trespass of private motor vehicles upon private parking servicing the owner of the site may seek to enter into a free parking area agreement with Council. Council may under such agreement enforce parking restrictions under section 650 of the Local Government Act 1993. • Further information can be obtained from Council's Compliance Team by calling 9391 7000 or from the Office of Local Government at www.olg.nsw.gov.au or call 4428 4100. <p data-bbox="316 663 1241 694">Condition Reason: To ensure adequate on-site parking is maintained.</p>	Use	Number of spaces	Car Parking (residents)	16	Car Parking (residents)	2	Bicycle Parking	12	Motorbike Parking	2
Use	Number of spaces										
Car Parking (residents)	16										
Car Parking (residents)	2										
Bicycle Parking	12										
Motorbike Parking	2										
<p data-bbox="181 725 284 757">H. 2.</p>	<p data-bbox="316 725 831 757">Maintenance of BASIX Commitments</p> <p data-bbox="316 797 1422 864">During the occupation and ongoing use, all BASIX commitments must be maintained in accordance with the BASIX Certificate No. 1418155M_02.</p> <p data-bbox="316 898 1374 999">This condition affects successors in title with the intent that environmental sustainability measures must be maintained for the life of development under this consent.</p> <p data-bbox="316 1032 1406 1099">Condition Reason: To ensure the approved environmental sustainability measures are maintained for the life of development.</p>										
<p data-bbox="181 1133 284 1164">H. 3.</p>	<p data-bbox="316 1133 719 1164">Maintenance of Landscaping</p> <p data-bbox="316 1205 1445 1272">During the occupation and ongoing use, all landscaping must be maintained in general accordance with this consent.</p> <p data-bbox="316 1305 1422 1373">This condition does not prohibit the planting of additional trees or shrubs subject that they are native species endemic to the immediate locality.</p> <p data-bbox="316 1406 400 1438">Notes:</p> <ul data-bbox="316 1438 1430 1686" style="list-style-type: none"> • This condition also acknowledges that development consent is not required to plant vegetation and that over time additional vegetation may be planted to replace vegetation or enhance the amenity of the locality. • Owners must have regard to the amenity impact of trees upon the site and neighbouring land. Further, drought proof vegetation being native species endemic to the immediate locality is encouraged. Suggested native species endemic to the immediate locality are listed in the brochure "Local Native Plants for Sydney's Eastern Suburbs" published by Woollahra, Waverley, Randwick and Botany Bay Councils. <p data-bbox="316 1720 1414 1787">Condition Reason: To ensure that the landscaping design intent is not eroded over time by the removal of landscaping or inappropriate exotic planting.</p>										
<p data-bbox="181 1821 284 1852">H. 4.</p>	<p data-bbox="316 1821 1398 1888">Ongoing Maintenance of the Rainwater Retention and Reuse System, On-site Absorption Systems, Stormwater Treatment Systems and Pump Out System</p> <p data-bbox="316 1921 1382 1989">During the occupation and ongoing use, in accordance with this condition and any positive covenant, the person with the benefit of this consent must:</p> <ol data-bbox="316 1989 1445 2056" style="list-style-type: none"> Permit stormwater to be temporarily detained, retained and reused by the System; Keep the system clean and free of silt rubbish and debris, 										

	<p>c) Maintain renew and repair as reasonably required from time to time the whole or part of the system so that it functions in a safe and efficient manner.</p> <p>d) Carry out the matters referred to in paragraphs (b) and (c) at the Owners expense.</p> <p>e) Not make any alterations to the system or elements thereof without prior consent in writing of the Council and not interfere with the system or by its act or omission cause it to be interfered with so that it does not function or operate properly.</p> <p>f) Permit the Council or its authorised agents from time to time upon giving reasonable notice (but at any time and without notice in the case of an emergency) to enter and inspect the land with regard to compliance with the requirements of this covenant.</p> <p>g) Comply with the terms of any written notice issued by Council in respect to the requirements of this clause within the time stated in the notice.</p> <p>h) Where the Owner fails to comply with the Owner’s obligations under this covenant, permit the Council or its agents at all times and on reasonable notice at the Owner’s cost to enter the land with equipment, machinery or otherwise to carry out the works required by those obligations.</p> <p>The owner:</p> <p>a) Indemnifies the Council from and against all claims, demands, suits, proceedings or actions in respect of any injury, damage, loss, cost, or liability (Claims) that may be sustained, suffered, or made against the Council arising in connection with the performance of the Owner’s obligations under this covenant except if, and to the extent that, the Claim arises because of the Council’s negligence or default; and</p> <p>b) releases the Council from any Claim it may have against the Council arising in connection with the performance of the Owner’s obligations under this covenant except if, and to the extent that, the Claim arises because of the Council’s negligence or default.</p> <p>Notes:</p> <ul style="list-style-type: none"> This condition is supplementary to the owner(s) obligations and Council’s rights under any positive covenant.
	<p>Condition Reason: To ensure that owners are aware of maintenance requirements for their stormwater systems.</p>
<p>H. 5.</p>	<p>Annual Fire Safety Statements (Class 1b to 9c buildings inclusive)</p> <p>During the occupation and ongoing use, each year, an annual fire safety statement must be provided to Council and the Commissioner of Fire and Rescue NSW. The annual fire safety statement must be prominently displayed in the building.</p> <p>Notes:</p> <ul style="list-style-type: none"> essential fire safety measure has the same meaning as in Schedule 2 of the Development Certification and Fire Safety Regulation. annual fire safety statement has the same meaning as in clause 88 of the Development Certification and Fire Safety Regulation. Visit Council’s website for additional information in relation to fire safety www.woollahra.nsw.gov.au. <p>Condition Reason: To ensure public safety.</p>
<p>H. 6.</p>	<p>Outdoor Lighting – Residential</p> <p>During the occupation and ongoing use, outdoor lighting must comply with AS/NZS 4282: Control of the obtrusive effects of outdoor lighting. The maximum luminous intensity from each luminare and threshold limits must not exceed the level 1 control relevant under tables in AS/NZS 4282.</p>

	<p>Condition Reason: To protect the amenity of neighbours and limit the obtrusive effects of outdoor lighting.</p>
H. 7.	<p>Outdoor Lighting – Roof Terraces</p>
	<p>During the occupation and ongoing use, outdoor lighting must comply with AS/NZS 4282: Control of the obtrusive effects of outdoor lighting. The maximum luminous intensity from each luminare and threshold limits must not exceed the level 1 control relevant under tables in AS/NZS 4282.</p> <p>All lighting to be installed on the roof terrace will be recessed lights or will be surface wall/balustrade mounted lights at a maximum height of 600mm above the finished floor level of the roof terrace.</p> <p>Notes:</p> <ul style="list-style-type: none"> Council may consider, subject to an appropriate Section 4.55 Application, relaxation of this condition where it can be demonstrated, by expert report, that the level of lighting in the existing area already exceeds the above criteria, where physical shielding is present or physical shielding is reasonably possible.
	<p>Condition Reason: To protect the amenity of neighbours and limit the obtrusive effects of outdoor lighting.</p>
H. 8.	<p>Waste Management – Residential</p>
	<p>During the occupation and ongoing use, waste management must comply with the approved site waste minimisation and management plan (SWMMP) and with Woollahra DCP 2015, Chapter E5–Waste Management.</p> <p>The waste and recycling bins/crates must be placed on the footpath for collection, but not earlier than 12 hours prior to the designated collection time.</p> <p>The occupier of the site must remove waste and recycling bins/crates from the footpath within 12 hours of being emptied by Council’s waste service and they must be stored within the site in the approved waste storage area.</p> <p>No commercial waste must be placed within residential waste and recycling bins/crates.</p> <p>Notes: For further residential wastes management policy information go to www.woollahra.nsw.gov.au</p>
	<p>Condition Reason: To ensure that the provisions of the approved SWMMP and Woollahra DCP are complied with during the ongoing operations of the development.</p>
H. 9.	<p>Noise from Mechanical Plant and Equipment</p>
	<p>During the occupation and ongoing use, the noise level measured at any boundary of the site at any time while the mechanical plant and equipment is operating must not exceed the background noise level. Where noise sensitive receivers are located within the site, the noise level is measured from the nearest strata, stratum or community title land and must not exceed background noise level at any time.</p> <p>The background noise level is the underlying level present in the ambient noise, excluding the subject noise source, when extraneous noise is removed. For assessment purposes the background noise level is the LA90, 15 minute level measured by a sound level meter.</p>

	<p>Notes:</p> <ul style="list-style-type: none"> Words in this condition have the same meaning as in the Noise Policy for Industry (2017) www.epa.nsw.gov.au/your-environment/noise/industrial-noise/noise-policy-for-industry-(2017) and Noise Guide for Local Government (2013) www.epa.nsw.gov.au/your-environment/noise/regulating-noise/noise-guide-local-government
	<p>Condition Reason: To protect the amenity of the neighbourhood.</p>
H. 10.	<p>Parking Permits</p>
	<p>During the occupation and ongoing use, future tenants and residents of the proposed development will not be eligible for resident or visitor parking permits.</p>
	<p>Condition Reason: To minimise the impact of the development upon on street car parking.</p>

SUBDIVISION WORK

I. BEFORE ISSUE OF A SUBDIVISION WORKS CERTIFICATE

Nil

J. BEFORE SUBDIVISION WORK COMMENCES

Nil

K. BEFORE ISSUE OF A SUBDIVISION CERTIFICATE

Nil

LAND SUBDIVISION

L. BEFORE ISSUE OF A SUBDIVISION CERTIFICATE

Nil

STRATA SUBDIVISION

M. BEFORE ISSUE OF A STRATA CERTIFICATE

Nil

Note: In accordance with the Woollahra Local Planning Panel Operational Procedures the votes are recorded on this planning matter.

For the Motion

Peter Brennan
 Larissa Ozog
 David Ryan
 Malcolm Young

4/0

Against the Motion

Nil

ITEM No.	D2
FILE No.	DA411/2023/1
ADDRESS	54 Cranbrook Road Bellevue Hill
PROPOSAL	Substantial alterations and additions to the existing residential flat building (effectively a new residential flat building) including an increase in the number of units from 3 to 6, the provision of a basement car park and a new level above the existing building, landscaping and site works

Reasons for Decision

The Panel has undertaken a site inspection, considered any submissions and reviewed the assessment report prepared by Council officers that addresses the relevant matters detailed in Section 4.15 of the Environmental Planning and Assessment Act 1979.

For the reasons generally in the assessment report, the Panel is satisfied that the application be refused for the reasons set out below with the addition of reasons for refusal No. 11. (Height of Building).

Resolved: Pursuant to Section 4.16 of the Environmental Planning and Assessment Act 1979

THAT the Woollahra Local Planning Panel, exercising the functions of Council, as the consent authority, refuse development consent to Development Application No. 411/2023/1 for substantial alterations and additions to the existing residential flat building (effectively a new residential flat building) including an increase in the number of units from 3 to 6, the provision of a basement car park and a new level above the existing building, landscaping and site works on land at 54 Cranbrook Road Bellevue Hill, for the following reasons:

1. Insufficient deep soil landscaping

The proposal involves a significant non-compliance with the deep soil landscaping control under Section B3.7.1 (landscape area and private open space) of the WDCP 2015:

- C2 requires that 35% (248m²) of the site area is provided as deep soil landscaped area.
- C3 requires at least 40% (34.5m²) of the front setback area comprises deep soil landscaping.

As such, the proposal is contrary to the following objectives:

- Aim (g) to protect and enhance amenity and the natural environment (Part 1.2(2) of the Woollahra LEP 2014)
- O1 To respect and enhance the streetscape character and key elements of the precinct (B1.7.2 under WDCP 2015).
- O8 To retain and reinforce the green setting of mature street trees, private trees and garden plantings and minimise hard stand areas (B1.7.2 under WDCP 2015).
- O1 To ensure that the areas outside the floorplate contribute to the desired future character of the location (B3.7.1 under WDCP 2015).

The above non-compliances are largely a result of an unsatisfactory basement and driveway design that does not allow for provision of deep soil landscaping within the side setbacks. The basement access ramp should be setback from all boundaries to provide opportunities for deep soil landscaping.

2. Tree removal/insufficient information within the Arboricultural Impact Assessment

The submitted Arboricultural Impact Assessment provides insufficient information in relation to root mapping, tree protection and tree retention as follows:

- The report recommends to undertake root mapping investigations to Tree Nos. 1, 2, 5, 9, 10, 14 & 15, however that information has not been provided with this application.

- There is a large *Ficus microcarpa* var. 'Hillii' (Hills Weeping Fig) (Tree 1) within the road reserve and proposed to be retained. The plans show a proposed driveway and retaining wall requiring excavation within the TPZ and within the SRZ of the tree. As per 3.3.3 of the AS 4970-2009 *Protection of trees on development sites*, if the proposed encroachment is greater than 10% of the TPZ or inside the SRZ, the project arborist must demonstrate that the tree(s) would remain viable. However, the arborist has provided no information to confirm if the proposed works can be carried out and the tree successfully retained.
Additionally, significant pruning of large diameter branches is likely required to facilitate construction. However, the AIA has not assessed the potential impact of these works.
- There are two large *Lophostemon confertus* (Brush Box) (Trees 9 and 10) located on the adjacent property at 52 Cranbrook Road. The plans show a proposed driveway, parking areas and other structures requiring excavation within the TPZ and within the SRZ of the trees. As per 3.3.3 of the AS 4970-2009 *Protection of trees on development sites*, if the proposed encroachment is greater than 10% of the TPZ or inside the SRZ, the project arborist must demonstrate that the tree(s) would remain viable. However, the arborist has provided no information to confirm if the proposed works can be carried out and the trees successfully retained and protected. Additionally, proposed FFL are approximately 0.5m above existing levels requiring fill, however the plans do not show how this fill will be contained.
- A number of trees found on the property are suitable for retention. It is considered that a number of these trees could be successfully retained and incorporated as part of the proposal as they are in average health and condition and provide landscape and environmental benefits.

As such, the proposal is contrary to the following objectives:

- Control 3(a) & 3(b) which require that development consent is only granted if the proposal allows for the retention of trees to minimise the urban heat island effect and avoids or minimises impacts to the existing tree canopy (Part 6.9 of Woollahra LEP 2014).
- Aim (n) to encourage the retention and planting of trees and other vegetation as part of development and minimise the urban heat island effect (Part 1.2(2) of the Woollahra LEP 2014).
- O1 To respect and enhance the streetscape character and key elements of the precinct (B1.7.2 under WDCP 2015).
- O7 To reinforce the landscape setting and maintain the existing tree canopy (B1.7.2 under WDCP 2015).
- O8 To retain and reinforce the green setting of mature street trees, private trees and garden plantings and minimise hard stand areas (B1.7.2 under WDCP 2015).
- O1 To ensure that the areas outside the floorplate contribute to the desired future character of the location (B3.7.1 under WDCP 2015).
- O7 To retain important existing mature trees, vegetation and other landscape features (B3.7.1 under WDCP 2015).
- O9 To ensure that landscaping contributes positively to the streetscape and the amenity of adjoining residents (B3.7.1 under WDCP 2015).
- C16 Existing trees and vegetation of landscape value are incorporated into the landscape area and treatment (B3.7.1 under WDCP 2015).
- C18 Landscaping provides for a diversity of native species and a complexity of habitat through vertical layering (B3.7.1 under WDCP 2015).
- O3 To promote, maintain and conserve the leafy character of the Woollahra Municipality (Chapter E3 – *Tree Management* of the DCP 2015).
- O4 To conserve significant trees of historic, cultural, commemorative, scientific, visual or aesthetic importance (Chapter E3 – *Tree Management* of the DCP 2015).

3. Insufficient communal open space

The proposal involves a significant non-compliance with the area of communal open space required under Part 3D of the Apartment Design Guide as follows:

- Part 3D (design criteria 1) requires that 25% (177.15m²) of the site area is provided as communal open space.
- Part 3D requires that communal open space should be consolidated into a well-designed, easily identified and usable area. No part of the communal open space is considered to have any useability given the landscape proposed for the area in the landscape plan.

4. Excessive gross floor area

While the FSR does not technically apply to development on the site, it is noted that Clause 4.4E of WLEP 2014 permits an FSR of 0.5:1 on the surrounding sites. The proposed gross floor area (1.01:1) is considered to be excessive in the context of what is permissible on the neighbouring properties and represents an overdevelopment of the site. The bulk and scale is inconsistent with the existing and desired future character of the area and results in a sense of enclosure to the neighbouring properties. Furthermore the excessive gross floor area results in a significant deep soil landscaping shortfall. The proposal is inconsistent with the following objectives of the control:

- (a) to ensure the bulk and scale of development is compatible with the desired future character of the area,
- (c) to ensure development makes adequate provision for deep soil planting, tree canopy cover and private open space.

5. Urban design issues and Apartment Design Guide

The design of the proposed development is deficient with regard to the following:

- To ensure that the proposal satisfies the internal amenity controls within WDCP 2015, the privacy screening to the habitable rooms should be amended to provide for solar access (C2 under B3.5.5 of WDCP 2015).
- Secondary stair access between building levels and to apartments should be located within the building (Part 3G of the Apartment Design Guide).
- Elevations addressing Carrington Avenue should include more activation by way of full windows and unscreened balconies, noting the need for privacy (Part 3G of the Apartment Design Guide. Landscaping should be provided within the Carrington Avenue elevation to achieve an acceptable streetscape presentation.
- An acoustic study is required to determine acoustic impacts relating to the driveway roller doors and the turntables (Part 4H of the Apartment Design Guide).
- Waste storage should be located within the building in a convenient location to residents and not located at the Cranbrook Road frontage (Part 4W of the Apartment Design Guide).
- Access to the roof should be shown for maintenance (Part 4X of the Apartment Design Guide).
- Stormwater infrastructure should not be located within landscaped areas.

6. Unsatisfactory Driveway Width

The proposed driveway width is considered to be excessive as follows:

- The proposed access driveway incorporates two turntables to provide separate entry and exit. As a result, the width of the access driveway is 6.6m and is considered to be excessive considering the scale and nature of the development. Traffic generation associated with the development is minor and is queuing is unlikely to extend beyond the property boundary, particularly with the proposed provision of a traffic light system (which should give priority to vehicles entering the site). Only one turntable should be provided and the access driveway should be reduced to 3.5m in width.

The centre of the turntable must align with the centreline of the internal driveway and the new crossing.

7. Parking Facilities

The current design of the parking facilities is unacceptable and requires that the following is provided:

- A 2.5m x 2m sight splay, clear of obstruction to visibility, along both sides of the driveway and clearly depicted on the architectural drawings (C8 under B3.7 of WDCP 2015).
- A traffic light system be incorporated to manage traffic flow between the basement car park and ground Level. The traffic light system should be designed to ensure priority is given to vehicles entering the site to minimise disruptions to traffic along the frontage road.
- A minimum of seven bicycle parking spaces must be provided (C1 under Part E1.6 of WDCP 2015).
- Accessible parking spaces, including the adjacent shared area, should be designed in accordance with AS 2890.6. Bollard and line marking should be provided to ensure unimpeded access.

8. Insufficient Information

Architectural Plans

The plans and submitted documentation provide insufficient information in relation to the following:

- Any fire hydrant cabinet, AC condensers, solar panels, lift overruns, mechanical exhaust riser or ducting between levels and the roof level should be shown on the plans.
- More details should be provided in the survey plan in relation to the windows, existing ground levels and garden areas of 2 Carrington Avenue and 52 Cranbrook Road.
- Sections through the proposed development and existing adjoining dwellings should be provided to illustrate sightlines for privacy assessment.
- A comprehensive set of shadow and solar diagrams should be prepared based on the additional survey information.
- The survey should provide details on the existing easements in the site.
- A visual impact assessment should be provided.
- An acoustic impact assessment should be provided to address potential noise impact from the garage door, any above ground car parking at the southern boundary and the turntables.
- A demolition report should be prepared to demonstrate why more of the fabric and character of the existing inter war building cannot be preserved in the redevelopment.

Stormwater Management Plan

The applicant has provided insufficient information to allow the proposed stormwater management to be properly assessed. The Stormwater Management Plan is unsatisfactory as it has failed to address Council's request for additional information (letter dated 22 November 2023). The Stormwater Management Plan must address the following requirements:

- The Stormwater Management Plan has demonstrated the road reserve incorrectly. Where the plans have marked Carrington Road, is in fact private property, being Lot 2 of DP 317841. Plans are to be amended to correct this.

- Stormwater Treatment Systems shall be provided for the proposed development with Water Quality Targets submitted using MUSIC Modelling. A copy of the MUSIC Model shall be attached to the Stormwater Management Plans. The specifications shall be in accordance with Council's water quality targets detailed in Council's Chapter E2 "Stormwater and Flood Risk Management" DCP – Water Quality Targets Location and section details of the treatment systems shall be provided within the Stormwater Management Plan. The design within the MUSIC Model and the Stormwater Management Plan shall coincide.
- The plans demonstrate that the site's stormwater is draining to an existing inter-allotment drainage easement. As such, Title Documents and all associated 88B Instruments must be submitted to Council to demonstrate that the subject site benefits by the drainage easement. Where this is not the case, an alternative stormwater design must be adopted as outlined in council's Request for Additional Information letter (22 November 2023) which states the following:

"The property falls away from Council's drainage infrastructure located within the roadway. In order to avoid nuisance and flooding to downstream properties and to address Woollahra DCP Chapter E2 – Stormwater Flood Risk Management, the acquisition of a downstream easement is required for this development if stormwater discharge from the subject property into Council's stormwater drainage system by gravity is not feasible.

In this regard, the applicant shall submit documentary evidence by way of title documents and associated instruments demonstrating that the subject property is benefited from the existing Drainage Easement and the acquisition of an inter-allotment drainage easement over No. 2 Carrington Avenue is successful. If the subject property does not benefit from the existing Drainage Easement, the applicant must acquire a private interallotment drainage easement over all downstream property(s)."

- The plans note the proposed removal of the existing drainage easement within the site and the connection of the site's stormwater to the remainder of the existing easement. As such, CCTV footage must be provided prior to DA approval to demonstrate 1) no presence of any pipes or overland flow within the easement over the site and showing the easement as redundant and 2) the location of the existing pipe within the existing drainage easement over the neighbouring property and 3) demonstrate that this stormwater pipe is in good working order and is connected to a recognised public underground drainage system in Beresford Crescent.
- If the subject property benefits from the existing Drainage Easement and the acquisition of a new inter-allotment drainage easement over No. 2 Carrington Avenue is successful, the applicant provide the following :
 - a) Carry out site investigation and depict the invert level of the existing 600mm diameter pipeline within the drainage easement for the proposed stormwater connection on the stormwater plans. Sections showing the pipelines and surrounding ground levels for the proposed stormwater connection shall be included in the stormwater plans.
 - b) A HGL analysis must be provided between the existing 600mm pipeline and drainage system within the site when the pipeline is in full capacity. The applicant shall demonstrate that there is no backwater effect from the existing 600mm pipeline to the drainage system within the site.
- If the subject property does not benefit from the existing Drainage Easement and/or a private inter-allotment drainage easement is not available from all downstream property(s), the applicant must provide an alternative in accordance with E2.2.9 (low level properties and easements) of WDCP 2015.

Structures over Existing Drainage Easement

The applicant has provided insufficient information with regard to the structures over the existing drainage easement as follows:

- From the survey and architectural plans provided, it is noted that the proposed basement and building would be constructed over the existing Drainage Easement that is traversing the site. The applicant should be aware that Council will not approve the construction of any permanent structure or the placing of fill over a drainage easement and/or within the extent of the estimated overland flowpath if the structure or fill will hinder or obstruct the overland flows, construction, reconstruction, maintenance, cleaning or access to the pipeline or easement. However, Council's Assets Team may in this instance consider the proposal and the possibility to extinguish this easement provided that the following criteria are fully met:
 - a. The applicant shall submit documentary evidence by way of title documents including all associated instruments confirming that the drainage easement was created in favour of Council.
 - b. Evidence shall be provided showing whether the existing drainage easement over the property is operational with no blockages and/or whether it is collecting stormwater from Carrington Road.
 - c. In light of point (b) above, the applicant shall carry out site investigation and identify if there is any pipeline exists within the easement. As such, detailed survey showing the invert levels of the existing pipelines at every 5 metres intervals and at each end of the drainage pit must be provided. If there is pipeline that is trasversing the site, the applicant must prepare detailed design, prepared by a suitably qualified and experienced civil engineer, for the proposed upgrade or relocation of the existing stormwater pipe. Longitudinal section (scale 1:100V, 1:50 H) showing both existing and finished ground levels, chainage point, HGL, gradient representing in percentage, pipe size and grade shall be provided. The design engineer must demonstrate by way of supporting calculations that the proposed pipeline will have equal or greater capacity than the existing pipeline. The proposed pipelines shall be minimum Class 2, rubber ring jointed (RRJ) steel reinforced concrete pipe (RCP). Provision of a drainage pit must be provided where there is a change of direction for the proposed pipelines.
 - d. In light of point (b) above, the applicant must submit CCTV footage for the underground drainage system in Carrington Avenue. The applicant must demonstrate that the existing underground drainage system in Carrington Avenue located upstream from the site does not connect to any stormwater pipe that may exist within Drainage Easement.
 - e. The suitably qualified and experienced civil engineer must certify that no overland floodwater currently flows through the Drainage Easement and the construction of the proposed structures will not hinder and/or obstruct any overland flows which will cause adverse impacts to downstream properties.

Geotechnical and Hydrogeological Report

The Geotechnical & Hydrogeological Investigation Report, referenced G19012BH-R02F (REV 2), prepared by Geo-Environmental Engineering, dated 13 August 2023 does not address all relevant requirements, as listed below:

- The report must address all requirements outlined in Woollahra Council's DCP Document - Attachment 6 - Guidelines for Geotechnical and Hydrogeological Reports, predominantly, but not limited, to the following;
- Demonstrate that there will be no adverse impact on surrounding property and infrastructure as a result of changes in local hydrogeology (behaviour of groundwater) created by the method of construction.

This includes the short-term effects resulting from construction practices, including the method and rate of dewatering (if any) and the long-term effects resulting from the support and retention of property and infrastructure after construction has been completed.

- Demonstrate that ground settlement in areas adjacent to the development site resulting from temporary and permanent site support and retention measures will have no adverse impact on the surrounding properties and infrastructure.
- Demonstrate that permanent support and retention measures will be set back a minimum of 900mm (or minimum as advised in the relevant Development Control Plan) from the adjacent property boundaries. Please Note: It may be possible for the development to be built up to the boundary however it will require the geotechnical/hydrogeological report to confirm the structural adequacy of any adjacent structures.
- Demonstrate that permanent earth or ground anchors will not be required on or below any road reserve or other Council property. Council may accept the use of temporary anchors if the applicant can adequately demonstrate that the use of temporary anchors would sufficiently improve the safety of the retention of excavations that may be proposed. The installation of such temporary anchors must comply with the Council's Rock Anchor Policy. (Use of permanent and/or temporary anchors on private property is not allowed without written confirmation by the property owners).
Further, where required ground anchors will encroach onto private properties, written approval from the properties must be provided prior to DA approval, otherwise an alternative option must also be provided.
- The report shall be revised to ensure all requirements within Council's Chapter E2 "Stormwater and Flood Risk Management" DCP - Section E2.2.10 have been addressed;
 - The report shall include a site-specific risk assessment matrix with appropriate definitions for qualitative measures of likelihood and consequences for assessing the risk of damage to existing development by the new development.
 - The report shall also contain an Implementation Plan, including a Monitoring Program, Contingency Plan and Construction Methodology.
 - Structural Report including design statement and supporting drawings shall also be submitted showing design measures to minimise risks and to ensure that no adverse impacts will occur.
- The Structural Engineer's Report is unsatisfactory with regard to the information requested in Point 5 of Council's request for additional information (letter dated 22 November 2023).

9. Site Waste Management Plan

The proposal is inconsistent with Chapter E5 of WDCP 2015 which requires that a Site Waste Management Plan is provided.

10. State Environmental Planning Policy (Housing) 2021 – Chapter Two, Part Three

The application has not been accompanied with sufficient information to determine whether it is subject to Part 3 of the SEPP. To determine this, an affordable rental housing report is required which details whether the units within the existing building are low-rental dwellings under the SEPP.

11. Height of building

The Clause 4.6 request in relation to the breach of the height standard is not well founded, particularly given the bulk and scale of the proposed building at that non complying height. Compliance with the standard is not unreasonable or unnecessary in the circumstances.

Note: In accordance with the Woollahra Local Planning Panel Operational Procedures the votes are recorded on this planning matter.

For the Motion

Peter Brennan
Larissa Ozog
David Ryan
Malcolm Young

4/0

Against the Motion

Nil

ITEM No.	D3
FILE No.	DA28/2024/1
ADDRESS	426-440 New South Head Road Double Bay
PROPOSAL	Demolition of existing buildings and construction of a new shop top housing development with mechanical basement parking

Reasons for Decision

The Panel has undertaken a site inspection, considered any submissions and reviewed the assessment report prepared by Council officers that addresses the relevant matters detailed in Section 4.15 of the Environmental Planning and Assessment Act 1979.

For the reasons generally in the assessment report, the Panel is satisfied that the application be refused for the reasons set out below subject to the amendment of Condition 11. b. (Desired Future Character).

Resolved: Pursuant to Section 4.16 of the Environmental Planning and Assessment Act 1979

THAT the Woollahra Local Planning Panel, exercising the functions of Council, as the consent authority, refuse development consent to Development Application No. 28/2024/1 for the demolition of existing buildings and construction of a new shop top housing development with mechanical basement parking on land at 426-440 New South Head Road Double Bay, for the following reasons:

1. State Environmental Planning Policy Housing (2021) – Chapter 4: Design of Residential Apartment Development

The proposal is inconsistent with the following design quality principles of the State Environmental Planning Policy Housing (2021) – Chapter 4: Design of Residential Apartment Development:

- Schedule 9, Principle 1: Context and Neighbourhood Character - Whilst the siting and character of this development provides a compatible response to other neighbouring developments, its relationship with the building on the adjoining side boundary (No. 442 - 446) is poor and viability of the retail space to Cross Lane questionable given its poor exposure.
- Schedule 9, Principle 2: Built Form and Scale – The non-compliance with the maximum height development standard in the WLEP and lack of curved articulation on the North West elevation is not compatible with the built form and scale of this section of the Double Bay Centre.
- Schedule 9, Principle 3: Density – The non-compliance with the maximum floor space ratio development standard in the WLEP creates a building envelope that does not align with the Desired Future Character of the area. The appointed floor space for each dwelling is considered generous.

- Schedule 9, Principle 9: Aesthetics – The different styles adopted between the Cross Lane and New South Head Road Facades results in the building presentation reading as two separate buildings. This inconsistent design takes away from the buildings identity and address in the streetscape.

2. Apartment Design Guide

The proposal is inconsistent with the objectives outlined in following Parts of the Apartment Design Guide:

- 3B – Orientation
- 3C – Public Domain Interface
- 4G – Storage
- 4N – Roof design

3. State Environmental Planning Policy Housing (2021) – Chapter 2: Affordable Housing

The proposal fails to address the relevant matters for consideration in Clause 47 of Chapter 2, Part 3 of the SEPP Housing (2021) as the application has not been accompanied with sufficient information to determine whether the units within the existing building are low-rental dwellings and whether it is subject to Part 3 of the SEPP.

4. State Environmental Planning Policy (Resilience and Hazards) 2021 – Chapter 4: Remediation of Land

The proposal fails to address the relevant matters for consideration in Section 4.6 of Chapter 4 – Remediation of Land of the Resilience and Hazards SEPP2021, as insufficient information has been provided to determine whether the land beneath the building is contaminated and whether the subject site is suitable for the proposed mixed use development.

5. Environmental Planning and Assessment (Housing and Productivity Contribution) Ministerial Order 2023

The applicant has not provided an assessment of contributions in accordance with *Subdivision 4 Housing and Productivity Contributions*.

6. Woollahra Local Environmental Plan 2014, Clause 1.2 Aims of Plan

The proposal fails to achieve the following aims prescribed in Clause 1.2(2) of the Woollahra LEP 2014:

- (g) to protect and enhance amenity and the natural environment,*
- (j) to promote a high standard of design in the private and public domain,*
- (k) to minimise and manage traffic and parking impacts,*
- (l) to ensure development achieves the desired future character of the area.*

7. Woollahra Local Environmental Plan, Part 2, Land Use Table

The proposal is inconsistent with the relevant objective of the E1 Local Centre zone because:

- The development is not of a scale and type that is compatible with the amenity of the surrounding residential area.
- The development is not of a height and scale that achieves the desired future character of the local centre.

- The development does not provide diverse and active ground floor uses to contribute to vibrant and functional streets and public spaces.

8. Woollahra Local Environmental Plan 2014, Part 4 – Clause 4.3 Height of buildings

The proposal does not comply with the Height of buildings development standard prescribed in Clause 4.3 of the Woollahra Local Environmental Plan 2014. The proposal fails to achieve consistency with the Objectives (a), (c) & (d), prescribed in Clause 4.3(1) of the Woollahra Local Environmental Plan 2014.

9. Woollahra Local Environmental Plan 2014, Part 4 – Clause 4.4 Floor Space Ratio

The proposal does not comply with the Floor Space Ratio development standard prescribed in Clause 4.4 of the Woollahra Local Environmental Plan 2014. The proposal fails to achieve consistency with the Objective (i) prescribed in Clause 4.4(1)(a) of the Woollahra Local Environmental Plan 2014.

10. Woollahra Local Environmental Plan 2014, Part 4 – Clause 4.6 Exceptions to Development Standards

The consent authority is of the opinion that the submitted written requests fail to justify the contravention of the *Height of buildings and Floor space ratio* development standards under Clauses 4.3 and 4.4 in accordance with Clause 4.6(3)(a) and 4.6(3)(b). The submitted written requests have not adequately addressed the matters required to be demonstrated by sub-clause (3) in that:

- strict compliance with the development standards is unreasonable or unnecessary in the circumstances of the case;
- there are sufficient environmental planning grounds to justify contravening the development standards.

11. Woollahra Development Control Plan 2015, Chapter D5 Double Bay Centre

The proposed new works will have an adverse impact on the desired future character of the Double Bay Centre by failing to satisfy the following controls and objectives prescribed in Chapter D5: Double Bay Centre of the Woollahra DCP 2015:

a) Part D5.3: Urban structure

i. Part D5.3.2: Key Strategies for the Double Bay Centre

- The proposal fails to achieve strategy items b) & c) prescribed in Part D5.3.2 of the Woollahra DCP 2015.

b) Part D5.4 Street Character

i. Part D5.4.3 New South Head Road

- The proposal fails to achieve the Desired Future Character prescribed in the Woollahra DCP 2015.

c) Part D5.6 Development Controls

i. Part D5.6.3 Urban Character

- The proposal does not comply with Control C1 and fails to achieve Objective O1 prescribed in Part D5.6.3.1: Building envelopes of the Woollahra DCP 2015.
- The proposal fails to achieve Objectives O1 & O2 prescribed in Part 5.6.3.2: Height of the Woollahra DCP 2015
- The proposal is contrary to Control Drawing 2 and requirements for building articulation prescribed in Part 5.6.3.3: Building articulation of the Woollahra DCP 2015
- The proposal fails to achieve Objectives O2 & O4 prescribed in Part D5.6.3.6: Architectural resolution

ii. Part D5.6.4 Relationship to Public Domain

- The proposal fails to achieve Objectives O1 & O4 prescribed in Part D5.6.4.6: Ground floor active lane frontage of the Woollahra DCP 2015.

iii. Part D5.6.6 Solar access and natural ventilation

- The proposal does not comply with Controls C2 & C4 and fails to achieve Objective O1 prescribed in Part D5.6.6.1: Solar access of the Woollahra DCP 2015.

iv. Part D5.6.8: Parking and servicing

- The proposal does not comply with Control C1 and fails to achieve Objective O2 prescribed in Part D5.6.8.1: On-site parking of the Woollahra DCP 2015.
- The proposal does not comply with Control C3 and fails to achieve Objectives O1, O2 & O3 prescribed in Part D5.6.8.2 of the Woollahra DCP 2015.

12. Woollahra Development Control Plan 2015, Chapter E1 Parking and Access

a) Part E1.1.3 Objectives

- The proposal fails to achieve Objectives O1, O3 & O5 in Part E1.1.3 of the Woollahra DCP 2015.

b) Part E1.10: Parking and Access Design Standards

i. Part E1.10.2 Australian Standards

- The proposal is contrary to Part 3.2 and 3.5 prescribed in AS/NZS2890.1

ii. Part E1.10.6 Driveways and access points

- The proposal is contrary to the access driveway width prescribed in this part.

c) Part E1.15: Mechanical Parking Installations and Paid Parking Stations

i. Part E1.15.3 Waiting bays

- The proposal is contrary to the requirements for waiting bays prescribed in this part.

13. Woollahra Development Control Plan 2015, Chapter E4 Contaminated Land

The proposal is unacceptable with regard to Chapter E4 of the Woollahra DCP 2015 as insufficient information has been provided to determine whether the land beneath the building is contaminated and whether the subject site is suitable for the proposed mixed use development.

14. Insufficient/inconsistent Information

i. Survey

The submitted site survey by Chadwick Cheng consulting surveyors dated 22.11.2023 details the combined lot size of lots 6, 7, 8 & 9 and does not include lots 4 & 5. This does not depict the correct size of the combined site which prohibits an accurate assessment of the Floor Space Ratio development standard.

ii. Dates of the Design Verification Statement and Architectural Plans

The Design Verification Statement provided for this development application does not address the objectives in Parts 3 and 4 of the Apartment Design Guide as required under Part 3 Clause 29 (2)(b)(ii) of the Environmental Planning and Assessment Regulation 2021.

iii. On-site Parking

- The proposed waiting bays on the architectural plans need to be properly depicted and include a traffic light system to manage traffic flow.
- No details are provided with regard to the parking allocation [residential (to which units) or commercial (to which premises)] and the operation of the mechanical car stacker with respect to the different users (residential or commercial).

iv. Shadow Diagrams

The assessment of shadow impact relies on a survey plan ("Norton Surveyors ref 41432") and Architectural Plans (dated 01 November 2023) that differ from that submitted with the development application. Insufficient information therefore hinders an accurate assessment against the controls and objectives under Part D5.6.6.1 of the Woollahra DCP 2015.

v. View Impact Assessment

A thorough view impact analysis must be submitted that identifies the locations where potential view loss impacts may exist. The analysis must be consistent with the four-step process in the NSW Land and Environment Court's Planning Principles established in *Tenacity Consulting v Warringah Council [2004] NSWLEC 140*.

vi. Contamination - Preliminary (Environmental) Site Investigation (**PSI**), Detailed Site Investigation (DSI) and Remediation Action Plan (RAP)

- a) A Detailed Site Investigation (DSI) is required to be submitted on the data gaps and identified Potential Areas of Environmental Concern (PAEC), as detailed in section 6.3 of the Stage 1 Preliminary (Environmental) Site Investigation (PSI): prepared by EBG Environmental Geoscience – Report ID: EBG-03023.Stage 1.PSI.05.23 – 10 May 2023 report, given that the land beneath the building may be contaminated.
- b) Where site constraints may hinder supplementary assessment of the Detailed Site Investigation, the Applicant shall prepare a Remediation Action Plan (RAP). The RAP should:
- set remediation goals that ensure the remediated site will be suitable for the proposed use and will not pose an unacceptable risk to human health or to the environment.
 - document in detail all procedures and plans to be implemented to reduce risks to acceptable levels for the proposed use
 - provide the procedures required for remediation including material excavation and off-site disposal at an EPA licensed landfill
 - include a site management plan that sets out the environmental safeguards required to complete the remediation in an environmentally acceptable manner
 - outline the validation requirements for the site including methodology and validation acceptance criteria
 - detail any long-term environmental management plan.
- vii. State Environmental Planning Policy (Housing) 2021 – Chapter 2, Part 3 (Retention of existing affordable rental housing)

The application has not been accompanied with sufficient information to determine whether it is subject to Part 3 of the SEPP. To determine this, an affordable rental housing report is required which details whether the units within the existing building are low-rental dwellings under the SEPP.

15. Public Interest

The proposed development is not in the public interest.

Note: In accordance with the Woollahra Local Planning Panel Operational Procedures the votes are recorded on this planning matter.

For the Motion

Peter Brennan
Larissa Ozog
David Ryan
Malcolm Young

4/0

Against the Motion

Nil

ITEM No. D4
FILE No. DA354/2023/1
ADDRESS 14 Manning Road, Double Bay
PROPOSAL Demolition of the existing dwelling and the construction of a new residential flat building and associated landscaping.

Note: Malcolm Young declared and Non Pecuniary Non-Significant interest in this Item, as some years ago Mr Young was on a residents' committee with Ms G Ettinger-Epstein. Mr Young noted Ms G Ettinger-Epstein's short objection seemed principally to relate to a possible condition or conditions of consent rather than whether consent should be granted. Mr Young further declared knowing Sacha Ettinger, Councillor Mark Silcocks and Katherine Grinberg from the Double Bay Residents Association, all of whom made submissions in the Late Correspondence. Mr Young remained in the meeting, participated in the debate and voted on the matter.

Note: Late correspondence was tabled by Mark Silcocks, Sascha Epstein, Helen Moutzouris and Double Bay Residents Association.

Reasons for Decision

The Panel has undertaken a site inspection, considered any submissions and late correspondence, and reviewed the assessment report prepared by Council officers that addresses the relevant matters detailed in Section 4.15 of the Environmental Planning and Assessment Act 1979.

For the reasons generally in the assessment report, the Panel is satisfied that the application can be approved subject to the amendment to Condition H.4 (Provision of Off-street Public and Visitor Parking)

Resolved: Pursuant to Section 4.16 of the Environmental Planning and Assessment Act 1979

THAT the Woollahra Local Planning Panel, exercising the functions of Council, as the consent authority, is satisfied that the matters required to be addressed under Clause 4.6(4) of the Woollahra Local Environmental Plan 2014 have been demonstrated and that consent may be granted to the development application, which contravenes the Minimum lot size development standard under Clause 4.1A of the Woollahra LEP 2014.

AND

THAT the Woollahra Local Planning Panel, exercising the functions of Council, as the consent authority, grant development consent to Development Application No. 354/2023/1 for the demolition of the existing dwelling and the construction of a new residential flat building and associated landscaping on land at 14 Manning Road Double Bay, subject to the following conditions:

ALL DEVELOPMENT TYPES

A. GENERAL CONDITIONS

<p>A. 1.</p>	<p>Conditions</p> <p>Consent is granted subject to the following conditions imposed under section 4.16 of the Environmental Planning and Assessment Act 1979 (“the Act”), and the provisions of the Environmental Planning and Assessment Regulation 2021 (“the Regulations”) and the provisions of the Environmental Planning and Assessment (Development Certification and Fire Safety) Regulation 2021 (“the Development Certification and Fire Safety Regulations”), such conditions being reasonable and relevant to the development as assessed under section 4.15 of the Act.</p> <p>Notes:</p> <ul style="list-style-type: none"> • Failure to comply with this development consent and any condition of this consent is a criminal offence. Failure to comply with other environmental laws is also a criminal offence. • Where there is any breach Council may without any further warning: <ul style="list-style-type: none"> a) Issue Penalty Infringement Notices (On-the-spot fines); b) Issue notices and orders; c) Prosecute any person breaching this consent; and/or d) Seek injunctions/orders before the courts to restrain and remedy any breach. • Maximum penalties under NSW environmental laws include fines up to \$1.1 Million and/or custodial sentences for serious offences. • Should Council have to take any action to enforced compliance with this consent or other environmental laws Council’s policy is to seek from the Court appropriate orders requiring the payments of its costs beyond any penalty or remedy the Court may order. • This consent and this specific advice will be tendered to the Court when seeking costs orders from the Court where Council is successful in any necessary enforcement action. • The payment of environmental penalty infringement notices does not result in any criminal offence being recorded. If a penalty infringement notice is challenged in Court and the person is found guilty of the offence by the Court, subject to section 10 of the Crimes (Sentencing Procedure) Act 1999, a criminal conviction is recorded. The effect of a criminal conviction beyond any fine is serious. <p>Condition Reason: To ensure all parties are aware of the relevant legislation that applies to the development.</p>
<p>A. 2.</p>	<p>Definitions</p> <p>Unless specified otherwise, words have the same meaning as defined by the <i>Act</i>, the <i>Regulations</i>, the <i>Development Certification and Fire Safety Regulations</i> and the <i>Interpretation Act 1987</i> as in force at the date of consent.</p> <p>Applicant means the applicant for this consent.</p> <p>Approved Plans mean the plans endorsed by Council referenced by this consent as amended by conditions of this consent.</p> <p>Local native plants means species of native plant endemic to Sydney’s eastern suburbs.</p> <p>Owner-builder has the same meaning as in the <i>Home Building Act 1989</i>.</p> <p>PC means the Principal Certifier under the <i>Act</i>.</p>

	<p>Principal Contractor has the same meaning as in the <i>Act</i>, or where a Principal Contractor has not been appointed by the Owner of the land being developed Principal Contractor means the Owner of the land being developed.</p> <p>Professional engineer has the same meaning as in the BCA.</p> <p>Public place has the same meaning as in the <i>Local Government Act 1993</i>.</p> <p>Road has the same meaning as in the <i>Roads Act 1993</i>.</p> <p>SEE means the final version of the Statement of Environmental Effects lodged by the Applicant.</p> <p>Site means the land being developed subject to this consent.</p> <p>Site work means any work that is physically carried out on the land to which the development the subject of this development consent is to be carried out, including but not limited to building work, subdivision work, demolition work, clearing of vegetation or remediation work.</p> <p>Woollahra LEP means <i>Woollahra Local Environmental Plan 2014</i></p> <p>Woollahra DCP means <i>Woollahra Development Control Plan 2015</i></p> <p>Work for the purposes of this consent means:</p> <ul style="list-style-type: none"> • the use of land in connection with development, • the subdivision of land, • the erection of a building, • the carrying out of any work, • the use of any site crane, machine, article, material, or thing, • the storage of waste, materials, site crane, machine, article, material, or thing, • the demolition of a building, • the piling, piercing, cutting, boring, drilling, rock breaking, rock sawing or excavation of land, • the delivery to or removal from the <i>site</i> of any machine, article, material, or thing, or • the occupation of the <i>site</i> by any person unless authorised by an occupation certificate.
	<p>Condition Reason: To ensure all parties are aware of the relevant definitions.</p>
<p>A. 3.</p>	<p>Approved Plans and Supporting Documents</p> <p>Those with the benefit of this consent must carry out all work and maintain the use and works in accordance with both the architectural plans to which is affixed a Council stamp “Approved” and supporting documents listed below unless modified by any following condition.</p> <p>Where the plans relate to alterations or additions only those works shown in colour or highlighted are approved.</p>

Reference	Description	Author	Date
DA1003 DA2000 DA2001 DA2002 DA2003 DA2004 DA3000 DA3001 DA3002 DA3003 DA3100 DA3101 (All Rev B)	Architectural Plans	All by MHNDUnion	All dated 02/01/2024
1377864M	BASIX Certificate	NSW Department of Planning, Industry and Environment	20/03/2023
LS01, LS02, LS2.1, LS2.2, LS03, LS04, LS05, LS06, LS07	Landscape Plans	Melissa Wilson Landscape Architects	08/09/2023
n/a	Arborist Report	Dr Treegood	09/2023
15938-GR-1-1- Rev01	Geotechnical Report	Alliance	26/07/2023
22576	Traffic & Parking Matters	Varga Traffic	30/08/2023
22576	Revised Traffic and Parking Assessment Report	Varga Traffic	19/09/2023
15938.1-ER-1-1	Conceptual Acid Sulphate Soil Management Plan	Alliance Geotechnical Pty Ltd	09/05/2024

Notes:

- Warning to Principal Certifier – You must always insist on sighting the original Council stamped approved plans. You must not rely solely upon the plan reference numbers in this condition. Should the Applicant not be able to provide you with the original copy Council will provide you with access to its files so you may review our original copy of the approved plans.
- These plans and supporting documentation may be subject to conditions imposed under section 4.17(1)(g) of the Act modifying or amending the development.

Condition Reason: To ensure all parties are aware of the approved plans and supporting documentation that applies to the development.

A. 4. Ancillary Aspects of Development (section 4.17(2) of the Act)

The Owner must procure the repair, replacement or rebuilding of all road pavement, kerb, gutter, footway, footpaths adjoining the site or damaged as a result of work under this consent or as a consequence of work under this consent. Such work must be undertaken to Council's satisfaction in accordance with Council's Specification for Roadworks, Drainage and Miscellaneous Works (2012) unless expressly provided otherwise by these conditions at the Owner's expense.

Notes:

- This condition does not affect the Principal Contractor's or any sub-contractors obligations to protect and preserve public infrastructure from damage or affect their liability for any damage that occurs.

Condition Reason: To ensure all parties are aware of works required to public infrastructure and to ensure payment for works.

A. 5.	<p>No Underpinning works</p> <p>This development consent does NOT give approval to any works outside the boundaries of the subject property including any underpinning works to any structures on adjoining properties.</p> <p>Condition Reason: To ensure all works are located within the boundaries of the site and to confirm that no consent is granted for underpinning works to any structures on adjoining properties.</p>																																												
A. 6.	<p>Tree Preservation and Landscaping Works</p> <p>While site work is being carried out, all landscape works must be undertaken in accordance with the approved landscape plan, arborist report, tree management plan and transplant method statement as applicable.</p> <p>a) The following trees must be retained:</p> <ul style="list-style-type: none"> • Trees on private land: <table border="1" style="width: 100%; border-collapse: collapse;"> <thead> <tr> <th style="text-align: center;">Council Ref No</th> <th style="text-align: center;">Species</th> <th style="text-align: center;">Location</th> <th style="text-align: center;">Dimension (metres)</th> </tr> </thead> <tbody> <tr> <td style="text-align: center;">1</td> <td><i>Archontophoenix cunninghamiana</i></td> <td>Front Yard – western boundary</td> <td style="text-align: center;">10 x 2</td> </tr> <tr> <td style="text-align: center;">4</td> <td><i>Archontophoenix cunninghamiana</i></td> <td>Front Yard – western boundary</td> <td style="text-align: center;">8 x 2</td> </tr> <tr> <td style="text-align: center;">10</td> <td><i>Washingtonia robusta</i></td> <td>Rear Yard – northern boundary</td> <td style="text-align: center;">20 x 2</td> </tr> </tbody> </table> <p>The tree/s required to be retained must appear coloured green on the Construction Certificate plans.</p> <p>b) The following trees may be removed:</p> <table border="1" style="width: 100%; border-collapse: collapse;"> <thead> <tr> <th style="text-align: center;">Council Ref No</th> <th style="text-align: center;">Species</th> <th style="text-align: center;">Location</th> <th style="text-align: center;">Dimension (metres)</th> </tr> </thead> <tbody> <tr> <td style="text-align: center;">2</td> <td><i>Yucca</i> spp.</td> <td rowspan="8" style="text-align: center; vertical-align: middle;">Refer to the Arborist Report prepared by Dr Treegood dated September 2023 for tree numbers and locations.</td> <td style="text-align: center;">5 x 2</td> </tr> <tr> <td style="text-align: center;">3</td> <td><i>Yucca</i> spp.</td> <td style="text-align: center;">5 x 1</td> </tr> <tr> <td style="text-align: center;">5</td> <td><i>Yucca</i> spp.</td> <td style="text-align: center;">5 x 3</td> </tr> <tr> <td style="text-align: center;">6</td> <td><i>Yucca</i> spp.</td> <td style="text-align: center;">5 x 1</td> </tr> <tr> <td style="text-align: center;">7</td> <td><i>Yucca</i> spp.</td> <td style="text-align: center;">5 x 1</td> </tr> <tr> <td style="text-align: center;">8</td> <td><i>Dyopsis lutescens</i></td> <td style="text-align: center;">5 x 2</td> </tr> <tr> <td style="text-align: center;">9</td> <td><i>Yucca</i> spp.</td> <td style="text-align: center;">6 x 2</td> </tr> </tbody> </table> <p>The tree/s that may be removed must appear coloured red on the Construction Certificate plans.</p> <p>The species marked (*) is exempt from the WMC DCP 2015 and can be removed without requiring consent from Council.</p> <p>Condition Reason: To ensure all landscape works are undertaken in accordance with the approved plans and documents.</p>			Council Ref No	Species	Location	Dimension (metres)	1	<i>Archontophoenix cunninghamiana</i>	Front Yard – western boundary	10 x 2	4	<i>Archontophoenix cunninghamiana</i>	Front Yard – western boundary	8 x 2	10	<i>Washingtonia robusta</i>	Rear Yard – northern boundary	20 x 2	Council Ref No	Species	Location	Dimension (metres)	2	<i>Yucca</i> spp.	Refer to the Arborist Report prepared by Dr Treegood dated September 2023 for tree numbers and locations.	5 x 2	3	<i>Yucca</i> spp.	5 x 1	5	<i>Yucca</i> spp.	5 x 3	6	<i>Yucca</i> spp.	5 x 1	7	<i>Yucca</i> spp.	5 x 1	8	<i>Dyopsis lutescens</i>	5 x 2	9	<i>Yucca</i> spp.	6 x 2
Council Ref No	Species	Location	Dimension (metres)																																										
1	<i>Archontophoenix cunninghamiana</i>	Front Yard – western boundary	10 x 2																																										
4	<i>Archontophoenix cunninghamiana</i>	Front Yard – western boundary	8 x 2																																										
10	<i>Washingtonia robusta</i>	Rear Yard – northern boundary	20 x 2																																										
Council Ref No	Species	Location	Dimension (metres)																																										
2	<i>Yucca</i> spp.	Refer to the Arborist Report prepared by Dr Treegood dated September 2023 for tree numbers and locations.	5 x 2																																										
3	<i>Yucca</i> spp.		5 x 1																																										
5	<i>Yucca</i> spp.		5 x 3																																										
6	<i>Yucca</i> spp.		5 x 1																																										
7	<i>Yucca</i> spp.		5 x 1																																										
8	<i>Dyopsis lutescens</i>		5 x 2																																										
9	<i>Yucca</i> spp.		6 x 2																																										

A.	7.	<p>General Terms of Approval – <i>Water Management Act 2000 (WaterNSW)</i></p> <p>The GTA issued by WaterNSW do not constitute an approval under the <i>Water Management Act 2000</i>. The development consent holder must apply to WaterNSW for the relevant approval after development consent has been issued by Council and before the commencement of any work or activity.</p> <p>Condition Number Details</p> <p>Dewatering</p> <p>GT0115-00001 Groundwater must only be pumped or extracted for the purpose of temporary construction dewatering at the site identified in the development application. For clarity, the purpose for which this approval is granted is only for dewatering that is required for the construction phase of the development and not for any dewatering that is required once construction is completed.</p> <p>GT0116-00001 Before any construction certificate is issued for any excavation under the development consent, the applicant must: 1. apply to WaterNSW for, and obtain, an approval under the Water Management Act 2000 or Water Act 1912, for any water supply works required by the development; and 2. notify WaterNSW of the programme for the dewatering activity to include the commencement and proposed completion date of the dewatering activity Advisory Note: 3. An approval under the Water Management Act 2000 is required to construct and/or install the water supply works. For the avoidance of doubt, these General Terms of Approval do not represent any authorisation for the take of groundwater, nor do they constitute the grant or the indication of an intention to grant, any required Water Access Licence (WAL). A WAL is required to lawfully take more than 3ML of water per water year as part of the dewatering activity. 4. A water use approval may also be required, unless the use of the water is for a purpose for which a development consent is in force.</p> <p>GT0117-00001 A water access licence, for the relevant water source, must be obtained prior to extracting more than 3ML per water year of water as part of the construction dewatering activity. Advisory Notes: 1. This approval is not a water access licence. 2. A water year commences on 1 July each year. 3. This approval may contain an extraction limit which may also restrict the ability to take more than 3ML per water year without further information being provided to WaterNSW. 4. Note that certain water sources may be exempted from this requirement - see paragraph17A, Schedule 4 of the Water Management (General) Regulation 2018.</p> <p>GT0118-00001 If no water access licence is obtained for the first 3ML / year (or less) of water extracted, then, in accordance with clause 21(6), Water Management (General) Regulation 2018, the applicant must: (a) record water taken for which the exemption is claimed, and (b) record the take of water not later than 24 hours after water is taken, and (c) make the record on WAL exemption form located on WaterNSW website "Record of groundwater take under exemption", and (d) keep the record for a period of 5 years, and</p>
----	----	--

	<p>(e) give the record to WaterNSW either via email to Customer.Helpdesk@waternsw.com.au or post completed forms to - PO Box 398 Parramatta NSW 2124 (i) not later than 28 days after the end of the water year (being 30 June) in which the water was taken, or (ii) if WaterNSW directs the person in writing to give the record to WaterNSW on an earlier date, by that date.</p>
GT0119-00001	<p>All extracted groundwater must be discharged from the site in accordance with Council requirements for stormwater drainage or in accordance with any applicable trade waste agreement.</p>
GT0120-00001	<p>The design and construction of the building must prevent: (a) any take of groundwater, following the grant of an occupation certificate (and completion of construction of development), by making any below-ground levels that may be impacted by any water table fully watertight for the anticipated life of the building. Waterproofing of below-ground levels must be sufficiently extensive to incorporate adequate provision for unforeseen high water table elevations to prevent potential future inundation; (b) obstruction to groundwater flow, by using sufficient permanent drainage beneath and around the outside of the watertight structure to ensure that any groundwater mounding shall not be greater than 10 % above the pre-development level; and (c) any elevated water table from rising to within 1.0 m below the natural ground surface.</p>
GT0121-00001	<p>Construction phase monitoring bore requirements GTA: a) A minimum of three monitoring bore locations are required at or around the subject property, unless otherwise agreed by WaterNSW. b) The location and number of proposed monitoring bores must be submitted for approval, to WaterNSW with the water supply work application. c) The monitoring bores must be installed and maintained as required by the water supply work approval. d) The monitoring bores must be protected from construction damage.</p>
GT0122-00001	<p>Construction Phase Monitoring programme and content: a) A monitoring programme must be submitted, for approval, to WaterNSW with the water supply work application. The monitoring programme must, unless agreed otherwise in writing by WaterNSW, include matters set out in any Guide published by the NSW Department of Planning Industry and Environment in relation to groundwater investigations and monitoring. Where no Guide is current or published, the monitoring programme must include the following (unless otherwise agreed in writing by WaterNSW): i. Pre-application measurement requirements: The results of groundwater measurements on or around the site, with a minimum of 3 bore locations, over a minimum period of 3 months in the six months prior to the submission of the approval to WaterNSW. ii. Field measurements: Include provision for testing electrical conductivity; temperature; pH; redox potential and standing water level of the groundwater; iii. Water quality:</p>

	<p>Include a programme for water quality testing which includes testing for those analytes as required by WaterNSW; iv. QA: Include details of quality assurance and control v. Lab assurance: Include a requirement for the testing by National Association of Testing Authorities accredited laboratories. b) The applicant must comply with the monitoring programme as approved by WaterNSW for the duration of the water supply work approval (Approved Monitoring Programme)</p>
GT0123-00001	<p>(a) Prior to the issuing of the occupation certificate, and following the completion of the dewatering activity, and any monitoring required under the Approved Monitoring Programme, the applicant must submit a completion report to WaterNSW. (b) The completion report must, unless agreed otherwise in writing by WaterNSW, include matters set out in any guideline published by the NSW Department of Planning Industry and Environment in relation to groundwater investigations and monitoring. Where no guideline is current or published, the completion report must include the following (unless otherwise agreed in writing by WaterNSW): 1) All results from the Approved Monitoring Programme; and 2) Any other information required on the WaterNSW completion report form as updated from time to time on the WaterNSW website. c) The completion report must be submitted using "Completion Report for Dewatering work form" located on WaterNSW website www.waternsw.com.au/customer-service/water-licensing/dewatering</p>
GT0150-00001	<p>The extraction limit shall be set at a total of 3ML per water year (being from 1 July to 30 June). The applicant may apply to WaterNSW to increase the extraction limit under this condition. Any application to increase the extraction limit must be in writing and provide all information required for a hydrogeological assessment. Advisory note: Any application to increase the extraction limit should include the following: - Groundwater investigation report describing the groundwater conditions beneath and around the site and subsurface conceptualisation - Survey plan showing ground surface elevation across the site - Architectural drawings showing basement dimensions - Environmental site assessment report for any sites containing contaminated soil or groundwater (apart from acid sulphate soils (ASS)) - Laboratory test results for soil sampling testing for ASS - If ASS, details of proposed management and treatment of soil and groundwater. Testing and management should align with the NSW Acid Sulphate Soil Manual</p>
GT0151-00001	<p>Any dewatering activity approved under this approval shall cease after a period of two (2) years from the date of this approval, unless otherwise agreed in writing by WaterNSW (Term of the dewatering approval). Advisory note: an extension of this approval may be applied for within 6 months of the expiry of Term.</p>
GT0152-00001	<p>This approval must be surrendered after compliance with all conditions of this approval, and prior to the expiry of the Term of the dewatering approval, in condition GT0151-00001.</p>

<p>GT0155-00001</p>	<p>Advisory note: an extension of this approval may be applied for within 6 months of the expiry of Term.</p> <p>The following construction phase monitoring requirements apply (Works Approval): a. The monitoring bores must be installed in accordance with the number and location shown, as modified by this approval, unless otherwise agreed in writing with WaterNSW. b. The applicant must comply with the monitoring programme as amended by this approval (Approved Monitoring Programme). c. The applicant must submit all results from the Approved Monitoring Programme, to WaterNSW, as part of the Completion Report.</p> <p>SCHEDULE 1</p> <p>The plans and associated documentation listed in this schedule are referred to in general terms of approval (GTA) issued by WaterNSW for integrated development associated with DA354/23 as provided by Council:</p> <ul style="list-style-type: none"> • Geotechnical Investigation Report prepared by Alliance Geotechnical & Environmental Solutions Report No. 15938-GR-1-1-Rev01 dated 26 July 2023. • Acid Sulfate Soils Assessment Report prepared by Alliance Geotechnical & Environmental Solutions Report No.15938-ER-1-1_Rev1 dated 21 March 2023. • Statement of Environmental Effects prepared by GSA Planning Job No. 22490 dated September 2023. • Architectural Plans prepared by MHN Design Union Project No. 22-016 Issue date 30 August 2023. <p>Note: These conditions have not been imposed by Council but are required to be incorporate as conditions of development consent. Where there is any inconsistency between these general terms of approval and other conditions of this consent the more onerous requirement prevails.</p> <hr/> <p>Condition Reason: To ensure appropriate conditions are complied with for dewatering in accordance with the General Terms of Approval from WaterNSW.</p>
---------------------	--

DEMOLITION WORK

B. BEFORE DEMOLITION WORK COMMENCES

<p>B. 1.</p>	<p>Construction Certificate Required Prior to Any Demolition</p> <p>Where demolition is associated with an altered portion of, or an extension to an existing building the demolition of any part of a building is "commencement of erection of building" under section 6.6 of the Act.</p> <p>In such circumstance all conditions included at the following development stages of this consent must be satisfied prior to any demolition work:</p> <ul style="list-style-type: none"> • Before issue of a construction certificate • Before building work commences
---------------------	---

	<p>This includes, but is not limited to, the issue of a Construction Certificate, appointment of a Principal Certifier, and Notice of Commencement under the Act.</p> <p>Note:</p> <ul style="list-style-type: none"> • See Over our Dead Body Society Inc v Byron Bay Community Association Inc [2001] NSWLEC 125. <p>Condition Reason: To ensure appropriate conditions are complied with for development for the alteration and extension of an existing building.</p>
<p>B. 2.</p>	<p>Erosion and Sediment Controls – Installation</p> <p>Before any site work commences, water pollution, erosion and sedimentation controls must be installed and maintained in accordance with:</p> <ol style="list-style-type: none"> “Do it Right On Site, Soil and Water Management for the Construction Industry” and accompanying factsheets published by the Southern Sydney Regional Organisation of Councils, and “Managing Urban Stormwater - Soils and Construction” 2004 published by the NSW Government (The Blue Book). <p>Where there is any conflict The Blue Book takes precedence.</p> <p>Notes:</p> <ul style="list-style-type: none"> • The “Do it Right On Site, Soil and Water Management for the Construction Industry” publication and accompanying factsheets can be downloaded from www.woollahra.nsw.gov.au and The Blue Book is available at www.environment.nsw.gov.au • A failure to comply with this condition may result in penalty infringement notices, prosecution, notices and orders under the Act and/or the Protection of the Environment Operations Act 1997 without any further warning. It is a criminal offence to cause, permit or allow pollution. • Section 257 of the Protection of the Environment Operations Act 1997 provides inter alia that “the occupier of premises at or from which any pollution occurs is taken to have caused the pollution”. • Warning: Irrespective of this condition any person occupying the site may be subject to proceedings under the Protection of the Environment Operations Act 1997 where pollution is caused, permitted or allowed as the result of their occupation of the land being developed. <p>Condition Reason: To prevent potential water pollution and dust nuisance.</p>
<p>B. 3.</p>	<p>Identification of Hazardous Material</p> <p>Prior to any site works, and in accordance with Australian Standard AS2601: The Demolition of Structures, all hazardous substances located on the site must be identified, including asbestos, polychlorinated biphenyls (PCBs), lead paint, underground storage tanks, chemicals, etc.</p> <p>In this regard, prior to any site works, Council must be provided with a written report prepared by a suitably qualified competent person detailing:</p> <ul style="list-style-type: none"> • all hazardous materials identified on the site, • the specific location of all hazardous materials identified, • whether the hazardous materials are to be removed from the site as part of the works to be undertaken, and • safety measures to be put in place.

	<p>Condition Reason: To protect the health and safety of all persons while works are being undertaken and to ensure all safety measures have been identified and are in place to protect all parties in the immediate vicinity of the site.</p>																								
<p>B. 4.</p>	<p>Public Road Assets Prior to Any Work/Demolition</p> <p>Prior to any site works, a full record of the condition of the public infrastructure on public land adjacent to the development site must be submitted to Council.</p> <p>The report must include photographs and/or CCTV footage showing the current condition and any existing damage fronting and adjoining the site to the:</p> <ul style="list-style-type: none"> • road pavement, • street signage including street lights, • kerb and gutter, • footway including pedestrian crossings, footpath, and driveways, • retaining walls, or other significant structures, • Heritage Items, including street name inlays, • utility service items including historical utility covers, and • drainage structures/pits/pipes (CCTV footage). <p>The reports are to be supplied in electronic format in Word and if applicable accompanied by CCTV footage. Photographs are to be in colour, digital and date stamped.</p> <p>If the required report is not submitted then Council will assume there was no damage to any infrastructure in the immediate vicinity of the site prior to the commencement of any site works under this consent.</p> <p>Condition Reason: To clarify the condition of the existing public infrastructure prior to the commencement of any site works.</p>																								
<p>B. 5.</p>	<p>Payment of Security and Fees</p> <p>Prior to any site works, the following security and fees must be paid in full:</p> <table border="1" data-bbox="335 1384 1401 1841"> <thead> <tr> <th>Description</th> <th>Amount</th> <th>Indexed</th> <th>Council Fee Code</th> </tr> </thead> <tbody> <tr> <td colspan="4">SECURITY under section 4.17(6) of the <i>Environmental Planning and Assessment Act 1979</i></td> </tr> <tr> <td>Property Damage Security Deposit - making good any damage caused to any property of the Council</td> <td>\$85,540.00</td> <td>No</td> <td>T115</td> </tr> <tr> <td colspan="4">INSPECTION FEES under section 608 of the <i>Local Government Act 1993</i></td> </tr> <tr> <td>Security Deposit Administration Fee</td> <td>\$225.00</td> <td>No</td> <td>T16</td> </tr> <tr> <td>TOTAL SECURITY AND FEES</td> <td>\$85,765.00</td> <td></td> <td></td> </tr> </tbody> </table> <p>How must the payments be made? Payments must be made by:</p> <ul style="list-style-type: none"> • cash deposit with Council, • credit card payment with Council, or • bank cheque made payable to Woollahra Municipal Council. 	Description	Amount	Indexed	Council Fee Code	SECURITY under section 4.17(6) of the <i>Environmental Planning and Assessment Act 1979</i>				Property Damage Security Deposit - making good any damage caused to any property of the Council	\$85,540.00	No	T115	INSPECTION FEES under section 608 of the <i>Local Government Act 1993</i>				Security Deposit Administration Fee	\$225.00	No	T16	TOTAL SECURITY AND FEES	\$85,765.00		
Description	Amount	Indexed	Council Fee Code																						
SECURITY under section 4.17(6) of the <i>Environmental Planning and Assessment Act 1979</i>																									
Property Damage Security Deposit - making good any damage caused to any property of the Council	\$85,540.00	No	T115																						
INSPECTION FEES under section 608 of the <i>Local Government Act 1993</i>																									
Security Deposit Administration Fee	\$225.00	No	T16																						
TOTAL SECURITY AND FEES	\$85,765.00																								

The payment of a security may be made by a bank guarantee where:

- the guarantee is by an Australian bank for the amount of the total outstanding contribution,
- the bank unconditionally agrees to pay the guaranteed sum to the Council on written request by Council on completion of the development or no earlier than 12 months from the provision of the guarantee whichever occurs first [NOTE: a time limited bank guarantee or a bank guarantee with an expiry date is not acceptable],
- the bank agrees to pay the guaranteed sum without reference to the Applicant or landowner or other person who provided the guarantee and without regard to any dispute, controversy, issue or other matter relating to the development consent or the carrying out of development in accordance with the development consent,
- the bank guarantee is lodged with the Council prior to any site works being undertaken, and
- the bank's obligations are discharged when payment to the Council is made in accordance with the guarantee or when Council notifies the bank in writing that the guarantee is no longer required.


Notes:

- An application must be made to Council by the person who paid the security for release of the securities held under section 4.17 of the Act.
- The securities will not be released until the Occupation Certificate has been lodged with Council, Council has inspected the site and Council is satisfied that the public works have been carried out to Council's requirements. Council may use part or all of the security to complete the works to its satisfaction if the works do not meet Council's requirements.
- Council will only release the security upon being satisfied that all damage or all works, the purpose for which the security has been held have been remedied or completed to Council's satisfaction as the case may be.
- Council may retain a portion of the security to remedy any defects in any such public work that arise within 6 months after the work is completed.
- Upon completion of each section of road, drainage and landscape work to Council's satisfaction, 90% of the bond monies held by Council for these works will be released upon application. 10% may be retained by Council for a further 6 month period and may be used by Council to repair or rectify any defects or temporary works during the 6 month period.
- The Refund of Security Bond Application form can be downloaded from www.woollahra.nsw.gov.au

Condition Reason: To ensure any relevant security and fees are paid.


B. 6. Security Fencing, Hoarding (including 'Creative Hoardings') and Overhead Protection

Before any site work commences, security fencing must be provided around the perimeter of the development site, including any additional precautionary measures taken to prevent unauthorised entry to the site at all times during the demolition, excavation and construction period. Security fencing must be the equivalent 1.8m high chain wire as specified in AS 1725.



Type A Hoarding

Where the development site adjoins a public thoroughfare, the common boundary between them must be fenced for its full length with a hoarding, unless the least horizontal distance between the common boundary and the nearest parts of the structure is greater than twice the height of the structure. The hoarding must be constructed of solid materials (chain wire or the like is not acceptable) to a height of not less than 1.8m adjacent to the thoroughfare.




Type B Hoarding

Where a development site adjoins a public thoroughfare with a footpath alongside the common boundary then, in addition to the hoarding required above, the footpath must be covered by an overhead protective structure and the facing facade protected by heavy-duty scaffolding, unless either:

- the vertical height above footpath level of the structure being demolished is less than 4.0m; or
- the least horizontal distance between footpath and the nearest part of the structure is greater than half the height of the structure.

The overhead structure must consist of a horizontal platform of solid construction and vertical supports, and the platform must:

- extend from the common boundary to 200mm from the edge of the carriageway for the full length of the boundary,
- have a clear height above the footpath of not less than 2.1m,
- terminate 200mm from the edge of the carriageway (clearance to be left to prevent impact from passing vehicles) with a continuous solid upstand projecting not less than 0.5m above the platform surface, and
- together with its supports, be designed for a uniformly distributed live load of not less than 7 kPa.



The overhead protective structures must be installed and maintained in accordance with the NSW "Code of Practice - Overhead Protective Structures 1995". This is code available at www.safework.nsw.gov.au/__data/assets/pdf_file/0008/52883/Overhead-protective-structures-Code-of-practice.pdf

All Hoardings

Security fencing, hoarding and overhead protective structure must not obstruct access to utilities services including but not limited to man holes, pits, stop valves, fire hydrants or the like.

	<p>Hoardings on Public Land including ‘Creative Hoardings’ All fees associated with the application and occupation and use of the road (footway) for required hoarding or overhead protection must be paid in full.</p> <p>A creative hoarding (i.e. an approved artwork or historic image affixed to the hoarding) is required if the hoarding meets the criteria in Council’s Creative Hoardings Policy (adopted March 2020). The cost of printing and affixing the creative hoarding is the responsibility of the person with the benefit of this consent. The Creative Hoardings Policy can be downloaded from Council’s website www.woollahra.nsw.gov.au</p> <p>Notes:</p> <ul style="list-style-type: none"> • A minimum of two (2) weeks from the date of making a hoarding application to determination must be allowed. Any approval for a hoarding or overhead protection under the Roads Act 1993 will be subject to its own conditions and fees. • Council seeks to increase public art in the public domain by requiring artwork or historic images on hoardings located on public land. Under the Creative Hoardings Policy an application for a hoarding proposed on public land will require an approved artwork or historic image affixed to the hoarding if the hoarding meets the criteria in section 3 of the Policy: <ul style="list-style-type: none"> A. Hoardings proposed on land zoned E1 Local Centre, or MU1 Mixed Use, or SP2 Infrastructure under Woollahra Local Environmental Plan 2014 AND erected for 8 weeks or more OR B. Hoardings proposed on land located along a State classified road (regardless of the zone) AND erected for 8 weeks or more OR C. Hoardings proposed in any other location than that referred to in A. and B. above AND erected for 12 weeks or more, except where: <ul style="list-style-type: none"> 1. the capital investment value of the work to which the hoarding relates is less than \$1 million, or 2. the land is zoned R2 Low Density Residential, or 3. the land is zoned R3 Medium Density Residential and the hoarding is located in a lane or street that does not have through traffic (e.g. a cul-de-sac or no through road). • Artwork and historic images for the hoardings are assessed and approved in accordance with the Creative Hoardings Policy. Details of the artwork or images proposed to be affixed to the hoardings must be submitted with Council’s form “Application for a permit to use a footpath for the erection of a hoarding/scaffolding”. The Creative Hoardings Policy can be downloaded from www.woollahra.nsw.gov.au
	<p>Condition Reason: To ensure public safety.</p>
<p>B. 7.</p>	<p>Site Signs</p> <p>Before any site work commences, the sign/s required by clauses 70 of the Regulation and 75 of the Development Certification and Fire Safety Regulation must be erected and maintained at all times.</p> <p>Clause 70 of the Regulation provides:</p> <p>Erection of signs</p> <ul style="list-style-type: none"> • For the purposes of section 4.17(11) of the Act, the requirements of subclauses (2) and (3) are prescribed as conditions of a development consent for development that involves any building work, subdivision work or demolition work. • A sign must be erected in a prominent position on any site on which building work, subdivision work or demolition work is being carried out:

- a) showing the name, address and telephone number of the principal certifier for the work, and
- b) showing the name of the principal contractor (if any) for any building work and a telephone number on which that person may be contacted outside working hours, and
- c) stating that unauthorised entry to the work site is prohibited.
- Any such sign is to be maintained while the building work, subdivision work or demolition work is being carried out, but must be removed when the work has been completed.
- This clause does not apply in relation to building work, subdivision work or demolition work that is carried out inside an existing building that does not affect the external walls of the building.
- This clause does not apply in relation to Crown building work that is certified, in accordance with section 6.28 of the Act, to comply with the Building Code of Australia.

Clause 75 of the Development Certification and Fire Safety Regulation provides:

Signs on development sites

If there is a person who is the Principal Certifier or the Principal Contractor for any building work, subdivision work or demolition work authorised to be carried out on a site by a development consent or complying development certificate:

- Each such person MUST ensure that a rigid and durable sign showing the person’s identifying particulars so that they can be read easily by anyone in any public road or other public place adjacent to the site is erected in a prominent position on the site before the commencement of work, and is maintained on the site at all times while this clause applies until the work has been carried out.

Notes:

- Clause 75 of the Development Certification and Fire Safety Regulations imposes a maximum penalty of 55 penalty units if these requirements are not complied with.
- If Council is appointed as the Principal Certifier it will provide the sign to the Principal Contractor or Owner-builder who must ensure that the sign is erected and maintained as required by clause 70 of the Regulation and clause 75 of the Development Certification and Fire Safety Regulation.

Condition Reason: To ensure that contact details for the principal certifier and principal contractor are provided on a sign at the development site.

B. 8. Toilet Facilities

Before any site work commences, toilet facilities are to be provided, at or in the vicinity of the work site on which work involved in the erection or demolition of a building is being carried out, at the rate of one toilet for every 20 persons or part of 20 persons employed at the site.

Each toilet provided:

- a) must be a standard flushing toilet, and
- b) must be connected to a public sewer, or
- c) if connection to a public sewer is not practicable, to an accredited sewage management facility approved by the Council, or
- d) if connection to a public sewer or an accredited sewage management facility is not practicable, to some other sewage management facility approved by the Council.

	<p>The provision of toilet facilities in accordance with this condition must be completed before any other work is commenced.</p> <p>Notes:</p> <ul style="list-style-type: none"> • In this condition ‘sewage management facility’ and ‘public sewer’ are as defined by clause 25 of the Local Government (Approvals) Regulation 1999. • This condition does not set aside the requirement to comply with SafeWork NSW requirements. <p>Condition Reason: To ensure toilet facilities are provided for workers at the work site.</p>
<p>B. 9.</p>	<p>Establishment of Boundary Location, Building Location and Datum</p> <p>Before any site work commences, a surveyor registered under the Surveying and Spatial Information Act 2002 must:</p> <ol style="list-style-type: none"> set out the boundaries of the site by permanent marks (including permanent recovery points), set out the location and level of foundation excavations, footings, walls and slabs by permanent marks, pegs or profiles relative to the boundaries of the land and relative to Australian Height Datum (AHD) in compliance with the approved plans, establish a permanent datum point (bench mark) within the boundaries of the site relative to AHD, and provide a copy of a survey report, prepared by the registered surveyor, detailing the title boundaries, pegs/profiles, recovery points and bench mark locations as established under this condition to the Principal Certifier. <p>Notes:</p> <ul style="list-style-type: none"> • Where there is any discrepancy between the approved development consent and the Construction Certificate, especially in relation to the height, location or external configuration of the building (but not limited to these issues) the site works must not proceed until the variations as shown are consistent with the consent. Failure to do so may result in a breach of development consent. • On larger developments, or where boundary redefinition is required, the placement of new State Survey Marks as permanent marks must be considered by the registered surveyor. <p>Condition Reason: To ensure that the boundary locations, building location, and a datum point is established by a surveyor.</p>
<p>B. 10.</p>	<p>Compliance with Australian Standard for Demolition</p> <p>While site work is being carried out, the demolition of buildings and structures must comply with Australian Standard AS 2601—2001: The Demolition of Structures.</p> <p>Condition Reason To control the risks of demolition work.</p>
<p>B. 11.</p>	<p>Dilapidation Reports for Existing Buildings</p> <p>Before any site work commences, dilapidation surveys and dilapidation reports must be conducted and prepared by a professional structural engineer for all buildings and/or structures that are located within the likely “zone of influence” of any excavation, dewatering and/or construction induced vibration as determined applicable by the structural engineer.</p> <p>These properties must include (but is not limited to):</p> <ol style="list-style-type: none"> 16 Manning Road 4-8 Patterson Street

	<p>Where access is not granted to any adjoining properties to prepare the dilapidation report, the report must be based on a survey of what can be observed externally and it must be demonstrated, in writing, to the satisfaction of the Principal Certifier, that all reasonable steps were taken to obtain access.</p> <p>The completed dilapidation reports must be submitted to the Principal Certifier for approval, and an approved copy of the reports must be submitted to Council with the Notice of Commencement prior to the commencement of any development work.</p> <p>No less than two (2) days before any site work commences, neighbouring building owner(s) must be provided with a copy of the dilapidation report for their property(ies).</p> <p>Notes:</p> <ul style="list-style-type: none"> • The dilapidation report will be made available to affected property owners on request and may be used by them in the event of a dispute relating to damage allegedly caused by the carrying out of the development. • This condition cannot prevent neighbouring buildings being damaged by the carrying out of the development. • Council will not be held responsible for any damage which may be caused to adjoining buildings as a consequence of the development being carried out. • Council will not become directly involved in disputes between the developer, its contractors and the owners of neighbouring buildings. <p>Condition Reason: To establish and document the structural condition of adjoining properties for comparison as site work progresses and is completed and ensure neighbours and Council are provided with the dilapidation report.</p>
<p>B. 12.</p>	<p>Dilapidation Reports for Public Infrastructure</p> <p>Before any site work commences, to clarify the existing state of public infrastructure prior to the commencement of the development (including prior to any demolition), a dilapidation report, prepared by a chartered professional engineer, on Council's infrastructure within and near the development site must be prepared.</p> <p>The dilapidation report must be submitted to Council prior to the commencement of any site work and include:</p> <ol style="list-style-type: none"> a) photographs showing any existing damage to the road pavement fronting the site, b) photographs showing any existing damage to the kerb and gutter fronting the site, c) photographs showing any existing damage to the footway including footpath pavement fronting the site, d) photographs showing any existing damage to retaining walls within the footway or road, e) photographs showing any existing damage to street signs, heritage name plates, and historical items, f) the full name and signature of the Chartered Professional Engineer. <p>The report is to be supplied in both paper copy and electronic format in PDF. Photographs are to be in colour, digital, and date stamped.</p> <p>The dilapidation report must specify (with supporting photographic/DVD evidence) the exact location and extent of any damaged or defective public infrastructure prior to the commencement of any site work. If the required report is not submitted, Council will assume there was no damage to any infrastructure in the immediate vicinity of the site prior to the commencement of any site work under this consent.</p>

	<p>Notes:</p> <ul style="list-style-type: none"> • If a dilapidation report is not submitted as required by this condition, and damage is occasioned to public assets, which adjoin the site, Council will deduct from security any costs associated with remedying, repairing or replacing damaged public infrastructure. • Nothing in this condition prevents Council making any claim against security held for this purpose. <p>Condition Reason: To establish and document the structural condition of public land for comparison as site work progresses and is completed and ensure Council is provided with the dilapidation report.</p>
<p>B. 13.</p>	<p>Adjoining Buildings Founded on Loose Foundation Materials</p> <p>Before any site work commences, a professional engineer must determine the possibility of any adjoining buildings founded on loose foundation materials being affected by piling, piers or excavation. The professional engineer (geotechnical consultant) must assess the requirements for underpinning any adjoining or adjacent buildings founded on such soil on a case by case basis, and any reasonable direction of the professional engineer must be complied with.</p> <p>Notes:</p> <ul style="list-style-type: none"> • A failure to adequately assess and seek professional engineering (geotechnical) advice to ensure that appropriate underpinning and support to adjoining land is maintained prior to commencement may result in damage to adjoining land and buildings. • The person with the benefit of this consent is likely to be held responsible for any damages arising from the removal of any support to supported land as defined by section 177 of the Conveyancing Act 1919. <p>Condition Reason: To ensure professional engineering advice is obtained to confirm that appropriate underpinning and support to adjoining land is maintained.</p>
<p>B. 14.</p>	<p>Piezometers for the Monitoring of Ground Water Levels</p> <p>Before any site work commences, 2 piezometers within the excavation area and a further 2 piezometers around the perimeter of the wall must be provided. The piezometers are to be installed to monitor ground water levels (GWL) before and during all dewatering works for the construction phase.</p> <p>The GWL monitoring wells and monitoring program must be maintained until the issue of the occupation certificate.</p> <p>The GWL are to be regularly monitored during the course of the works as required by the work method statement for the control of GWL. Any damaged piezometers are to be replaced to allow uninterrupted monitoring.</p> <p>Where there are any movements in the GWL outside a safe range set by the work method statement for the control of GWL, corrective action must be undertaken under the direction of the professional engineer (hydrological/geotechnical engineer).</p> <p>Condition Reason: To ensure that piezometers are provided to monitor ground water levels.</p>

B. 15. Establishment Tree Protection Measures within the Tree Protection Zones (TPZ)

Prior to any site works, tree protection measures must be established around all trees to be retained in accordance with Section 4 of the Australian Standard Protection of Trees on Development Sites (AS 4970).

The Tree Protection Zones must be calculated in accordance with Section 3 of the Australian Standard Protection of Trees on Development Sites (AS 4970).

A Construction Site Management Plan, which clearly details the tree protection measures, must be prepared before the issue of a construction certificate. The tree protection measures must comply with the following requirements;

a) Tree Protection Fencing:

Council Ref No	Species	Tree Location	Fence Radius from Centre of Trunk (Metres)*
1	<i>Archontophoenix cunninghamiana</i>	Front Yard – western boundary	1m
4	<i>Archontophoenix cunninghamiana</i>	Front Yard – western boundary	1m
10	<i>Washingtonia robusta</i>	Rear Yard – northern boundary	1m

Where this condition relates to street trees, and the fence cannot be placed at the specified radius, the fencing is to be positioned so that the entire verge (nature strip) area in front of the subject property, excluding existing driveways and footpaths, and bus stops is protected.

Where this condition relates to trees on private property, the radial distance of fencing must be positioned only within the subject property relating to the development consent.

- b) Tree Protection Zones must be fenced with a 1.8 metre high chainmesh or weldmesh fence and secured to restrict access. The fence must be established prior to any materials being brought onto the site and before the commencement of works including demolition. The area within the fence must be mulched and the mulch layer maintained to a depth of 75mm. The soil within the TPZ area must be kept in a moist condition for the duration of the construction works. Unless approved by the site arborist there must be no access within the TPZ area.
- c) Signs identifying the Tree Protection Zone area must be erected on each side of the protection fence indicating the existence of a TPZ area. Signage must be visible from within the development site.
- d) No excavation, construction activity, grade changes, storage of materials, stockpiling, siting of works sheds, preparation of mixes or cleaning of tools is permitted within Tree Protection Zones, unless specified in this consent.
- e) Temporary access within the TPZ area for pedestrian and machinery movements must only be permitted with the approval of the site arborist or unless specified in this consent.

	<p>f) The site supervisor must be made aware of all tree protection requirements associated with these conditions of consent by the project arborist. Any subsequent site personnel and contractors to the site must be made aware of all tree protection requirements by the site foreman.</p> <p>g) The project arborist must provide written certification of compliance to the Principal Certifier with the above conditions.</p> <p>Condition Reason: To ensure the protection of existing trees</p>
<p>B. 16.</p>	<p>Construction Management Plan Arborist Review</p> <p>Prior to any site works, the Construction Management Plan must be reviewed and certified by the Project Arborist confirming that appropriate tree protection measures are implemented. The Construction Management Plan must be prepared in accordance with all tree protection measures specified within this consent.</p> <p>The plan must address:</p> <ol style="list-style-type: none"> a) Drawings and method statement showing details and the location of hoarding and scaffold and any pruning required to accommodate the hoarding and scaffolding; b) The movement and positioning of heavy machinery, lifting cranes, pier drilling gantry etc.; c) Site construction access, temporary crossings and movement corridors on the site defined; d) Contractors car parking; e) Phasing of construction works; f) The space needed for all foundation excavations and construction works; g) All changes in ground level; h) Space for site sheds and other temporary structures such as toilets; i) Space for sorting and storing materials (short or long term), spoil and fuel and the mixing of cement and concrete; and j) The effects of slope on the movement of potentially harmful liquid spillages towards or into tree protection areas. <p>Condition Reason To ensure the Construction Management Plan incorporates measures for the protection of existing trees.</p>
<p>B. 17.</p>	<p>Arborists Documentation and Compliance Checklist</p> <p>Prior to any site works, the project arborist must provide written certification that all tree protection measures and construction techniques relevant to this consent are implemented. Documentation for each site visit must include:</p> <ul style="list-style-type: none"> • A record of the condition of trees to be retained prior to and throughout development. • Recommended actions to improve site conditions and rectification of non-compliance. • Recommendations for future works which may impact the trees. <p>All compliance certification documents must be kept on site.</p> <p>As a minimum the following intervals of site inspections must be made:</p>

	<table border="1" data-bbox="335 197 1401 600"> <tr> <th data-bbox="335 197 639 320">Stage of arboricultural inspection and supervision</th> <th data-bbox="639 197 1401 320">Compliance documentation and photos must include</th> </tr> <tr> <td data-bbox="335 320 639 600">Prior to any site works</td> <td data-bbox="639 320 1401 600"> <ul style="list-style-type: none"> Project Arborist to hold pre construction site meeting with the principal contractor to discuss methods and importance of tree protection measures and resolve any issues in relation to feasibility of tree protection requirements that may arise. Project Arborist to mark all trees approved for removal under DA consent. The project arborist must install or supervise the installation of tree protection fencing, trunk protection, ground protection and traffic height control beam. </td> </tr> </table> <p data-bbox="335 638 1417 705">Inspections and compliance documentation must be made by an arborist with AQF Level 5 qualifications.</p> <p data-bbox="335 739 1380 806">Additional site visits must be made when required by the site arborist and/or site foreman for ongoing monitoring/supervisory work.</p> <p data-bbox="335 840 1332 940">Condition Reason To ensure that written certification that all tree protection measures and construction techniques relevant to this consent have been implemented.</p>	Stage of arboricultural inspection and supervision	Compliance documentation and photos must include	Prior to any site works	<ul style="list-style-type: none"> Project Arborist to hold pre construction site meeting with the principal contractor to discuss methods and importance of tree protection measures and resolve any issues in relation to feasibility of tree protection requirements that may arise. Project Arborist to mark all trees approved for removal under DA consent. The project arborist must install or supervise the installation of tree protection fencing, trunk protection, ground protection and traffic height control beam. 												
Stage of arboricultural inspection and supervision	Compliance documentation and photos must include																
Prior to any site works	<ul style="list-style-type: none"> Project Arborist to hold pre construction site meeting with the principal contractor to discuss methods and importance of tree protection measures and resolve any issues in relation to feasibility of tree protection requirements that may arise. Project Arborist to mark all trees approved for removal under DA consent. The project arborist must install or supervise the installation of tree protection fencing, trunk protection, ground protection and traffic height control beam. 																
<p data-bbox="175 985 295 1019">B. 18.</p>	<p data-bbox="327 985 989 1019">Permissible work within Tree Protection Zones</p> <p data-bbox="327 1052 1444 1120">Prior to any site works, the following works are permissible within the Tree Protection Zone:</p> <table border="1" data-bbox="335 1153 1401 1438"> <thead> <tr> <th data-bbox="335 1153 470 1220">Council Ref No</th> <th data-bbox="470 1153 758 1220">Species</th> <th data-bbox="758 1153 1061 1220">Radius from Centre of Trunk (Metres)</th> <th data-bbox="1061 1153 1401 1220">Approved works</th> </tr> </thead> <tbody> <tr> <td data-bbox="335 1220 470 1276">1</td> <td data-bbox="470 1220 758 1276"><i>Archontophoenix cunninghamiana</i></td> <td data-bbox="758 1220 1061 1276">2m</td> <td data-bbox="1061 1220 1401 1276">Landscape works</td> </tr> <tr> <td data-bbox="335 1276 470 1332">4</td> <td data-bbox="470 1276 758 1332"><i>Archontophoenix cunninghamiana</i></td> <td data-bbox="758 1276 1061 1332">2m</td> <td data-bbox="1061 1276 1401 1332">Landscape works</td> </tr> <tr> <td data-bbox="335 1332 470 1438">10</td> <td data-bbox="470 1332 758 1438"><i>Washingtonia robusta</i></td> <td data-bbox="758 1332 1061 1438">2m</td> <td data-bbox="1061 1332 1401 1438">Landscape works, construction of new driveway</td> </tr> </tbody> </table> <p data-bbox="327 1467 1412 1534">The project arborist must provide written certification of compliance to the Principal Certifier with the above condition.</p> <p data-bbox="327 1568 1380 1635">Condition Reason To establish the works which are permissible within the Tree Protection Zones.</p>	Council Ref No	Species	Radius from Centre of Trunk (Metres)	Approved works	1	<i>Archontophoenix cunninghamiana</i>	2m	Landscape works	4	<i>Archontophoenix cunninghamiana</i>	2m	Landscape works	10	<i>Washingtonia robusta</i>	2m	Landscape works, construction of new driveway
Council Ref No	Species	Radius from Centre of Trunk (Metres)	Approved works														
1	<i>Archontophoenix cunninghamiana</i>	2m	Landscape works														
4	<i>Archontophoenix cunninghamiana</i>	2m	Landscape works														
10	<i>Washingtonia robusta</i>	2m	Landscape works, construction of new driveway														
<p data-bbox="175 1691 295 1724">B. 19.</p>	<p data-bbox="327 1758 1428 1859">While site work is being carried out, if a person reasonably suspects archaeological features are discovered, work must cease immediately in the affected area(s) and the Heritage Council must be notified.</p> <p data-bbox="327 1892 1428 1960">Site work may recommence at a time confirmed in writing by the Heritage Council or its delegate.</p> <p data-bbox="327 1993 1444 2060">Additional assessment and approval under the Heritage Act 1977 may be required prior to works continuing in the affected area(s) based on the nature of the discovery.</p>																

	<p>Notes:</p> <ul style="list-style-type: none"> • Definition of archaeological feature as per the NSW Heritage Manual: Any physical evidence of past human activity. • Archaeological features include buildings, works, relics, structures, foundations, deposits, cultural landscapes and shipwrecks. • During an archaeological excavation the term ‘feature’ may be used in a specific sense to refer to any item that is not a structure, a layer or an artefact (for example, a post hole). <p>Condition Reason: To protect archaeological features.</p>
<p>B. 20.</p>	<p>Skeletal Remains</p> <p>While site work is being carried out, if any skeletal remains suspected of being human are found, work must cease immediately and no further disturbance of the site must occur. The following must be notified:</p> <ol style="list-style-type: none"> a) NSW Police, and b) The person who is the authority for the protection of Aboriginal objects under the National Parks and Wildlife Act 1974, section 85. <p>Details of the remains and their precise location are to be provided.</p> <p>Site work may recommence at a time confirmed in writing by the NSW Police and the person who is the authority for the protection of Aboriginal objects under the National Parks and Wildlife Act 1974, section 85.</p> <p>Condition Reason: To ensure the appropriate management of skeletal remains.</p>
<p>B. 21.</p>	<p>Aboriginal Objects – Unexpected Findings</p> <p>While site work is being carried out, if unexpected Aboriginal objects or bones are found, you must:</p> <ol style="list-style-type: none"> a) Not further disturb or move these objects or bones. b) Immediately cease all work at the particular location. c) In the case of suspected human remains, notify NSW Police. d) Notify the Heritage NSW Environment Line on 131 555 and the La Perouse Land Council (LALC) on (02) 9311 4282 as soon as practicable and provide available details of the objects or remains and their location. e) Notify the person who is the authority for the protection of Aboriginal objects under the National Parks and Wildlife Act 1974, section 85. f) Not recommence any work at the particular location unless authorised in writing by the police (in the case of human remains) and the person who is the authority for the protection of Aboriginal objects under the National Parks and Wildlife Act 1974, section 85. Additional assessment and approval under the National Parks and Wildlife Act 1974 may be required prior to works continuing in the affected area(s) based on the nature of the discovery. <p>Notes:</p> <ul style="list-style-type: none"> • The Definition of Aboriginal object, as per the National Parks & Wildlife Act 1974, is any deposit, object or other material evidence (not being a handicraft made for sale) relating to the Aboriginal habitation of an area of New South Wales, being habitation before or concurrent with (or both) the occupation of that area by persons of non-Aboriginal extraction, and includes Aboriginal remains. <p>Condition Reason: To protect Aboriginal objects</p>

<p>B. 22.</p>	<p>Aboriginal Heritage Due Diligence Responsibilities</p> <p>While site work is being carried out, nothing in this approval allows to cause harm to an Aboriginal object as defined in the National Parks & Wildlife Act 1974. Under the National Parks & Wildlife Act 1974, it is an offence to harm Aboriginal 'objects' (consisting of any material evidence of the Aboriginal occupation of NSW) without a valid Aboriginal Heritage Impact Permit under Section 90 of the Act. This applies whether the harm occurs either knowingly [s86(1)] or unknowingly [s86(2)].</p> <p>It is a defence to the strict liability offence of harm to an Aboriginal object under s86(2) if a process of Due Diligence was followed which reasonably determined that the proposed activity would not harm an Aboriginal object.</p> <p>Condition Reason: To protect Aboriginal heritage.</p>						
<p>B. 23.</p>	<p>Aboriginal Heritage Induction</p> <p>Prior to any site works:</p> <ul style="list-style-type: none"> a) All construction staff and contractors must be made aware of their statutory obligations for Aboriginal heritage under the National Parks and Wildlife Act 1974; b) An Aboriginal heritage induction is to be delivered by the La Perouse Local Aboriginal Land Council, or by a heritage consultant with Aboriginal heritage expertise (if a representative of the Local Land Council is not able to provide the induction), to explain what Aboriginal heritage may be found and outline the unexpected findings procedures; and c) Documentary evidence demonstrating compliance with a) and b) above must be submitted to Council and the Principal Certifier. <p>Condition Reason: To protect Aboriginal heritage.</p>						
<p>B. 24.</p>	<p>Recording of Building Prior to any Demolition or Alteration</p> <p>Prior to any site works and prior to the issue of any Construction Certificate, a full archival record of the building and landscape elements to be altered is to be submitted, to the satisfaction of Council's heritage officer.</p> <p>The archival record must be completed by a heritage consultant listed on the Consultants Directory by the NSW Office of Environment and Heritage, or by a suitably qualified consultant who demonstrates a working knowledge of archival principles.</p> <p>Photographic archival records must be taken of the building, landscape or item in accordance with 'The Heritage Information Series: Photographic Recording of Heritage Items Using Film or Digital Capture 2006' published by the former NSW Department of Planning Heritage Branch.</p> <p>There must be one digital set of the photographic report. The following table summarises the lodgement details for photographic records.</p> <table border="1" data-bbox="331 1877 1401 2022"> <thead> <tr> <th>Material</th> <th>Minimum Requirement</th> <th>Repository</th> </tr> </thead> <tbody> <tr> <td>Digital Materials</td> <td>1 copy of photographic report including images</td> <td>Woollahra Council – Report and images (digital)</td> </tr> </tbody> </table>	Material	Minimum Requirement	Repository	Digital Materials	1 copy of photographic report including images	Woollahra Council – Report and images (digital)
Material	Minimum Requirement	Repository					
Digital Materials	1 copy of photographic report including images	Woollahra Council – Report and images (digital)					

	<p>The photographic archival recording is to be submitted in a digital format and is to include the following:</p> <ol style="list-style-type: none"> a) Site plan at a scale of 1:200 (or 1:500 if appropriate) of all structures and major landscape elements including their relationship to the street and adjoining properties and directional details of photographs taken. b) Floorplans of the internal layout and directional details of photographs taken. c) Coloured photographs of: <ul style="list-style-type: none"> • each elevation, • each structure and landscape feature, • internal images of each room and significant architectural detailing, and • views to the subject property from each street and laneway or public space. <p>Notes:</p> <ul style="list-style-type: none"> • Refer to the NSW Office of Environment and Heritage website for the free publication 'Photographic Recording of Heritage Items using Film or Digital Capture' available at https://www.environment.nsw.gov.au/-/media/OEH/Corporate-Site/Documents/Heritage/photographic-recording-of-heritage-items-using-film-or-digital-capture.pdf <p>Condition Reason: To ensure existing building and landscape elements are recorded.</p>
<p>B. 25.</p>	<p>Construction Management Plan</p> <p>Before any site work commences, and as a result of the site constraints, limited space and access, a Construction Management Plan (CMP) is to be submitted to Council for approval. Also, due to lack of on-street parking a Work Zone may be required during construction.</p> <p>An application for the CMP must be submitted for approval, and all associated application fees must be paid.</p> <p>The CMP must be submitted as a self-contained document that outlines the nature of the construction project and as applicable, include the following information:</p> <ol style="list-style-type: none"> a) Detail the scope of the works to be completed including details of the various stages, e.g. demolition, excavation, construction etc. and the duration of each stage. b) Identify local traffic routes to be used by construction vehicles. c) Identify ways to manage construction works to address impacts on local traffic routes, particularly during school pick-up and drop-off hours. d) Identify other developments that may be occurring in the area and identify ways to minimise the cumulative traffic impact of these developments. Should other developments be occurring in close proximity (500m or in the same street) to the subject site, the developer/builder is to liaise fortnightly with the other developers/builders undertaking work in the area in order to minimise the cumulative traffic and parking impacts of the developments. e) Detail how construction workers will travel to and from the site and parking arrangements for those that drive. f) Identify any proposed road closures, temporary traffic routes, loss of pedestrian or cyclist access, or reversing manoeuvres onto a public road, and provide Traffic Control Plans (TCPs) prepared by an accredited RMS Red or Orange card holder to manage these temporary changes. g) Detail the size (including dimensions), numbers and frequency of arrival of the construction vehicles that will service the site for each stage of works. h) Provide for the standing of vehicles during construction.

	<p>i) If construction vehicles are to be accommodated on the site, provide a scaled drawing showing where these vehicles will stand and the vehicle swept path to show that these vehicles can access and egress the site in a forward direction (including dimensions and all adjacent traffic control devices, such as parking restrictions, pedestrian facilities, kerb extensions, etc.).</p> <p>j) If trucks are to be accommodated on Council property, provide a scaled drawing showing the location of any proposed Works Zone (including dimensions and all adjacent traffic control devices, such as parking restrictions, pedestrian facilities, kerb extensions, etc.).</p> <p>k) Show the location of any site sheds and any anticipated use of cranes and concrete pumps and identify the relevant permits that will be required.</p> <p>l) If a crane/s are to be accommodated on site, detail how the crane/s will be erected and removed, including the location, number and size of vehicles involved in the erection/removal of the crane/s, the duration of the operation and the proposed day and times, any full or partial road closures required to erect or remove the crane/s and appropriate Traffic Control Plans (TCPs) prepared by an approved RMS Red or Orange Card holder.</p> <p>m) Make provision for all materials, plant, etc. to be stored within the development site at all times during construction.</p> <p>n) State that any oversized vehicles proposed to operate on Council property (including Council approved Works Zones) will attain a Permit to StandPlant on each occasion (Note: oversized vehicles are vehicles longer than 7.5m or heavier than 4.5T.)</p> <p>o) Show the location of any proposed excavation and estimated volumes.</p> <p>p) When demolition, excavation and construction works are to be undertaken on school days, all vehicular movements associated with this work must only be undertaken between the hours of 9.30am and 2.30pm, in order to minimise disruption to the traffic network during school pick up and drop off times.</p> <p>q) Show the location of all Tree Protection (Exclusion) zones (Note: storage of building materials or access through Reserve will not be permitted without prior approval by Council).</p> <p>Notes:</p> <ul style="list-style-type: none"> • A minimum of eight weeks will be required for assessment. Site work must not commence until the Construction Management Plan is approved. • Failure to comply with this condition may result in fines and proceedings to stop work. • Council and NSW Police approval is required prior to a partial or full temporary road closure. If you are seeking a partial or full temporary road closure you must comply with the relevant conditions of this consent and you must also gain the approval of the Eastern Suburbs Police Area Command. • If you partial or full close a road without compliance with Council and NSW Police requirements Council Rangers or the Police can issue Penalty Infringement Notices or Court Attendance Notices leading to prosecution. • Traffic Supervisors at the Eastern Suburbs Police Area Command can be contacted on eastsubtraffic@police.nsw.gov <p>Condition Reason: To facilitate the efficient operation of construction projects, minimise traffic disruption, and protect the public, and the surrounding environment, during site works and construction.</p>
<p>B. 26.</p>	<p>Works (Construction) Zone – Approval and Implementation</p> <p>If the Construction Management Plan relies upon a Works Zone, before any site work commences, a Works Zone application must be made.</p> <p>If the works zone is approved, all fees for the Works Zone must be paid before it can be installed.</p>

	<p>All Works Zone signs must have been erected by Council to permit enforcement of the Works Zone by Council's Rangers and NSW Police before commencement of any site work. Signs are not erected until full payment of Works Zone fees is made.</p> <p>Notes:</p> <ul style="list-style-type: none"> A minimum of four to six weeks must be allowed (for routine applications) from the date of making an application to the Traffic Committee (Woollahra Local Traffic Committee) constituted under clause 20 of the Transport Administration (General) Regulation 2018 to exercise those functions delegated by Transport for New South Wales under section 31(3) of the Transport Administration Act 1988. The enforcement of the Works Zone is at the discretion of Council's Rangers and the NSW Police Service. Any breach of the Works Zone must be reported to either Council or the NSW Police Service. <p>Condition Reason: To facilitate the efficient operation of construction projects and to minimise traffic disruption.</p>
<p>B. 27.</p>	<p>Noise Control Objectives during Demolition Works</p> <p>Prior to any siteworks, the NSW Department of Environment & Climate Change: Construction Noise Guideline must be applied to the site to provide a quantitative and qualitative assessment for evaluating performance and compliance of resultant noise from demolishing works of the existing dwelling and outbuilding. In particular reference is made to Table 2 of the NSW Department of Environment & Climate Change: Construction Noise Guideline which sets out management levels for noise at residences and other sensitive land uses.</p> <p>Condition Reason: To assist in managing impacts of noise from the demolishing of the existing building and outbuildings on residences and other sensitive land uses.</p>

REMEDIATION WORK

C. ON COMPLETION OF REMEDIATION WORK

Nil.

BUILDING WORK

D. BEFORE ISSUE OF A CONSTRUCTION CERTIFICATE

<p>D. 1.</p>	<p>Payment of Long Service Levy</p> <p>Before the issue of any construction certificate, the original receipt(s) for the payment of the following levy must be provided to the Principal Certifier:</p> <table border="1" data-bbox="335 1680 1420 1948"> <thead> <tr> <th>Description</th> <th>Amount</th> <th>Indexed</th> <th>Council Fee Code</th> </tr> </thead> <tbody> <tr> <td colspan="4">LONG SERVICE LEVY under <i>Building and Construction Industry Long Service Payments Act 1986</i></td> </tr> <tr> <td>Long Service Levy www.longservice.nsw.gov.au/bci/levy/other-information/levy-calculator</td> <td>Contact LSL Corporation or use online calculator</td> <td>No</td> <td></td> </tr> </tbody> </table>	Description	Amount	Indexed	Council Fee Code	LONG SERVICE LEVY under <i>Building and Construction Industry Long Service Payments Act 1986</i>				Long Service Levy www.longservice.nsw.gov.au/bci/levy/other-information/levy-calculator	Contact LSL Corporation or use online calculator	No	
Description	Amount	Indexed	Council Fee Code										
LONG SERVICE LEVY under <i>Building and Construction Industry Long Service Payments Act 1986</i>													
Long Service Levy www.longservice.nsw.gov.au/bci/levy/other-information/levy-calculator	Contact LSL Corporation or use online calculator	No											

	<p>Building and Construction Industry Long Service Payment The long service levy under section 34 of the Building and Construction Industry Long Service Payment Act 1986, must be paid and proof of payment provided to the Principal Certifier prior to the issue of any construction certificate. The levy can be paid directly to the Long Service Corporation or to Council. Further information can be obtained from the Long Service Corporation website www.longservice.nsw.gov.au or the Long Service Corporation on 131 441.</p> <p>How must the payments be made? Payments must be made by:</p> <ul style="list-style-type: none"> • cash deposit with Council, • credit card payment with Council, or • bank cheque made payable to Woollahra Municipal Council. <p>Condition Reason: To ensure any relevant levy is paid.</p>
<p>D. 2.</p>	<p>Modification of Details of the Development (section 4.17(1)(g) of the Act</p> <p>Before the issue of any construction certificate, the approved plans and the construction certificate plans and specification, required to be submitted to the Principal Certifier under clause 7 of the Development Certification and Fire Safety Regulations, must detail the following amendments:</p> <p>a) The garbage area, as shown on basement plan, must be redesigned to include the following-</p> <p style="padding-left: 40px;">The size and design of the waste and recycling area or areas must accommodate:</p> <ul style="list-style-type: none"> a) 120L of residual waste per residential dwelling; b) 55L of recyclables per residential dwelling stored in colour coded, shared use, 120L and/or 240L mobile garbage bins; c) 240L shared use mobile garbage bins for food and garden organics. <p>Notes:</p> <ul style="list-style-type: none"> • Clause 20 of the Development Certification and Fire Safety Regulations prohibits <i>the</i> issue of any construction certificate subject to this condition unless the Principal Certifier is satisfied that the condition has been complied with. • Clause 19 of the Development Certification and Fire Safety Regulations prohibits the issue of any construction certificate that is inconsistent with this consent. <p>Condition Reason: To require design changes and/or further information to be provided to address specific issues identified during the assessment under section 4.15 of the Act.</p>
<p>D. 3.</p>	<p>BASIX Commitments</p> <p>Before the issue of any construction certificate, BASIX Certificate No. 1377864M must be submitted to the Principal Certifier with any application for a construction certificate.</p> <p>All commitments in the BASIX Certificate must be shown on the construction certificate plans and specifications prior to the issue of any construction certificate.</p>

	<p>Notes:</p> <ul style="list-style-type: none"> Where there is any proposed change in the BASIX commitments the Applicant must submit a new BASIX Certificate to the Principal Certifier and Council. If any proposed change in the BASIX commitments are inconsistent with development consent (see: clauses 19 and 20 of the Development Certification and Fire Safety Regulation) the Applicant will be required to submit an amended development application to Council under section 4.55 of the Act. Clause 19(1)(a) of the Development Certification and Fire Safety Regulation 2021 provides: a certifier must not issue a construction certificate for building work unless: the relevant building work plans and specifications include the matters required by a relevant BASIX certificate, if any.
	<p>Condition Reason: To ensure all commitments in the BASIX Certificate are incorporated into the development.</p>
<p>D. 4.</p>	<p>Erosion and Sediment Control Plan – Submission and Approval</p> <p>Before the issue of any construction certificate, an erosion and sediment control plan, prepared by a suitably qualified person in accordance with the following documents, must be submitted to the Principal Certifier. The erosion and sediment control plan must comply with:</p> <ul style="list-style-type: none"> a) “Do it Right On Site, Soil and Water Management for the Construction Industry” and the accompanying factsheets published by the Southern Sydney Regional Organisation of Councils; and b) “Managing Urban Stormwater - Soils and Construction” 2004 published by the NSW Government (The Blue Book). <p>Where there is any conflict The Blue Book takes precedence.</p> <p>The Principal Certifier must be satisfied that the erosion and sediment control plan complies with the publications above prior to issuing any construction certificate.</p> <p>Notes:</p> <ul style="list-style-type: none"> The International Erosion Control Association – Australasia www.austieca.com.au lists consultant experts who can assist in ensuring compliance with this condition. Where erosion and sedimentation plans are required for larger projects it is recommended that expert consultants produce these plans. The “Do it Right On Site, Soil and Water Management for the Construction Industry” publication and accompanying factsheets can be downloaded from www.woollahra.nsw.gov.au, and The Blue Book is available at www.environment.nsw.gov.au Under clause 73(2)(a)(v) of the Development Certification and Fire Safety Regulation an Accredited Certifier may be satisfied as to this matter. <p>Condition Reason: To prevent potential water pollution and dust nuisance.</p>
<p>D. 5.</p>	<p>Professional Engineering Details</p> <p>Before the issue of any construction certificate, the construction certificate plans and specifications, required under clause 7 of the Development Certification and Fire Safety Regulation, must include detailed professional engineering plans and/or specifications for all structural, electrical, hydraulic, hydrogeological, geotechnical, mechanical and civil work complying with this consent, approved plans, and supporting documentation.</p> <p>Detailed professional engineering plans and/or specifications must be submitted to the Principal Certifier with the application for any construction certificate.</p>

	<p>Notes:</p> <ul style="list-style-type: none"> This does not affect the right of the developer to seek staged construction certificates. <p>Condition Reason: To ensure professional engineering details and technical specifications are provided.</p>
<p>D. 6.</p>	<p>Road and Public Domain Works</p> <p>Before the issue of any construction certificate, a separate application under Section 138 of the Roads Act 1993 is to be made to, and be approved by Council, for the following infrastructure works. The infrastructure works must be carried out at the applicant's expense:</p> <ol style="list-style-type: none"> The removal of the redundant vehicular crossing including layback and gutter and reinstated into Council's standard kerb and gutter and nature strip in accordance with Council's Specification for Roadworks, Drainage and Miscellaneous Works and to the satisfaction of Council's Assets Engineers, The construction of a new 3.2 metres wide vehicular crossing in accordance with Council's Crossing Specification, standard driveway drawing RF2_D and to the satisfaction of Council's Assets Engineers. The new vehicular crossing must be constructed at a right angle to the street kerb in plain concrete where the centreline of the new crossing must align with the centreline of the internal driveway at the property boundary. Design longitudinal surface profiles along each side/edge for the proposed driveway, starting from the road centreline to the parking slab must be submitted for assessment, The installation of a stormwater outlet pipe across the road reserve, from the property boundary pit to the existing Council's kerb inlet pit located on the northern side of Patterson Street, fronting No. 1 Kiaora Road. This outlet pipe must be made by using minimum 225mm diameter with full concrete encasement. An inspection eye shall be provided for this outlet pipe on the nature strip. The design shall be prepared in accordance with Council's Specification for Roadworks, Drainage and Miscellaneous Works and to the satisfaction of Council's Assets Engineers, In light of point (c) above, site plans and longitudinal sections (scale: 1:100) showing the stormwater outlet pipe and inspection eye must be submitted for assessment. All design details including chainages, invert levels, concrete encasement works and location of all existing public utility services must be included in the longitudinal section, The reconstruction of the existing concrete footpath including any kerb access ramps for the full frontage of the site in Manning Road and Patterson Street in accordance with Council's Specification, Council's standard drawing RF3 and to the satisfaction of Council's Assets Engineers. A maximum cross-fall of 3% must be provided for the footpath, graded from the property boundary towards the top of kerb. A design longitudinal surface profile (scale 1:100) and cross sections (scale 1:50) at every 5 metres interval must be submitted for assessment, The reinstatement of all damaged kerb and gutter and road pavement to Council's Specification for Roadworks, Drainage and Miscellaneous Works and to the satisfaction of Council's Assets Engineers. Where a grass verge exists, the balance of the area between the footpath and the kerb over the full frontage of the proposed development must be turfed. The grass verge must be constructed to contain a uniform minimum 75mm of friable growing medium and have a total cover of Couch turf. <p>Before the issue of any construction certificate, the principal certifier must be provided with the original receipt(s) for the payment of all of the following security bonds and fees:</p>

Description	Amount	Indexed	Council Fee Code
SECURITY under section 4.17(6) of the <i>Environmental Planning and Assessment Act 1979</i>			
Infrastructure Works Bond - completing any public work required in connection with the consent.	\$ 40,950.00	No	T113
Infrastructure Works Bond – remedying any defects in any public work that arise within 6 months after the work is completed	\$ Nil	No	T113
INSPECTION FEES under section 608 of the <i>Local Government Act 1993</i>			
Public Road and Footpath Infrastructure Inspection Fee	\$ 645.00	No	T45
TOTAL SECURITY AND FEES	\$ 41,595.00		

How must the payments be made?

Payments must be made by:

- cash deposit with Council,
- credit card payment with Council, or
- bank cheque made payable to Woollahra Municipal Council.

The payment of a security may be made by a bank guarantee where:

- the guarantee is by an Australian bank for the amount of the total outstanding contribution,
- the bank unconditionally agrees to pay the guaranteed sum to the Council on written request by Council on completion of the development or no earlier than 12 months from the provision of the guarantee whichever occurs first [NOTE: a time limited bank guarantee or a bank guarantee with an expiry date is not acceptable],
- the bank agrees to pay the guaranteed sum without reference to the Applicant or landowner or other person who provided the guarantee and without regard to any dispute, controversy, issue or other matter relating to the development consent or the carrying out of development in accordance with the development consent,
- the bank guarantee is lodged with the Council prior to any site works being undertaken, and
- the bank’s obligations are discharged when payment to the Council is made in accordance with the guarantee or when Council notifies the bank in writing that the guarantee is no longer required.

Notes:

- **Road** has the same meaning as in the Roads Act 1993.
- Changes in levels may arise from the detailed design of buildings, road, footpath, driveway crossing grades and stormwater. Changes required under Roads Act 1993 approvals may necessitate design and levels changes under this consent. This may in turn require the Applicant to seek to amend this consent.
- Works or structures over, on or under public roads or footpaths are subject to sections 138, 139 and 218 of the Roads Act 1993 and specifically:
 - Construction of driveways and/or new or alterations to footpath paving
 - Alteration and/or extension to Council drainage infrastructure
 - Alteration and/or addition of retaining walls
 - Pumping of water to Council’s below ground stormwater system
 - Installation of soil/rock anchors under the roadway
 - Installation of Stormwater outlet pipes across the nature strip

- An “Application to Carry Out Works in a Public Road” form must be completed and lodged, with the application fee, at Council’s Customer Services. Detailed plans and specifications of all works (including but not limited to structures, road works, driveway crossings, footpaths and stormwater drainage etc) within existing roads, must be attached, submitted to and approved by Council under section 138 of the Roads Act 1993, before the issue of any construction certificate.
- Detailed engineering plans and specifications of the works required by this condition must accompany the application form. The plans must clearly show the following:
- Engineering drawings (plan, sections and elevation views) and specifications of the footpath, driveways, kerb and gutter, new gully pit showing clearly the connection point of site outlet pipe(s). The connection drainage lines must be as direct as possible and generally run perpendicular to the kerb alignment.
- Engineering drawings of the new drainage line to be constructed joining the new and existing drainage pits including services.
- All driveways must include a design longitudinal surface profile for the proposed driveway for assessment. The driveway profile is to start from the road centreline and be along the worst case edge of the proposed driveway. Gradients and transitions must be in accordance with clause 2.5.3, 2.6 of AS 2890.1 – 2004, Part 1 – Off-street car parking. The driveway profile submitted to Council must be to (1:25) scale (for template checking purposes) and contain all relevant details: reduced levels, proposed grades and distances.
- The existing footpath level and grade at the street alignment of the property must be maintained unless otherwise specified by Council. Your driveway levels are to comply with AS2890.1 and Council’s Standard Drawings. There may be occasions where these requirements conflict with your development and you are required to carefully check the driveway/garage slab and footpath levels for any variations.
- Any adjustments required from the garage slab and the street levels are to be carried out internally on private property
- Drainage design works must comply with the Woollahra DCP 2015 Chapter E2 – Stormwater and Flood Risk Management.
- Temporary ground anchors may be permitted, in accordance with Council’s “Rock Anchor Policy”.
- Services: Prior to any excavation works, the location and depth of all public utility services (telephone, cable TV, electricity, gas, water, sewer, drainage, etc.) must be ascertained. The Applicant must be responsible for all public utility adjustment/relocation works, necessitated by the development work and as required by the various public utility authorities and/or their agents.
- All public domain works must comply with the latest version of Council’s “Specification for Roadworks, Drainage and Miscellaneous Works” unless expressly provided otherwise by these conditions. This specification and the application form can be downloaded from www.woollahra.nsw.gov.au.
- When an application under the Roads Act is required, then four (4) weeks is to be allowed for assessment.
- An application must be made to Council by the person who paid the security for release of the securities held under section 4.17 of the Act.
- The securities will not be released until the Occupation Certificate has been lodged with Council, Council has inspected the site and Council is satisfied that the public works have been carried out to Council’s requirements. Council may use part or all of the security to complete the works to its satisfaction if the works do not meet Council’s requirements.
- Council will only release the security upon being satisfied that all damage or all works, the purpose for which the security has been held have been remedied or completed to Council’s satisfaction as the case may be.
- When determining whether the works within public land are satisfactory, Council will consider the ownership, construction quality, maintenance, operations, and public utility of such item/s.
- Upon completion of each section of road, drainage and landscape work to Council’s satisfaction, 90% of the bond monies held by Council for these works will be released upon application. 10% may be retained by Council for a further 6 month period and may be used by Council to repair or rectify any defects or temporary works during the 6 month period.

	<p>Condition Reason: To ensure the design of the road, footpaths, driveway crossings and public stormwater drainage works are detailed and approved under section 138 of the Roads Act 1993 and to ensure the works are completed to Council's satisfaction.</p>
<p>D. 7.</p>	<p>Provision for Energy Supplies</p> <p>Before the issue of any construction certificate:</p> <ul style="list-style-type: none">a) A survey is to be carried out of all utility services within and adjacent to the site. If necessary, this shall include relevant information from utility authorities and excavation, to determine the position and level of services.b) The applicant is to obtain written approval from Ausgrid for the relocation, adjustment or installation of new services, or existing services affected by, or required for the development.c) The applicant shall provide to the Principal Certifier a true copy of the plans developed by the applicant's Accredited Service Provider outlining the design and requirements for network modification and customer connection for the proposed development. The plans must have been reviewed and certified by Ausgrid to be deemed compliant of meeting this requirement. <p>Any required substation must be located within the boundaries of the site. Where an electricity substation is required, but no provision has been made to place it within the building and such substation has not been detailed upon the approved development consent plans an application under section 4.55 of the Act is required to be submitted to Council.</p> <p>The design and location of any substation should have regard to the electrical substation provisions within the Woollahra Development Control Plan 2015, which require substations to be located and/or concealed so they are not visible from the street. The design and placement of electrical substations shall comply with Ausgrid's relevant Network Standards and will prioritise the placement of the substation at the front of the property.</p> <p>Where an electrical pillar is required, the electrical designer must consider the impact of all existing and proposed work when preparing their connection or relocation design. Site specific conditions such as existing/proposed property boundaries, building setbacks, other street furniture, street trees and pedestrian pathways will all be taken into account when specifying the final location of the pillar. The design should be compliant with Ausgrid's Network Standards and satisfy Council's objective to maintain a safe and accessible public domain for pedestrians:</p> <ul style="list-style-type: none">a) The design and location of underground and aboveground utility infrastructure shall consider the finished streetscape and not adversely impact existing pedestrian footpath, or, where the only permissible location for aboveground infrastructure will impact the footpath, the applicant shall widen the footpath to meet minimum accessibility requirements. <p>The construction certificate plans and specifications, required to be submitted under clause 7 of the Development Certification and Fire Safety Regulation, must detail provisions to meet the requirements of Ausgrid.</p> <p>Where an electricity pillar and/or substation is required, the construction certificate plans and specifications must provide:</p>

	<p>a) The substation shall be located or concealed so not visible from the street.</p> <p>b) A setback not less than 3m from any side or rear site boundary (or fire source feature) and not within the areas required to be kept clear of obstructions to vehicle visibility under clause 3.2.4 of AS2890.1 (See: Figures 3.2 and 3.3).</p> <p>c) That vegetation does not overhang or encroach within the substation site.</p> <p>d) That the substation is installed outside of the mature growth root zone of any trees to be retained, or proposed to be planted, to prevent root damage to underground cables. A setback not less than the 10m from any NSW Fire Brigade booster connection as prescribed by clause 5.6.3(d)(iii) of AS 2419.1 or be separated from any booster connections by a construction with a fire resistance rating of not less than FRL 90/90/90 for a distance of not less than 2 m each side of and 3 m above the upper hose connections in the booster assembly under clause 5.6.3(c)(ii) of AS 2419.1, and</p> <p>e) The Owner must dedicate to the appropriate energy authority, free of cost, an area of land adjoining the street alignment to enable a substation to be established, if required. The size and location of the substation is to be in accordance with the requirements of the appropriate energy authority and Council. The opening of any access doors must not intrude onto the public road reserve.</p> <p>Notes:</p> <ul style="list-style-type: none"> • If the substation is not located within the building its location, all screen walls or fire separating walls must have been approved by the grant of development consent or amended development consent prior to the issue of any construction certificate for those works. Documentary evidence of compliance, including correspondence from the energy authority is to be provided to the Principal Certifier prior to issue of the construction certificate. The Principal Certifier must be satisfied that the requirements of the energy authority have been met prior to issue of the construction certificate. • Where it is proposed to shield any booster connection or any building from any electricity pillar and/or substation under clause 5.6.3(c)(ii) of AS 2419.1 or by fire resisting construction under the BCA respectively and this construction has not been detailed upon the approved development consent plans such works should be considered inconsistent with consent under clause 19 of the Development Certification and Fire Safety Regulation. The Applicant must lodge with Council details for any such construction under section 4.55 of the Act to allow assessment under section 4.15 of the Act. • Electricity pillar and/or Substations must not be located within the minimum sight distance at driveway entrances under Australian Standard AS/NZS 2890 (Set) Parking Facilities Set whether such driveways service the site or any adjoining land.
	<p>Condition Reason: To ensure the adequate provision of energy supply, and to ensure that any proposed electricity substation or the like does not compromise the design quality of the development.</p>
<p>D. 8.</p>	<p>Engineer Certification</p> <p>Before the issue of any construction certificate, engineer certification must be submitted to the Principal Certifier confirming that the structural design does not incorporate any temporary or permanent underpinning works or ground anchors, bolts, etc. which encroach outside the boundaries of the subject property.</p> <p>This development consent does NOT give approval to any works outside the boundaries of the subject property including any underpinning works to any structures on adjoining properties and Council's property.</p> <p>Condition Reason: To ensure certification is provided that demonstrates all structural works are located within the boundaries of the site and do not include underpinning works to any structures on adjoining properties.</p>

<p>D. 9.</p>	<p>Geotechnical and Hydrogeological Design, Certification and Monitoring</p> <p>Before the issue of the construction certificate, the applicant must submit, for approval by the Principal Certifier, a detailed geotechnical report prepared by a Geotechnical Engineer with National Engineering Register (NER) credentials in accordance with Chapter E2.2.10 of Council’s DCP and Council’s document “Guidelines for Preparation of Geotechnical and Hydrogeological Reports”. The report must include a Geotechnical / Hydrogeological Monitoring Program together with civil and structural engineering details for foundation retaining walls, footings, basement tanking, and subsoil drainage systems, as applicable, prepared by a professional engineer, who is suitably qualified and experienced in geotechnical and hydrogeological engineering.</p> <p>These details must be certified by the professional engineer to:</p> <ol style="list-style-type: none"> a) Provide appropriate support and retention to ensure there will be no ground settlement or movement, during excavation or after construction, sufficient to cause an adverse impact on adjoining property or public infrastructure, b) Provide appropriate support and retention to ensure there will be no adverse impact on surrounding property or infrastructure as a result of changes in local hydrogeology (behaviour of groundwater), c) Provide details of cut-off walls and/or similar controls prior to excavation such that any temporary changes to the groundwater level, during construction, will be kept within the historical range of natural groundwater fluctuations. Where the historical range of natural groundwater fluctuations is unknown, the design must demonstrate that changes in the level of the natural water table, due to construction, will not exceed 0.2m at any time, d) Provide tanking to below ground structures to prevent the entry of seepage water such that subsoil drainage/ seepage water is NOT collected and discharged to the kerb and gutter, e) Provide a Geotechnical and Hydrogeological Monitoring Program that: <ul style="list-style-type: none"> • will detect any settlement associated with temporary and permanent works and structures, • will detect deflection or movement of temporary and permanent retaining structures (foundation walls, shoring bracing or the like), • will detect vibration in accordance with AS 2187.2 Appendix J including acceptable velocity of vibration (peak particle velocity), • will detect groundwater changes calibrated against natural groundwater variations, • details the location and type of monitoring systems to be utilised, • details the pre-set acceptable limits for peak particle velocity and ground water fluctuations, • details recommended hold points to allow for the inspection and certification of geotechnical and hydrogeological measures by the professional engineer, and • details a contingency plan. <p>Condition Reason: To ensure that geotechnical and hydrogeological impacts are appropriately managed.</p>
<p>D. 10.</p>	<p>Ground Anchors</p> <p>This development consent does NOT give approval to works or structures over, on or under adjoining properties, public roads and/or footpaths.</p> <p>Before the issue of any construction certificate, if ground anchors are proposed:</p>

	<p>a) Prior written consent must be obtained from all relevant adjoining property owner(s) for the use of any ground anchors extending beyond the boundaries of the subject property.</p> <p>b) The use of permanent ground anchors under Council land is not permitted. Temporary ground anchors under Council's land may be permitted, in accordance with Council's "Rock Anchor Policy", where alternative methods of stabilisation would not be practicable or viable, and where there would be benefits in terms of reduced community impact due to a shorter construction period, reduced disruption to pedestrian and vehicular traffic on adjacent public roads, and a safer working environment.</p> <p>c) If temporary ground anchors under Council land are proposed, a separate application, including payment of fees, must be made to Council under Section 138 of the Roads Act 1993. Application forms and Council's "Rock Anchor Policy" are available from Council's website. Approval may be granted subject to conditions of consent. A minimum of four weeks should be allowed for assessment.</p> <p>Notes:</p> <ul style="list-style-type: none"> • To ensure that this work is completed to Council's satisfaction, this consent by separate condition, may impose one or more Infrastructure Works Bonds. • Road has the same meaning as in the Roads Act 1993. • Clause 17 of the Roads (General) Regulation 2018 prohibits excavation in the vicinity of roads as follows: "Excavations adjacent to road - A person must not excavate land in the vicinity of a road if the excavation is capable of causing damage to the road (such as by way of subsidence) or to any work or structure on the road." Separate approval is required under the Roads Act 1993 for any underpinning, shoring, soil anchoring (temporary) or the like within or under any road. Council will not give approval to permanent underpinning, shoring, soil anchoring within or under any road. <p>Condition Reason: To ensure the relevant approval is gained for any temporary ground anchors.</p>
<p>D. 11.</p>	<p>Stormwater Management Plan</p> <p>Before the issue of any construction certificate, the applicant must submit, for approval by the Principal Certifier, detailed stormwater management plans prepared by a chartered professional civil engineer, which detail the following:</p> <p>a) All below ground structures are to be fully tanked such that subsoil drainage/seepage water is NOT collected and discharged to the kerb and gutter to comply with Chapter E2.2.5 of Council's DCP. Notation to this requirement must be clearly depicted on the drawings,</p> <p>b) The discharge of stormwater from the site, by direct connection, to the existing Council's kerb inlet pit located on the northern side of Patterson Street, fronting No. 1 Kiaora Road by using a minimum 225mm diameter pipe with full concrete encasement. An inspection eye must be installed on nature strip for this stormwater outlet pipe and within the frontage of the site. Only one stormwater outlet will be permitted and the pipe must be concrete encased,</p> <p>c) A minimum 600mm x 600mm boundary junction pit must be provided prior to discharging stormwater from the site to the street drainage system. The stormwater outlet pipe across the Council's property must have a minimum grade of 1% to comply with the Council's DCP and AS3500.3,</p> <p>d) Interceptor drain(s) at the site boundary to prevent stormwater flows from the site crossing the footpath,</p>

- e) The provision of stormwater treatment system including Atlam FlowGuard or equivalent to achieve the water quality targets stipulated in Chapter E2.2.3 of Council's DCP,
- f) Internal stormwater drainage including but not limited to gutters and downpipes, pipes and pits are to be designed for rainfall intensities up to and including the 1% AEP event if an unimpeded overland flow path to the street drainage system is not available. Design details and calculations must be included in the stormwater management plans,
- g) Dimensions of all drainage pits and access grates must comply with AS3500.3,
- h) Compliance with the objectives and performance requirements of the BCA,
- i) General compliance with the Council's Woollahra DCP 2015 Chapter E2 – Stormwater and Flood Risk Management.

The Stormwater Management Plan must also include the following specific requirements:

Layout plan:

A detailed drainage plan at a scale of 1:100 based on drainage calculations prepared in accordance with the Australian Government publication, Australian Rainfall and Run-off, 2019 edition or most current version thereof. It must include:

- a) All pipe layouts, dimensions, grades, lengths and material specification.
- b) Location of proposed rainwater tanks.
- c) All invert levels reduced to Australian Height Datum (AHD).
- d) Location and dimensions of all drainage pits.
- e) Point and method of connection to Council's drainage infrastructure.
- f) Overland flow paths over impervious areas.

Rainwater Reuse System details:

- a) Any potential conflict between existing and proposed trees and vegetation.
- b) Internal dimensions and volume of the proposed rainwater storage.
- c) Plans, elevations and sections showing the rainwater tanks, finished surface level and adjacent structures.
- d) Details of access and maintenance facilities.
- e) Construction and structural details of all tanks and pits and/or manufacturer's specifications for proprietary products.
- f) Details of the emergency overland flow-path (to an approved Council drainage point) in the event of a blockage to the rainwater tanks

For Stormwater Drainage works on Council's property, separate approval under Section 138 of the Roads Act 1993 must be obtained from Council for those works before the issue of any construction certificate.

All Stormwater Drainage System work within any road or public place must comply with Woollahra Municipal Council's Specification for Roadworks, Drainage and Miscellaneous Works (2012).

Notes:

- The collection, storage and use of rainwater is to be in accordance with Standards Australia HB230 "Rainwater Tank Design and Installation Handbook".

Condition Reason: To ensure that site stormwater is disposed of in a controlled and sustainable manner.

<p>D. 12.</p>	<p>Flood Protection</p> <p>Before the issue of any construction certificate, the construction certificate plans and specifications required under clause 7 of the Development Certification and Fire Safety Regulation, must include a Flood Risk Management Plan on the basis of the Flood Planning Level (FPL).</p> <p><u>Flood Warning:</u></p> <p>a) A permanent flood risk management plan shall be installed in a prominent area of the basement carpark,</p> <p><u>Above Ground Car parking</u></p> <p>a) The garage floor shall be at or above the flood planning level of 3.3m AHD,</p> <p><u>Flood Proof Material</u></p> <p>a) Flood compatible materials shall be used for all flood exposed construction,</p> <p><u>Electricals</u></p> <p>a) All flood exposed electrical wiring and equipment shall be waterproofed,</p> <p><u>Certification</u></p> <p>a) All flood protection measures shall be inspected and certified as fit for purpose after construction is complete by an engineer experienced in flood mitigation,</p> <p>Flood protection is to comply with Woollahra DCP 2015, Part E General Controls for All Development, Chapter E2 –Stormwater and Flood Risk Management.</p> <p>Notes:</p> <ul style="list-style-type: none"> The revised driveway profile, gradients and transitions must be in accordance with Australian Standard 2890.1, Part 1: Off-street car parking. The driveway profile submitted to Council must contain all relevant details: reduced levels, proposed grades and distances. Council will not allow alteration to existing reduced levels within the road or any other public place to achieve flood protection. <p>Condition Reason: To ensure the development incorporates flood inundation protection measures.</p>
<p>D. 13.</p>	<p>Tree Protection Plan and Specification</p> <p>Before the issue of any construction certificate, the Principal Certifier must ensure the measures for tree protection detailed in this consent are in place. The construction certificate plans and specifications must show the following information:</p> <p>a) Trees to be numbered and coloured in accordance with these conditions:</p> <ul style="list-style-type: none"> shaded green where required to be retained and protected shaded red where authorised to be removed shaded yellow where required to be transplanted shaded blue where required to be pruned <p>b) Tree Protection Plan and Specification prepared by an arborist with a minimum qualification of AQF 5 including the following:</p> <ul style="list-style-type: none"> Tree Location Plan (to scale) based on/overlaid with the approved plans, indicating trees to be retained, removed or transplanted, and the location of

	<p>tree protection zones (TPZ) and structural root zones (SRZ) of trees to be retained and protected.</p> <ul style="list-style-type: none"> • The plan must also include site specific tree protection recommendations such as fencing, ground and trunk protection and other protection devices. • Tree Protection Specification (written document) with tree protection requirements included from this consent and in accordance with sections 4 & 5 of AS4970, providing guidance for the implementation of tree protection methods. • To minimise construction damage, the plan must show specific areas requiring works to be done under direct supervision of the project arborist. <p>c) References to applicable tree management plan, arborists report or transplant method statement.</p> <p>This plan must be kept on site until the issue of the occupation certificate for the whole building.</p> <p>Condition Reason: To ensure the construction certificate includes the approved tree management details, and all measures are implemented.</p>
<p>D. 14.</p>	<p>Parking Facilities</p> <p>Before the issue of any construction certificate, the construction certificate plans and specifications required under clause 7 of the Development Certification and Fire Safety Regulation, must include detailed plans and specifications for all bicycle, car and commercial vehicle parking in compliance with AS/NZS 2890.1: Parking Facilities - Off-Street Car Parking.</p> <p>The plans must satisfy the following requirement(s):</p> <ol style="list-style-type: none"> a) Sight distance requirements must comply with Clause 3.2.4 and Figure 3.3 of AS2890.1:2004; b) A 2m x 2.5m sight splay be provided along both sides of the access driveway, as per Clause 3.2.4 and Figure 3.2 of AS/NZS2890.1:2004. Any structure within the splay area including landscape should be lower than 600mm to ensure visibility. <p>Access levels and grades must comply with access levels and grades required by Council under the Roads Act 1993.</p> <p>The Principal Certifier has no discretion to reduce or increase the number or area of car parking or commercial parking spaces required to be provided and maintained by this consent.</p> <p>Condition Reason: To ensure parking facilities are designed in accordance with the Australian Standard.</p>
<p>D. 15.</p>	<p>Woollahra Local Traffic Committee Approval</p> <p>Before the issue of a construction certificate, the applicant is to liaise with Council's Traffic and Transport Department for the required adjustment of parking restrictions. This matter must be referred to the Woollahra Local Traffic Committee for review and approval.</p> <p>Notes:</p> <ul style="list-style-type: none"> • This process can take up to 8 weeks. • All works associated with the signage changes shall be carried out at the full cost to the applicant.

	<p>Condition Reason: To ensure the approval of the Woollahra Local Traffic Committee is obtained.</p>
D. 16.	<p>Waste Storage – Residential Units (up to four units)</p> <p>Before the issue of any construction certificate, the construction certificate plans and specifications required by clause 7 of the Development Certification and Fire Safety Regulation, must include detailed plans and specifications must make provision for:</p> <ol style="list-style-type: none"> a) The storage of waste and recycling bins behind the building line or within non-habitable areas of the building as close as possible to the service road collection point. b) A path for wheeling bins between the waste and recycling storage area and the collection point free of steps and kerbs and having a maximum grade of 1:8. <p>Condition Reason: To ensure a waste and recycling storage area is provided.</p>
D. 17.	<p>Electric vehicle circuitry and electric vehicle charging point requirements</p> <p>Before the issue of any construction certificate, the construction certificate plans and specifications required under clause 7 of the Development Certification and Fire Safety Regulation, must include an accurate electrical plan of all off-street car parking spaces, prepared by a suitably qualified person, which includes details and specifications to illustrate how the off-street car parking spaces will be constructed with the capacity to install at a minimum, a 'Level 2' (single phase, 7Kw power) electric vehicle charger point.</p> <p>Condition Reason: To ensure the provision of electric vehicle circuitry to enable the future installation of electric vehicle charging point(s).</p>
D. 18.	<p>Light and Ventilation</p> <p>Before the issue of any construction certificate, the construction certificate plans and specifications required under clause 7 of the Development Certification and Fire Safety Regulation, must detail all lighting, mechanical ventilation or air-conditioning systems complying with Part F.4 of the BCA or clause 3.8.4 and 3.8.5 of the BCA Housing Provisions, inclusive of AS 1668.1, AS 1668.2 and AS/NZS 3666.1. If an alternate solution is proposed then the construction certificate application must include a statement as to how the performance requirements of the BCA are to be complied with and support the performance based solution by expert evidence of suitability.</p> <p>This condition does not set aside the mandatory requirements for 'Legionella Control' under the Public Health Act 2010 and Public Health Regulation 2022 in relation to regulated systems. This condition does not set aside the effect of the Protection of the Environment Operations Act 1997 in relation to offensive noise or odour.</p> <p>Notes:</p> <ul style="list-style-type: none"> • Clause 69 of the Regulation requires compliance with the BCA. Clause 19 of the Development Certification and Fire Safety Regulation prevents the issue of a construction certificate unless the Principal Certifier is satisfied that compliance has been achieved. • Part 3, Division 1 of the Development Certification and Fire Safety Regulation details what information must be submitted with any construction certificate. It is the Applicant's responsibility to demonstrate compliance through the construction certificate application process.

	<ul style="list-style-type: none"> • Applicants must also consider possible noise and odour nuisances that may arise. The provisions of the Protection of the Environment Operations Act 1997 have overriding effect if offensive noise or odour arises from the use. • Applicants must pay attention to the location of air intakes and air exhausts relative to sources of potentially contaminated air and neighbouring windows and air intakes respectively, see section 2 and 3 of AS 1668.2. <p>Condition Reason: To ensure the development is provided with adequate light and ventilation.</p>
<p>D. 19.</p>	<p>Acoustic Certification of Mechanical Plant and Equipment</p> <p>Before the issue of any construction certificate, the construction certificate plans and specifications required under clause 7 of the Development Certification and Fire Safety Regulation, must be accompanied by a certificate from a professional acoustic engineer certifying that the noise level measured at any boundary of the site at any time while the proposed mechanical plant and equipment is operating will not exceed the background noise level. Where noise sensitive receivers are located within the site, the noise level is measured from the nearest strata, stratum or community title land and must not exceed background noise level, at any time.</p> <p>The background noise level is the underlying level present in the ambient noise, excluding the subject noise source, when extraneous noise is removed. For assessment purposes the background noise level is the LA90, 15 minute level measured by a sound level meter.</p> <p>Where sound attenuation is required this must be detailed.</p> <p>Notes:</p> <ul style="list-style-type: none"> • Further information including lists of Acoustic Engineers can be obtained from: <ul style="list-style-type: none"> - Australian Acoustical Society - professional society of noise-related professional www.acoustics.asn.au - Association of Australian Acoustical Consultant - professional society of noise related professionals www.aaac.org.au <p>Condition Reason: To ensure the development does not result in any unreasonable acoustic impacts.</p>
<p>D. 20.</p>	<p>Ventilation - Enclosures used by Vehicles (Car parks, automotive service, enclosed driveways, loading docks and the like)</p> <p>Before the issue of any construction certificate, the <i>basement carpark</i> in which vehicles powered by internal combustion engines are parked, serviced or operated are required to comply with Section 4 'Ventilation of Enclosures used by Vehicles with Internal Combustion Engines' of Australian Standard 1668.2-1991. In general air distribution must achieve uniform dilution of contaminants in the garage and maintain contaminant concentrations below recommended exposure standards.</p> <p>The <i>basement carpark</i> must be naturally ventilated or provided with a combination of both supply and exhaust mechanical ventilation. The applicant is to determine the method of ventilation of the <i>basement carpark</i> and provide details to the Certifying Authority accordingly. Except as varied in accordance with Clause 4.4.1 (a), (b) or (c), the <i>basement carpark</i> shall be mechanically ventilated by a combination of general exhaust and supply flow rates in accordance with Australian Standard 1668.2-1991.</p> <p>Condition Reason: To ensure the development is adequately ventilated.</p>

D. 21.	<p>Ventilation - Internal Sanitary Rooms</p> <p>Before the issue of any construction certificate, all internal sanitary rooms and laundry facilities not provided with natural ventilation must be provided with a system of mechanical exhaust ventilation in accordance with <i>Table B1 Minimum Exhaust Ventilation Flow Rates of AS 1668.2-1991</i>. Details of any proposed mechanical ventilation system(s) must be submitted with the Construction Certificate plans and specifications to the Certifying Authority demonstrating compliance with AS 1668 Parts 1 & 2.</p> <p>Condition Reason: To ensure the development is adequately ventilated.</p>										
D. 22.	<p>Payment of S7.12 Contributions Levy</p> <p>A payment of a levy authorised by section 7.12 of the Environmental Planning and Assessment Act 1979 must be paid prior to the issue of any Construction Certificate or Subdivision Works Certificate. The Principal Certifier is to be provided with the original receipt for payment under the Woollahra Section 7.12 Development Contributions Plan 2022.</p> <p>A cost estimate report, no more than 3 months old, demonstrating the proposed cost of carrying out the development must be completed and submitted to Council for determination of the costs of work. This report must incorporate all approved modification applications. The costs and expenses of the proposed cost of development must be established in accordance with clause 208 of the Environmental Planning and Assessment Regulation 2021.</p> <p>The cost estimate report must be in the form of:</p> <ul style="list-style-type: none"> • A cost summary report, prepared by the applicant or a suitably qualified person for a development up to \$749,999; or • A quantity surveyor’s report, for development over \$750,000. <p>The applicable levy rate is to be calculated using the summary schedule below.</p> <table border="1" style="width: 100%; border-collapse: collapse;"> <thead> <tr> <th colspan="2" style="text-align: left;">Summary Schedule</th> </tr> <tr> <th style="text-align: left;">Development Cost</th> <th style="text-align: left;">Levy Rate</th> </tr> </thead> <tbody> <tr> <td>• Up to and including \$100,000</td> <td>Nil</td> </tr> <tr> <td>• More than \$100,000 and up to and including \$200,000</td> <td>0.5% of the cost</td> </tr> <tr> <td>• More than \$200,000</td> <td>1% of the cost</td> </tr> </tbody> </table> <p>How must the payments be made? Payments must be made by:</p> <ul style="list-style-type: none"> • Cash deposit with Council, • Credit card payment with Council, or • Bank cheque made payable to Woollahra Municipal Council. <p>Deferred or periodic payment of section 7.12 levy Where the Applicant makes a written request supported by reasons for payment of the section 7.12 levy other than as required by clause 2.9, the Council may accept deferred or periodic payment. The decision to accept a deferred or periodic payment is at the sole discretion of the Council, which will consider:</p> <ul style="list-style-type: none"> • the reasons given, • whether any prejudice will be caused to the community deriving benefit from the public facilities, • whether any prejudice will be caused to the efficacy and operation of the Plan, and • whether the provision of public facilities in accordance with the adopted works schedule will be adversely affected. 	Summary Schedule		Development Cost	Levy Rate	• Up to and including \$100,000	Nil	• More than \$100,000 and up to and including \$200,000	0.5% of the cost	• More than \$200,000	1% of the cost
Summary Schedule											
Development Cost	Levy Rate										
• Up to and including \$100,000	Nil										
• More than \$100,000 and up to and including \$200,000	0.5% of the cost										
• More than \$200,000	1% of the cost										

	<p>Council may, as a condition of accepting deferred or periodic payment, require the provision of a bank guarantee where:</p> <ul style="list-style-type: none"> • the guarantee is by an Australian bank for the amount of the total outstanding contribution, • the bank unconditionally and irrevocably agrees to pay the guaranteed sum to the Council on written request by Council prior to the issue of an occupation certificate, • a time limited bank guarantee or a bank guarantee with an expiry date is not acceptable, • the bank agrees to pay the guaranteed sum without recourse to the applicant or landowner or other person who provided the guarantee and without regard to any dispute, controversy, issue or other matter relating to the development consent or the carrying out of development in accordance with the development consent, and • the bank's obligations are discharged when payment to the Council is made in accordance with the guarantee or when Council notifies the bank in writing that the guarantee is no longer required. <p>Any deferred or periodic payment of the section 7.12 levy will be adjusted in accordance with clause 2.12 of the Plan. The Applicant will be required to pay any charges associated with establishing or operating the bank guarantee. Council will not cancel the bank guarantee until the outstanding contribution as indexed and any accrued charges are paid.</p> <p>Do you need HELP indexing the levy? Please contact Council's Customer Service Team on 02 9391 7000. Failure to correctly calculate the adjusted development levy will delay the issue of any certificate issued under section 6.4 of the Act and could void any such certificate (e.g. construction certificate, subdivision certificate, or occupation certificate).</p>
	<p>Condition Reason: To ensure any relevant contributions are paid.</p>

E. BEFORE BUILDING WORK COMMENCES

E.	1.	<p>Compliance with Building Code of Australia and insurance requirements under the Home Building Act 1989</p>
		<p>Before any building work commences, and under section 4.17(11) of the Act, the following conditions are prescribed in relation to a development consent for development that involves any building work:</p> <p>a) that the work must be carried out in accordance with the requirements of the Building Code of Australia,</p> <p>b) in the case of residential building work for which the Home Building Act 1989 requires there to be a contract of insurance in force in accordance with Part 6 of that Act, that such a contract of insurance is in force before any building work authorised to be carried out by the consent commences.</p> <p>This condition does not apply:</p> <p>a) to the extent to which an exemption is in force under the Home Building Regulation 2014, or</p> <p>b) to the erection of a temporary building.</p> <p>In this condition, a reference to the BCA is a reference to that code as in force on the date the application for the relevant Construction Certificate is made.</p> <p>Notes:</p> <ul style="list-style-type: none"> • This condition must be satisfied prior to commencement of any work in relation to the contract of insurance under the Home Building Act 1989. This condition also has effect during the carrying out of all building work with respect to compliance with the Building Code of Australia. • All new guttering is to comply with the provisions of AS3500.

	<p>Condition Reason: To ensure that works are carried out in accordance with the Building Code of Australia and any required contract of insurance is in force.</p>
<p>E. 2.</p>	<p>Erosion and Sediment Controls – Installation</p> <p>Before any building work commences, water pollution, erosion and sedimentation controls must be installed and maintained in accordance with:</p> <ol style="list-style-type: none"> a) The Soil and Water Management Plan if required under this consent; b) “Do it Right On Site, Soil and Water Management for the Construction Industry” and accompanying factsheets published by the Southern Sydney Regional Organisation of Councils, and c) “Managing Urban Stormwater - Soils and Construction” 2004 published by the NSW Government (The Blue Book). <p>Where there is any conflict The Blue Book takes precedence.</p> <p>Notes:</p> <ul style="list-style-type: none"> • The International Erosion Control Association – Australasia (www.austieca.com.au/) lists consultant experts who can assist in ensuring compliance with this condition. • Where Soil and Water Management Plan is required for larger projects it is recommended that this be produced by a member of the International Erosion Control Association – Australasia. • The “Do it Right On Site, Soil and Water Management for the Construction Industry” publication and the accompanying factsheets can be downloaded from www.woollahra.nsw.gov.au and The Blue Book is available at www.environment.nsw.gov.au • A failure to comply with this condition may result in penalty infringement notices, prosecution, notices and orders under the Act and/or the Protection of the Environment Operations Act 1997 without any further warning. It is a criminal offence to cause, permit or allow pollution. • Section 257 of the Protection of the Environment Operations Act 1997 provides inter alia that “the occupier of premises at or from which any pollution occurs is taken to have caused the pollution”. • Warning: Irrespective of this condition any person occupying the site may be subject to proceedings under the Protection of the Environment Operations Act 1997 where pollution is caused, permitted or allowed as the result of their occupation of the land being. <p>Condition Reason: To prevent potential water pollution and dust nuisance.</p>
<p>E. 3.</p>	<p>Building - Construction Certificate, Appointment of Principal Certifier, Appointment of Principal Contractor and Notice of Commencement (Part 6, Division 6.3 of the Act)</p> <p>Building work must not commence, until:</p> <ol style="list-style-type: none"> a) A construction certificate for the building work has been issued by the consent authority, the Council (if the Council is not the consent authority) or an accredited Certifier, and b) The person having the benefit of the development consent has: <ul style="list-style-type: none"> • appointed a Principal Certifier for the building work, and • notified the Principal Certifier that the person will carry out the building work as an Owner-builder, if that is the case, and c) The Principal Certifier has, no later than 2 days before the building work commences: <ul style="list-style-type: none"> • notified the consent authority and the Council (if the Council is not the consent authority) of his or her appointment, and • notified the person having the benefit of the development consent of any critical stage inspections and other inspections that are to be carried out in respect of the building work, and

	<p>d) The person having the benefit of the development consent, if not carrying out the work as an Owner-builder, has:</p> <ul style="list-style-type: none"> • appointed a Principal Contractor for the building work who must be the holder of a contractor licence if any residential building work is involved, and • notified the Principal Certifier of any such appointment, and • unless that person is the Principal Contractor, notified the Principal Contractor of any critical stage inspections and other inspections that are to be carried out in respect of the building work, and • given at least 2 days' notice to the Council of the person's intention to commence the erection of the building. <p>Notes:</p> <ul style="list-style-type: none"> • Building has the same meaning as in section 1.4 of the Act and includes part of a building and any structure or part of a structure. • New building has the same meaning as in section 6.1 of the Act and includes an altered portion of, or an extension to, an existing building. • The commencement of demolition works associated with an altered portion of, or an extension to, an existing building is considered to be the commencement of building work requiring compliance with section 6.6(2) of the Act (including the need for a Construction Certificate) prior to any demolition work. See: <i>Over our Dead Body Society Inc v Byron Bay Community Association Inc</i> [2001] NSWLEC 125. • Construction Certificate Application, PC Service Agreement and Notice of Commencement forms can be downloaded from Council's website www.woollahra.nsw.gov.au • It is an offence for any person to carry out the erection of a building in breach of this condition and in breach of section 6.6(2) of the Act. • Under the Home Building Act 1989 any property owner who intends undertaking construction work to a dwelling house or dual occupancy to the value of \$12,000 or over must complete an approved education course and obtain an owner-builder permit from NSW Fair Trading. <p>Condition Reason: To ensure a construction certificate has been issued, a Principal Certifier is appointed, a Principal Contractor (if applicable) is appointed, and a notice of commencement has been submitted.</p>
--	---

F. DURING BUILDING WORK

<p>F. 1.</p>	<p>Compliance with BCA and Insurance Requirements under the Home Building Act 1989</p> <p>While site work is being carried out:</p> <p>a) work must be carried out in accordance with the requirements of the Building Code of Australia (BCA),</p> <p>b) in the case of residential building work for which the Home Building Act 1989 requires there to be a contract of insurance in force in accordance with Part 6 of that Act, that such a contract of insurance is in force before any building work authorised to be carried out by the consent commences.</p> <p>This condition does not apply:</p> <p>a) to the extent to which an exemption is in force under the Development Certification and Fire Safety Regulations, or</p> <p>b) to the erection of a temporary building.</p> <p>In this clause, a reference to the BCA is a reference to that Code as in force on the date the application for the relevant construction certificate is made.</p>
---------------------	---

	<p>For the purposes of section 4.17(11) of the Act, the above condition is prescribed in relation to a development consent for development that involves any building work.</p> <p>Notes:</p> <ul style="list-style-type: none"> All new guttering is to comply with the provisions of AS 3500. <p>Condition Reason: To ensure compliance with the BCA and Home building Act 1989.</p>
<p>F. 2.</p>	<p>Requirement to Notify about New Evidence</p> <p>While site work is being carried out, any new information that comes to light, which has the potential to alter previous conclusions about site contamination, heritage significance, threatened species or other relevant matters must be immediately notified to Council and the Principal Certifier.</p> <p>Condition Reason: To ensure Council and the Principal Certifier are made aware of new information.</p>
<p>F. 3.</p>	<p>Critical Stage Inspections</p> <p>While site work is being carried out, critical stage inspections must be called for by the Principal Contractor or Owner-builder as required by the Principal Certifier, any PC service agreement, the Act, the Development Certification and Fire Safety Regulation, and the Regulation.</p> <p>Work must not proceed beyond each critical stage until the Principal Certifier is satisfied that work is proceeding in accordance with this consent, the construction certificate(s) and the Act.</p> <p>Critical stage inspections means the inspections prescribed by the Development Certification and Fire Safety Regulations, and Regulations for the purposes of section 6.5 of the Act or as required by the Principal Certifier and any PC Service Agreement.</p> <p>Notes:</p> <ul style="list-style-type: none"> The Principal Certifier may require inspections beyond mandatory critical stage inspections in order that the Principal Certifier be satisfied that work is proceeding in accordance with this consent. The Principal Certifier may, in addition to inspections, require the submission of Compliance Certificates, survey reports or evidence of suitability in accordance with Part A2G2 of the BCA in relation to any matter relevant to the development. <p>Condition Reason: To ensure that building work progresses in accordance with the approved plans, conditions of consent, and requirements of the act.</p>
<p>F. 4.</p>	<p>Hours of Work –Amenity of the Neighbourhood</p> <p>While site work is being carried out:</p> <ol style="list-style-type: none"> No work must take place on any Sunday or public holiday. No work must take place before 7am or after 5pm any weekday. No work must take place before 7am or after 1pm any Saturday. The following work must not take place before 9am or after 4pm any weekday, or before 9am or after 1pm any Saturday or at any time on a Sunday or public holiday: <ol style="list-style-type: none"> piling, piering,

- iii. rock or concrete cutting, boring or drilling,
 - iv. rock breaking,
 - v. rock sawing,
 - vi. jack hammering, or
 - vii. machine excavation.
- e) No loading or unloading of material or equipment associated with the activities listed in part d) above must take place before 9am or after 4pm any weekday, or before 9am or after 1pm any Saturday or at any time on a Sunday or public holiday.
- f) No operation of any equipment associated with the activities listed in part d) above must take place before 9am or after 4pm any weekday, or before 9am or after 1pm any Saturday or at any time on a Sunday or public holiday.
- g) No rock excavation being cutting, boring, drilling, breaking, sawing , jack hammering or bulk excavation of rock, must occur without a 15 minute interval break within every hour.

Notes:

- The use of noise and vibration generating plant and equipment and vehicular traffic, including trucks in particular, significantly degrade the amenity of neighbourhoods and more onerous restrictions apply to these activities. This more invasive work generally occurs during the foundation and bulk excavation stages of development. If you are in doubt as to whether or not a particular activity is considered to be subject to the more onerous requirement (9am to 4pm weekdays and 9am to 1pm Saturdays) please consult with Council.
- Each and every breach of this condition by any person may be subject to a separate penalty infringement notice or prosecution.
- The delivery and removal of plant, equipment and machinery associated with wide loads subject to Transport for NSW and NSW Police restrictions on their movement outside the approved hours of work will be considered on a case by case basis.
- Compliance with these hours of work does not affect the rights of any person to seek a remedy to offensive noise as defined by the Protection of the Environment Operations Act 1997, the Protection of the Environment Operations (Noise Control) Regulation 2017.
- NSW EPA Noise Guide is available at www.epa.nsw.gov.au/noise/nqlg.htm

Condition Reason: To mitigate the impact of work upon the amenity of the neighbourhood.

F. 5. Public Footpaths – Safety, Access and Maintenance

While site work is being carried out, any person acting with the benefit of this consent must:

- a) Not erect or maintain any gate or fence that swings out, or encroaches upon the road or the footway.
- b) Not use the road or footway for the storage of any article, material, matter, waste or thing.
- c) Not use the road or footway for any work.
- d) Keep the road and footway in good repair free of any trip hazard or obstruction.
- e) Any damage caused to the road, footway, vehicular crossing, nature strip or any public place must be immediately made safe and then repaired, to the satisfaction of Council.
- f) Not stand any plant and equipment upon the road or footway.

	<p>g) If it is proposed to locate any site fencing, hoardings, skip bins or other articles upon any part of the footpath, nature strip or any public place, or operate a crane, hoist or concrete pump on or over Council land, an application must be submitted to and approved by Council beforehand.</p> <p>h) Provide a clear safe pedestrian route a minimum of 1.5m wide.</p> <p>i) Protect heritage listed street name inlays located in the footpath, kerb and gutter, and any other structure, to ensure they are not removed or damaged during development.</p> <p>This condition does not apply to the extent that a permit or approval exists under the section 148B of the Road Transport Act 2013, section 138 of the Roads Act 1993 or section 68 of the Local Government Act 1993 except that at all time compliance is required with:</p> <p>a) Australian Standard AS 1742 (Set): Manual of uniform traffic control devices and all relevant parts of this set of standards.</p> <p>b) Australian Road Rules.</p> <p>Notes:</p> <ul style="list-style-type: none"> • Section 148B of the Road Transport Act 2013 allows the NSW Police to close any road or road related area to traffic during any temporary obstruction or danger to traffic or for any temporary purpose. • Section 138 of the Roads Act 1993 provides that a person must not: <ul style="list-style-type: none"> - erect a structure or carry out a work in, on or over a public road, or - dig up or disturb the surface of a public road, or - remove or interfere with a structure, work or tree on a public road, or - pump water into a public road from any land adjoining the road, or - connect a road (whether public or private) to a classified road, - otherwise than with the consent of the appropriate roads authority. • Section 68 of the Local Government Act 1993 provides that a person may carry out certain activities only with the prior approval of the Council including: <ul style="list-style-type: none"> - Part C Management of waste: <ul style="list-style-type: none"> a) For fee or reward, transport waste over or under a public place b) Place waste in a public place c) Place a waste storage container in a public place. - Part E Public roads: <ul style="list-style-type: none"> a) Swing or hoist goods across or over any part of a public road by means of a lift, hoist or tackle projecting over the footway b) Expose or allow to be exposed (whether for sale or otherwise) any article in or on or so as to overhang any part of the road or outside a shop window or doorway abutting the road, or hang an article beneath an awning over the road. <p>Condition Reason: To ensure safe access is maintained to footpaths and roads during building works.</p>
<p>F. 6.</p>	<p>Maintenance of Environmental Controls</p> <p>While site work is being carried out, the following monitoring, measures and controls must be maintained:</p> <p>a) erosion and sediment controls, b) dust controls, c) dewatering discharges, d) noise controls, e) vibration monitoring and controls, and f) ablutions.</p> <p>Condition Reason: To ensure that environmental controls are maintained during building works to protect the public and surrounding environment.</p>

<p>F. 7.</p>	<p>Compliance with Geotechnical / Hydrogeological Monitoring Program</p> <p>While site work is being carried out, excavation must be undertaken in accordance with the recommendations of the Geotechnical / Hydrogeological Monitoring Program and any oral or written direction of the supervising professional engineer.</p> <p>The Principal Contractor and any sub-contractor must strictly follow the Geotechnical / Hydrogeological Monitoring Program for the development including, but not limited to:</p> <ol style="list-style-type: none"> a) the location and type of monitoring systems to be utilised, b) recommended hold points to allow for inspection and certification of geotechnical and hydrogeological measures by the professional engineer, and c) the contingency plan. <p>Notes:</p> <ul style="list-style-type: none"> • The consent authority cannot require that the author of the geotechnical/hydrogeological report submitted with the development application to be appointed as the professional engineer supervising the work however, it is the Council’s recommendation that the author of the report be retained during the construction stage. <p>Condition Reason: To ensure the geotechnical and/or hydrogeological impacts of the development are appropriately managed.</p>
<p>F. 8.</p>	<p>Support of Adjoining Land and Buildings</p> <p>While site work is being carried out, a person must not to do anything on or in relation to the site (the supporting land) that removes the support provided by the supporting land to any other land (the supported land) or building (the supported building).</p> <p>For the purposes of this condition, supporting land includes the natural surface of the site, the subsoil of the site, any water beneath the site, and any part of the site that has been reclaimed.</p> <p>Notes:</p> <ul style="list-style-type: none"> • This condition does not authorise any trespass or encroachment upon any adjoining or supported land or building whether private or public. Where any underpinning, shoring, soil anchoring (temporary or permanent) or the like is considered necessary upon any adjoining or supported land by any person the Principal Contractor or Owner-builder must obtain: <ul style="list-style-type: none"> - the consent of the owners of such adjoining or supported land to trespass or encroach, or - an access order under the Access to Neighbouring Land Act 2000, or - an easement under section 88K of the Conveyancing Act 1919, or - an easement under section 40 of the Land and Environment Court Act 1979 as appropriate. • Section 177 of the Conveyancing Act 1919 creates a statutory duty of care in relation to support of land. Accordingly, a person has a duty of care not to do anything on or in relation to land being developed (the supporting land) that removes the support provided by the supporting land to any other adjoining land (the supported land). • Clause 17 of the Roads Regulation 2018 prohibits excavation in the vicinity of roads as follows: “Excavations adjacent to road - A person must not excavate land in the vicinity of a road if the excavation is capable of causing damage to the road (such as by way of subsidence) or to any work or structure on the road.” Separate approval is required under the Roads Act 1993 for any underpinning, shoring, soil anchoring (temporary) or the like within or under any road. Council will not give approval to permanent underpinning, shoring, soil anchoring within or under any road.

	<ul style="list-style-type: none"> The encroachment of work or the like is a civil matter of trespass or encroachment and Council does not adjudicate or regulate such trespasses or encroachments except in relation to encroachments upon any road, public place, Crown land under Council's care control or management, or any community or operational land as defined by the Local Government Act 1993.
	<p>Condition Reason: To ensure that the support of adjoining land is not removed.</p>
<p>F. 9.</p>	<p>Erosion and Sediment Controls – Maintenance</p> <p>While site work is being carried out, water pollution, erosion, and sedimentation controls must be maintained in accordance with:</p> <ol style="list-style-type: none"> the Soil and Water Management Plan required under this consent, “Do it Right On Site, Soil and Water Management for the Construction Industry” and the accompanying factsheets published by the Southern Sydney Regional Organisation of Councils, and “Managing Urban Stormwater - Soils and Construction” 2004 published by the NSW Government (The Blue Book). <p>Where there is any conflict The Blue Book takes precedence.</p> <p>Notes:</p> <ul style="list-style-type: none"> A failure to comply with this condition may result in penalty infringement notices, prosecution, notices and orders under the Act and/or the Protection of the Environment Operations Act 1997 without any further warning. It is a criminal offence to cause, permit or allow pollution. Section 257 of the Protection of the Environment Operations Act 1997 provides that “the occupier of premises at or from which any pollution occurs is taken to have caused the pollution”. Warning: Irrespective of this condition any person occupying the site may be subject to proceedings under the Protection of the Environment Operations Act 1997 where pollution is caused, permitted or allowed as the result of the occupation of the land being developed whether or not they actually cause the pollution. <p>Condition Reason: To prevent potential water pollution and dust nuisance.</p>
<p>F. 10.</p>	<p>Disposal of Site Water During Construction</p> <p>While site work is being carried out:</p> <ol style="list-style-type: none"> Prior to pumping any water into the road or public stormwater system, approval must be obtained from Council under section 138(1)(d) of the Roads Act 1993. Water pollution, as defined by the Protection of the Environment Operations Act 1997, must not occur as the result of the discharge to the road, public stormwater system or other place of any site water. That stormwater from any roof or other impervious areas is linked, via temporary downpipes and stormwater pipes, to a Council approved stormwater disposal system immediately upon completion of the roof installation or work creating other impervious areas. <p>Condition Reason: To ensure that adjoining and neighbouring land is not adversely affected by unreasonable overland flows of stormwater and that site water does not cause erosion and water pollution.</p>

<p>F. 11.</p>	<p>Check Surveys - boundary location, building location, building height, stormwater drainage system and flood protection measures relative to Australian Height Datum</p>
	<p>While site work is being carried out, a registered surveyor must carry out check surveys and provide survey certificates confirming the location of the building(s), ancillary works, flood protection works and the stormwater drainage system relative to the boundaries of the site and that the height of buildings, ancillary works, flood protection works and the stormwater drainage system relative to Australian Height Datum complies with this consent at the following critical stages.</p> <p>Work must not proceed beyond each of the following critical stages until compliance has been demonstrated to the Principal Certifier's satisfaction:</p> <ol style="list-style-type: none"> a) Upon the completion of foundation walls prior to the laying of any floor or the pouring of any floor slab and generally at damp proof course level. b) Upon the completion of formwork for floor slabs prior to the laying of any floor or the pouring of any concrete and generally at each storey. c) Upon the completion of formwork or framework for the roof(s) prior to the laying of any roofing or the pouring of any concrete roof. d) Upon the completion of formwork and steel fixing prior to pouring of any concrete for any ancillary structure, flood protection work, swimming pool or spa pool or the like. e) Upon the completion of formwork and steel fixing prior to pouring of any concrete for driveways showing transitions and crest thresholds confirming that driveway levels match Council approved driveway crossing levels and minimum flood levels. f) Stormwater drainage Systems are in place prior to back filling over pipes confirming location, height and capacity of works. g) Flood protection measures are in place confirming location, height and capacity.
	<p>Condition Reason: To ensure that development occurs in the location and at the height approved under this consent, which is critical to ensure that buildings are constructed to minimum heights for flood protection and maximum heights to protect views and the amenity of neighbours.</p>
<p>F. 12.</p>	<p>Placement and Use of Skip Bins</p>
	<p>While site work is being carried out, all waste storage containers, including but not limited to skip bins, must be stored within the site unless:</p> <ol style="list-style-type: none"> a) Activity Approval has been issued by Council under section 68 of the Local Government Act 1993 to place the waste storage container in a public place; and b) where located on the road it is located only in a positions where a vehicle may lawfully park in accordance with the Australian Road Rules. <p>Notes:</p> <ul style="list-style-type: none"> • Waste storage containers must not be located on the footpath without a site specific activity approval. Where such site specific activity approval is granted a 1.5m wide clear path of travel is maintained free of any trip hazards.
	<p>Condition Reason: To ensure waste storage containers are appropriately located.</p>

<p>F. 13.</p>	<p>Prohibition of Burning</p> <p>While site work is being carried out, there must be no burning of any waste or other materials. The burning of copper chrome arsenate (CCA) or pentachlorophenol (PCP) treated timber is prohibited in all parts of NSW. All burning is prohibited in the Woollahra local government area.</p> <p>Notes:</p> <ul style="list-style-type: none"> • Under the Protection of the Environment Operations (Clean Air) Regulation 2021 all burning (including burning of vegetation and domestic waste) is prohibited except with approval. No approval is granted under this consent for any burning. <p>Condition Reason: To ensure no burning of waste occurs.</p>
<p>F. 14.</p>	<p>Dust Mitigation</p> <p>While site work is being carried out, dust mitigation must be implemented in accordance with “Dust Control - Do it right on site” and the accompanying facts sheets published by the Southern Sydney Regional Organisation of Councils.</p> <p>This generally requires:</p> <ol style="list-style-type: none"> Dust screens to all hoardings and site fences. All stockpiles or loose materials to be covered when not being used. All equipment, where capable, being fitted with dust catchers. All loose materials being placed bags before placing into waste or skip bins. All waste and skip bins being kept covered when not being filled or emptied. The surface of excavation work being kept wet to minimise dust. Landscaping incorporating trees, dense shrubs and grass being implemented as soon as practically possible to minimise dust. <p>Notes:</p> <ul style="list-style-type: none"> • “Dust Control - Do it right on site” and the accompanying factsheets can be downloaded from Council’s website www.woollahra.nsw.gov.au • Special precautions must be taken when removing asbestos or lead materials from development sites. Additional information can be obtained from www.safework.nsw.gov.au and www.epa.nsw.gov.au. Other specific conditions and advice may apply. • Demolition and construction activities may affect local air quality and contribute to urban air pollution. The causes are dust, smoke and fumes coming from equipment or activities, and airborne chemicals when spraying for pest management. Precautions must be taken to prevent air pollution. <p>Condition Reason: To mitigate the impact of dust upon the amenity of the neighbourhood and prevent water pollution.</p>
<p>F. 15.</p>	<p>Site Waste Minimisation and Management – Demolition</p> <p>While site work is being carried out, in order to maximise resource recovery and minimise residual waste from demolition activities:</p> <ol style="list-style-type: none"> the provisions of the Site Waste Minimisation and Management Plan (SWMMP) are to be implemented at all times during the course of the work, an area is to be allocated for the storage of materials for use, recycling and disposal (giving consideration to slope, drainage, location of waterways, stormwater outlets, vegetation and access and handling requirements), separate collection bins and/or areas for the storage of residual waste are to be provided,

	<p>d) the purpose and content of the bins and/or storage areas are to be clearly 'signposted',</p> <p>e) measures to prevent damage by the elements, odour, health risks and windborne litter are to be implemented, and</p> <p>f) site disturbance must be minimised, and unnecessary excavation limited.</p> <p>When implementing the SWMMP the Applicant must ensure:</p> <p>a) footpaths, public reserves and street gutters are not used as places to store demolition waste or materials of any kind without Council approval,</p> <p>b) any material moved offsite is transported in accordance with the requirements of the Protection of the Environment Operations Act 1997,</p> <p>c) waste is only transported to a place that can lawfully be used as a waste facility,</p> <p>d) generation, storage, treatment and disposal of hazardous waste and special waste (including asbestos) is conducted in accordance with relevant waste legislation administered by the NSW Environment Protection Authority, and relevant occupational health and safety legislation administered by SafeWork NSW, and</p> <p>e) evidence such as weighbridge dockets and invoices for waste disposal or recycling services are retained.</p> <p>Notes:</p> <ul style="list-style-type: none"> Materials that have an existing reuse or recycling market must not be disposed of in a land fill. Reuse and recycling opportunities are decreased when asbestos is not carefully removed and segregated from other waste streams. <p>Condition Reason: To maximise resource recovery and minimise residual waste from demolition activities.</p>
<p>F. 16.</p>	<p>Site Waste Minimisation and Management – Construction</p> <p>While site work is being carried out, in order to maximise resource recovery and minimise residual waste from construction activities:</p> <p>a) the provisions of the Site Waste Minimisation and Management Plan (SWMMP) are to be implemented at all times during the course of the work,</p> <p>b) deliveries of materials must be arranged so that materials are delivered 'as needed' to prevent the degradation of materials through weathering and moisture damage,</p> <p>c) consideration must be given to returning excess materials to the supplier or manufacturer,</p> <p>d) an area must be allocated for the storage of materials for use, recycling and disposal (considering slope, drainage, location of waterways, stormwater outlets and vegetation),</p> <p>e) the purpose and content of the storage areas must be clearly 'signposted',</p> <p>f) contractors must be arranged for the transport, processing and disposal of waste and recycling and all contractors must be aware of the legal requirements for disposing of waste,</p> <p>g) separate collection bins or areas for the storage of residual waste must be promoted,</p> <p>h) measures to prevent damage by the elements, odour and health risks, and windborne litter must be implemented,</p> <p>i) site disturbance must be minimised and unnecessary excavation limited,</p> <p>j) all waste must be transported to a place that can lawfully be used as a waste facility, and</p> <p>k) records demonstrating lawful disposal of waste must be retained and kept readily accessible for inspection by regulatory authorities such as Council, the NSW EPA or SafeWork NSW.</p>

	<p>Condition Reason: To maximise resource recovery and minimise residual waste from construction activities.</p>
F. 17.	<p>Asbestos Removal</p> <p>While site work is being carried out, all asbestos removal work must be carried out safely according to NSW work health and safety legislation.</p> <p>Where hazardous material, including bonded or friable asbestos has been identified in accordance with the conditions in Section B above, and such material must be demolished, disturbed and subsequently removed, all such works must comply with the following criteria:</p> <ol style="list-style-type: none"> a) Be undertaken by contractors who hold a current SafeWork NSW “demolition licence” and a current SafeWork NSW “Class A licence” for friable asbestos removal. b) Be carried out in accordance with the relevant SafeWork NSW codes of practice. c) No asbestos products may be reused on the site. d) No asbestos laden skip or bins must be left in any public place. <p>Notes:</p> <ul style="list-style-type: none"> • Before starting work, a work site-specific permit approving each asbestos project must be obtained from SafeWork NSW. A permit will not be granted without a current SafeWork licence. • All removal, repair or disturbance of or to asbestos material must comply with: <ul style="list-style-type: none"> - Work Health and Safety Act 2011, - Work Health and Safety Regulation 2017, - SafeWork NSW “Code of Practice: How to Safely Remove Asbestos” (2016), and - SafeWork NSW “Code of Practice: How to Manage and Control Asbestos in the Workplace” (2016). • For more information go to the SafeWork NSW website on asbestos www.safework.nsw.gov.au/health-and-safety/safety-topics-a-z/asbestos, and www.safework.nsw.gov.au/law-and-policy/legislation-and-codes/codes-of-practice or call 131 050 <p>Condition Reason: To ensure the safe removal of asbestos and protect the health and safety of persons working on the site and the public.</p>
F. 18.	<p>Classification of Hazardous Waste</p> <p>While site work is being carried out, and prior to the exportation of hazardous waste (including hazardous fill or soil) from the site, the waste materials must be classified in accordance with the provision of the Protection of the Environment Operations Act 1997 and the NSW EPA Waste Classification Guidelines, Part1: Classifying Waste, 2014.</p> <p>Condition Reason: To ensure that where hazardous waste will be removed from a site an asbestos licensed contractor can definitively determine where the waste may be legally taken for disposal.</p>
F. 19.	<p>Disposal of Asbestos and Hazardous Waste</p> <p>While site work is being carried out, asbestos and hazardous waste, once classified in accordance with the hazardous waste classification condition must only be transported to waste facilities licensed to accept asbestos and appropriate classifications of hazardous waste.</p>

	<p>Condition Reason: To ensure that asbestos and other hazardous waste is disposed of lawfully under the Protection of the Environment Operations Act 1997 and relevant NSW EPA requirements.</p>
F. 20.	<p>Asbestos Removal Signage</p> <p>While site work is being carried out and when asbestos is being removed, standard commercially manufactured signs containing the words "DANGER ASBESTOS REMOVAL IN PROGRESS" measuring not less than 400mm x 300mm are to be erected in prominent visible positions on the site.</p> <p>Condition Reason: To ensure awareness of any hazard to the health and safety of persons working on the site and public.</p>
F. 21.	<p>Notification of Asbestos Removal</p> <p>While site work is being carried out, in addition to the requirements for licensed asbestos removalists to give written notice to SafeWork NSW, all adjoining properties and those opposite the development site must be notified in writing of the dates and times when asbestos removal is to be conducted.</p> <p>The notification is to identify the licensed asbestos removal contractor and include a contact person for the site together with telephone and facsimile numbers and email addresses.</p> <p>Condition Reason: To ensure that local residents are informed and have adequate contact details for incidents of asbestos removal.</p>
F. 22.	<p>Vibration Monitoring</p> <p>While site work is being carried out, vibration monitoring equipment must be installed and maintained, under the supervision of a professional engineer with expertise and experience in geotechnical engineering, between any potential source of vibration and any building identified by the professional engineer as being potentially at risk of movement or damage from settlement and/or vibration during the excavation and during the removal of any excavated material from the land being developed.</p> <p>If vibration monitoring equipment detects any vibration at the level of the footings of any adjacent building exceeding the peak particle velocity adopted by the professional engineer as the maximum acceptable peak particle velocity an audible alarm must activate such that the Principal Contractor and any sub-contractor are easily alerted to the event.</p> <p>Where any such alarm triggers all excavation works must cease immediately. Prior to the vibration monitoring equipment being reset by the professional engineer and any further work recommencing the event must be recorded and the cause of the event identified and documented by the professional engineer.</p> <p>Where the event requires, in the opinion of the professional engineer, any change in work practices to ensure that vibration at the level of the footings of any adjacent building does not exceed the peak particle velocity adopted by the professional engineer as the maximum acceptable peak particle velocity these changes in work practices must be documented and a written direction given by the professional engineer to the Principal Contractor and any sub-contractor clearly setting out required work practice.</p>

	<p>The Principal Contractor and any sub-contractor must comply with all work directions, verbal or written, given by the professional engineer.</p> <p>A copy of any written direction required by this condition must be provided to the Principal Certifier within 24 hours of any event.</p> <p>Where there is any movement in foundations such that damaged is occasioned to any adjoining building or such that there is any removal of support to supported land the professional engineer, Principal Contractor and any sub-contractor responsible for such work must immediately cease all work, inform the owner of that supported land and take immediate action under the direction of the professional engineer to prevent any further damage and restore support to the supported land.</p> <p>Notes:</p> <ul style="list-style-type: none"> • Professional engineer has the same mean as in Schedule 1 of the BCA. • Building has the same meaning as in section 1.4 of the Act i.e. “building includes part of a building and any structure or part of a structure...” • Supported land has the same meaning as in the Conveyancing Act 1919. <p>Condition Reason: To monitor and manage vibration impacts from development.</p>
<p>F. 23.</p>	<p>Site Cranes</p> <p>While site work is being carried out, site crane(s) and hoist(s) may be erected within the boundary of the land being developed subject to compliance with Australian Standards AS 1418, AS 2549 and AS 2550 and all relevant parts to these standards.</p> <p>Cranes must not swing or hoist over any public place unless the relevant approvals have been obtained under the Local Government Act 1993, Crown Lands Act 1989 or Roads Act 1993.</p> <p>The crane must not be illuminated outside approved working hours other than in relation to safety beacons required by the Civil Aviation Safety Authority under the Civil Aviation Act 1988 (Cth).</p> <p>No illuminated sign(s) must be erected upon or displayed upon any site crane.</p> <p>Notes:</p> <ul style="list-style-type: none"> • Where it is proposed to swing a crane over a public place a separate application to Council must be made under section 68 of the Local Government Act 1993 and obtain activity approval from Council prior to swinging or hoisting over the public place. • Where it is proposed to swing a crane over private land the consent of the owner of that private land is required. Alternatively, an access order under the Access to Neighbouring Land Act 2000 or easement under section 88K of the Conveyancing Act 1919 or section 40 of the Land and Environment Court Act 1979 as appropriate must be obtained. The encroachment of cranes or the like is a civil matter of trespass and encroachment. Council does not adjudicate or regulate such trespasses or encroachments. <p>Condition Reason: To ensure site cranes are used safely with the relevant approvals.</p>

<p>F. 24.</p>	<p>Compliance with Council’s Specification for Roadworks, Drainage and Miscellaneous Works, Road Works and, Work within the Road and Footway</p> <p>While site work is being carried out, all work carried out on assets which are under Council ownership or will revert to the ownership, care, control or management of Council in connection with the development to which this consent relates must comply with Council’s Specification for Roadworks, Drainage and Miscellaneous Works (2012).</p> <p>The person with the benefit of this consent must meet all costs associated with such works.</p> <p>This condition does not set aside the need to obtain relevant approvals under the Roads Act 1993 or Local Government Act 1993 for works within roads and other public places.</p> <p>Notes:</p> <ul style="list-style-type: none"> • A copy of Council’s Specification for Roadworks, Drainage and Miscellaneous Works can be downloaded from Council’s website www.woollahra.nsw.gov.au <p>Condition Reason: To ensure that any road, drainage, or miscellaneous works comply with Council’s specifications.</p>
<p>F. 25.</p>	<p>Shoring and Adequacy of Adjoining Property</p> <p>While site work is being carried out, the person having the benefit of the development consent must, at the person’s own expense:</p> <ol style="list-style-type: none"> protect and support the adjoining premises from possible damage from the excavation, and where necessary, underpin the adjoining premises to prevent any such damage. <p>For the purposes of section 4.17(11) of the Act, the following condition is prescribed in relation to a development consent for development that involves an excavation that extends below the level of the base of the footings of a building on adjoining land.</p> <p>Notes:</p> <ul style="list-style-type: none"> • This condition does not apply if the person having the benefit of the development consent owns the adjoining land or the owner of the adjoining land has given consent in writing to that condition not applying. <p>Condition Reason: To protect and support the adjoining premises from possible damage from the excavation.</p>
<p>F. 26.</p>	<p>Tree Preservation</p> <p>While site work is being carried out, all persons must comply with Chapter E.3 – <i>Tree Management</i> of Council’s Development Control Plan (DCP) 2015, other than where varied by this consent. The DCP applies to any tree with a height greater than 5 metres or a diameter spread of branches greater than 3 metres.</p> <p>General Protection Requirements:</p> <ol style="list-style-type: none"> The tree protection measures must be maintained during all development work unless otherwise specified within these conditions of consent.

- b) Excavation must cease where tree roots with a diameter exceeding 50mm are exposed. The principal contractor must procure an inspection of the exposed tree roots by an arborist with a minimum AQF Level 5 qualification. Excavation must only recommence with the implementation of the recommendations of the arborist.
- c) Where there is damage to any part of a tree the principal contractor must procure an inspection of the tree by a qualified arborist immediately. The principal contractor must immediately implement treatment as directed by the arborist. The arborist is to supply a detailed report to the appointed certifier.

Trees must be pruned in accordance with Australian Standard AS 4373 "Pruning of Amenity Trees" and WorkCover NSW Code of Practice Amenity Tree Industry.

Condition Reason: To protect trees during the carrying out of sitework.

F. 27. Arborists Documentation and Compliance Checklist

While site work is being carried out, the project arborist must provide written certification that all tree protection measures and construction techniques relevant to this consent have been implemented. Documentation for each site visit must include:

- a) a record of the condition of trees to be retained prior to and throughout development,
- b) recommended actions to improve site conditions and rectification of non-compliance, and
- c) recommendations for future works which may impact the trees.

All compliance certification documents must be kept on site by the site Supervisor.

As a minimum the following intervals of site inspections must be made:

Stage of arboricultural inspection and supervision	Compliance documentation and photos must include
While site work is carried out	<ul style="list-style-type: none"> • The project arborist must supervise all demolition and excavation works within the Tree Protection Zones or specified distances of nominated trees listed in this consent. • The project arborist must supervise the demolition of the existing ground surface materials within the TPZ of tree listed for retention. The condition of exposed roots must be managed and documented. • The project arborist must supervise the installation of the new driveway within 2 metres of Tree No 10, documenting the condition of roots and soil. • The project arborist must ensure pier holes within the Tree Protection Zones or specified distances of nominated trees listed in this consent are positioned to avoid the severance of and damage to the rootball of trees 1, 4, and 10. • The project arborist must inspect the installed irrigation system to plants in garden beds. The arborist must certify there is an appropriate distribution of water to planted and existing trees. • Project Arborist to approve relocation of tree protection for landscaping. All landscaping works within the TPZ of trees to be retained are to be undertaken in consultation with the project Arborist to minimise the impact to trees. • Regular inspections as indicated in the Tree Management Plan.

Inspections and compliance documentation must be made by an arborist with AQF Level 5 qualifications.

	<p>Additional site visits must be made when required by site arborist and/or site foreman for ongoing monitoring/supervisory work.</p> <p>Condition Reason: To ensure that all tree protection measures and construction techniques relevant to this consent have been implemented.</p>																
F. 28.	<p>Replacement/Supplementary trees which must be planted</p> <p>While site work is being carried out, any replacement or supplementary tree must be grown in accordance with Tree stock for landscape use (AS 2303). Replacement tree/s must be planted in deep soil landscaped area and maintained in a healthy and vigorous condition. If the replacement tree is found to be faulty, damaged, dying or dead before it attains a size whereby it becomes a prescribed tree in accordance with Chapter E.3 of Council’s Development Control Plan, it must be replaced with another of the same species, which complies with the approved Landscape Plans.</p> <p>The project arborist must document compliance with the above condition.</p> <p>Condition Reason: To ensure the provision of appropriate replacement planting.</p>																
F. 29.	<p>Paving in the vicinity of trees</p> <p>While site work is being carried out, paving works within the specified radius from the trunks of the following trees must be constructed in such a way as to ensure that the existing moisture infiltration and gaseous exchange to the tree root system are maintained. When preparing an area for paving within the specified radius the soil surface must not be skimmed/excavated. The new surface must be established above the former ground level.</p> <table border="1"> <thead> <tr> <th>Council Ref No</th> <th>Species</th> <th>Location</th> <th>Radius from centre of trunk (metres)</th> </tr> </thead> <tbody> <tr> <td>1</td> <td><i>Archontophoenix cunninghamiana</i></td> <td>Front Yard – western boundary</td> <td>1m</td> </tr> <tr> <td>4</td> <td><i>Archontophoenix cunninghamiana</i></td> <td>Front Yard – western boundary</td> <td>1m</td> </tr> <tr> <td>10</td> <td><i>Washingtonia robusta</i></td> <td>Rear Yard – northern boundary</td> <td>1m</td> </tr> </tbody> </table> <p>Paving works are to be designed in consultation with a qualified Arborist (minimum qualification of Australian Qualification Framework Level 5 or recognised equivalent) and are to utilise such measures as semiporous material.</p> <p>The project arborist must document compliance with the above condition.</p> <p>Condition Reason: To ensure that paving works would not adversely impact upon the health of existing trees.</p>	Council Ref No	Species	Location	Radius from centre of trunk (metres)	1	<i>Archontophoenix cunninghamiana</i>	Front Yard – western boundary	1m	4	<i>Archontophoenix cunninghamiana</i>	Front Yard – western boundary	1m	10	<i>Washingtonia robusta</i>	Rear Yard – northern boundary	1m
Council Ref No	Species	Location	Radius from centre of trunk (metres)														
1	<i>Archontophoenix cunninghamiana</i>	Front Yard – western boundary	1m														
4	<i>Archontophoenix cunninghamiana</i>	Front Yard – western boundary	1m														
10	<i>Washingtonia robusta</i>	Rear Yard – northern boundary	1m														
F. 30.	<p>Hand excavation within tree root zones</p> <p>While site work is being carried out, demolition of underground structures such as existing footings and approved excavation undertaken within the specified radius from the trunks of the following trees must be carried out by hand.</p>																

Council Ref No	Species	Location	Radius from centre of trunk (metres)
1	<i>Archontophoenix cunninghamiana</i>	Front Yard – western boundary	1m
4	<i>Archontophoenix cunninghamiana</i>	Front Yard – western boundary	1m
10	<i>Washingtonia robusta</i>	Rear Yard – northern boundary	1m

Small hand tools such as mattocks or using compressed air or water jetting only must be used. Roots from the above trees must not be severed or damaged unless approved in writing and documented by the project arborist.

Mechanical excavation is permitted beyond this radius when root pruning by hand along the hand excavated perimeter line is completed. Exposed roots to be retained must be covered with mulch or a geotextile fabric and kept in a moist condition and prevented from drying out.

All root pruning must be undertaken in accordance with the Australian Standard 4373 “Pruning of Amenity Trees” and carried out by a qualified Arborist (minimum qualification of Australian Qualification Framework Level 5 or recognised equivalent).

The project arborist must document compliance with the above condition.

Condition Reason: To ensure demolition and excavation works would not adversely impact upon the health of existing trees.

F. 31. Installation of stormwater pipes and pits in the vicinity of trees

While site work is being carried out, excavation for the installation of stormwater pipes and pits within the specified radius from the trunks of the following trees must be carried out by hand.

Council Ref No	Species	Location	Radius from centre of trunk (metres)
1	<i>Archontophoenix cunninghamiana</i>	Front Yard – western boundary	1m
4	<i>Archontophoenix cunninghamiana</i>	Front Yard – western boundary	1m
10	<i>Washingtonia robusta</i>	Rear Yard – northern boundary	1m

Any roots uncovered for the installation of stormwater pipes and pits must not be severed and remain in situ bridging across the excavated trench. Pipes must be guided under any roots bridging across excavated trenches. Stormwater pits must be positioned so that no roots are severed.

The project arborist must document compliance with the above condition.

Condition Reason: To ensure the installation of the stormwater works would not adversely impact upon the health of existing trees.

<p>F. 32.</p>	<p>Salvage Building Materials</p> <p>a) Architectural elements to be demolished such as bricks, timber flooring, skirting, tiles, doors and windows must be salvaged and where possible reused on the project.</p> <p>b) Salvaged building materials surplus to the project must either be stored on site for future reuse, or transferred to an established second building material dealer for recycling.</p> <p>Condition Reason: To maximise reuse of historic fabric</p>
<p>F. 33.</p>	<p>Compliance with Construction Management Plan</p> <p>While site work is being carried out, all development activities and traffic movements must be carried out in accordance with the approved Construction Management Plan (CMP). All controls in the CMP must be maintained at all times. A copy of the CMP must be kept on-site at all times and made available to the Principal Certifier on request.</p> <p>Notes:</p> <ul style="list-style-type: none"> • Irrespective of the provisions of the Construction Management Plan the provisions of traffic and parking legislation prevails. <p>Condition Reason: To ensure compliance with the Construction Management Plan.</p>
<p>F. 34.</p>	<p>Compliance with Conceptual Acid Sulfate Soils Management Plan</p> <p>While site work is being carried out, the Conceptual Acid Sulfate Soil Management Plan, 15938.1-ER-1-1 prepared by Alliance Geotechnical Pty Ltd, dated 09/05/2024, and the NSW Government Acid Sulfate Soils Management Advisory Committee manual, and any relevant guidelines must be complied with.</p> <p>Notes:</p> <ul style="list-style-type: none"> • The Acid Sulfate Soils Management plan submitted with the Development Application sets out all the above requirements in detail. • A failure to implement and maintain the Acid Sulfate Soils Management plan can result in the following environmental harm: <ul style="list-style-type: none"> - damage to the soil structure so plant roots and soil organisms can't easily move about, - plant roots being burnt by acid, reducing plant health and productivity, - acid intolerant soil fauna and flora are killed, so the soil biodiversity and health are reduced, - plants and soil life can be poisoned by the available toxic metals, - loss of aquatic plants that cannot survive acidic conditions, - loss of fish, crustaceans, birds and other animals, and - damage to metal and concrete structures (such as bridge pylons and pipes). <p>Condition Reason: To prevent environmental harm from Acid Sulfate Soils.</p>

G. BEFORE ISSUE OF AN OCCUPATION CERTIFICATE

<p>G. 1.</p>	<p>Occupation Certificate (section 6.9 of the Act)</p> <p>A person must not commence occupation or use of the whole or any part of a new building (within the meaning of section 6.10 of the Act) unless an occupation certificate has been issued in relation to the building or part.</p> <p>Notes:</p> <ul style="list-style-type: none"> • New building includes an altered portion of, or an extension to, an existing building. <p>Condition Reason: To ensure the building is suitable to occupy.</p>
<p>G. 2.</p>	<p>Fulfilment of BASIX Commitments – Clause 44 of the Development Certification and Fire Safety Regulation</p> <p>Before the issue of any occupation certificate, all BASIX commitments must be effected in accordance with the BASIX certificate No. 1377864M.</p> <p>Notes:</p> <ul style="list-style-type: none"> • Clause 44 of the Development Certification and Fire Safety Regulation applies to an occupation certificate if a relevant BASIX certificate requires a certifier to monitor fulfilment of a commitment listed in the certificate in relation to a building. The certifier must not issue an occupation certificate for the building unless the commitment has been fulfilled. <p>Condition Reason: To ensure that sustainable building commitments, to reduce water and energy consumption, are fulfilled prior to the occupation.</p>
<p>G. 3.</p>	<p>Removal of Ancillary Works and Structures</p> <p>Before the issue of any occupation certificate for the whole of the building, The following articles must be removed from the land and any adjoining public place:</p> <ol style="list-style-type: none"> a) the site sign, b) ablutions, c) hoarding, d) scaffolding, and e) waste materials, matter, article or thing. <p>Condition Reason: To ensure that all ancillary matter is removed prior to occupation.</p>
<p>G. 4.</p>	<p>Commissioning and Certification of Systems and Works</p> <p>Before the issue of any occupation certificate, works-as-executed (WAE) plans prepared by a registered surveyor, compliance certificates, and evidence of suitability in accordance with Part A5G1 of the BCA confirming that the works, as executed and as detailed, comply with the requirement of this consent, the Act, the Regulations, any relevant construction certificate, the BCA and relevant Australian Standards must be submitted to the satisfaction of the Principal Certifier.</p> <p>Works-as-executed plans, compliance certificates, and evidence of suitability in accordance with Part A5G1 of the BCA must include, but may not be limited to:</p> <ol style="list-style-type: none"> a) Certification from the supervising professional engineer that the requirement of the Geotechnical/Hydrogeological conditions and report recommendations were implemented and satisfied during development work. b) All flood protection measures.

	<p>c) All garage/car park/basement car park, driveways and access ramps comply with Australian Standard AS 2890.1: Off-Street car parking.</p> <p>d) All stormwater drainage and storage systems.</p> <p>e) All mechanical ventilation systems.</p> <p>f) All hydraulic systems.</p> <p>g) All structural work.</p> <p>h) All acoustic attenuation work.</p> <p>i) All waterproofing.</p> <p>j) Such further matters as the Principal Certifier may require.</p> <p>Notes:</p> <ul style="list-style-type: none"> The PC may require any number of WAE plans, certificates, or other evidence of suitability as necessary to confirm compliance with the Act, Regulation, development standards, BCA, and relevant Australia Standards. As a minimum WAE plans and certification is required for stormwater drainage and detention, mechanical ventilation work, hydraulic services (including but not limited to fire services). The PC must submit to Council, with any occupation certificate, copies of WAE plans, compliance certificates and evidence of suitability in accordance with Part A5G1 of the BCA upon which the PC has relied in issuing any occupation certificate. <p>Condition Reason: To ensure that systems and works as completed meet development standards as defined by the Act, comply with the BCA, and this consent, and to ensure a public record of works as executed is maintained.</p>
<p>G. 5.</p>	<p>Commissioning and Certification of Public Infrastructure Works</p> <p>Before the issue of any occupation certificate, certification from a professional engineer that all public infrastructure works have been executed in compliance with this consent and with Council's Specification for Roadworks, Drainage and Miscellaneous Works (2012) must be submitted to the satisfaction of Council, and the Principal Certifier must be provided with correspondence from Council to this effect.</p> <p>The certification must be supported by closed circuit television / video inspection provided on DVD of all stormwater drainage together with works-as-executed engineering plans and a survey report detailing all finished reduced levels.</p> <p>Condition Reason: To ensure that any road, drainage, or miscellaneous works have been completed in accordance with Council's specifications to the satisfaction of Council.</p>
<p>G. 6.</p>	<p>Works within Public Land (including Council, State or Federal owned land or property)</p> <p>Before the issue of any occupation certificate, the following works within public land, whether new/existing/renewed must be completed to the satisfaction of Council, in compliance with Council's Specification for Roadworks, Drainage and Miscellaneous Works (2012) unless expressly provided otherwise by these conditions at the person with the benefit of this consents expense:</p> <ol style="list-style-type: none"> stormwater pipes, pits, structures and connections to public stormwater systems within the road, driveways and vehicular crossings, renew/new retaining structures, overhang structures, encroachments or occupation or alienation of public land or property, removal of redundant driveways and any other structure, new footpaths, pathways, walkways, or dunny lanes,

- h) relocation of existing power/light pole, if applicable,
- i) relocation/provision of street signs, if applicable,
- j) new or replacement street trees, if applicable,
- k) verge landscape items, where a grass verge exists, the balance of the area between the footpath and the kerb or site boundary over the full frontage of the proposed development must be turfed. The grass verge must be constructed to contain a uniform minimum 75mm of friable growing medium and have a total cover of turf predominant within the street,
- l) new or reinstated kerb and guttering within the road, and
- m) new or reinstated road surface pavement within the road.

Notes:

- When determining whether the works within public land are satisfactory, Council will consider the ownership, construction quality, maintenance, operations, and public utility of such item/s.
- Security held by Council under section 4.17(6) of the Act will not be released until compliance has been achieved with this condition. An application for the refund of security must be submitted with the occupation certificate to Council. This form can be downloaded from Council's website www.woollahra.nsw.gov.au or obtained from Council's customer service centre.

Condition Reason: To ensure road, drainage and miscellaneous works are completed to the satisfaction of Council prior to occupation.

G. 7. Dilapidation Report for Public Infrastructure Works

Before the issue of an occupation certificate for the whole of the building, a follow up dilapidation report, prepared by a chartered professional engineer, on Council's infrastructure within and near the development site upon completion of the work must be submitted to Council.

The dilapidation report must include:

- a) photographs showing any existing damage to the road pavement fronting the site,
- b) photographs showing any existing damage to the kerb and gutter fronting the site,
- c) photographs showing any existing damage to the footway including footpath pavement fronting the site,
- d) photographs showing any existing damage to retaining walls within the footway or road,
- e) photographs showing any existing damage to street signs, heritage name plates, and historical items,
- f) the full name and signature of the professional engineer.

The reports are to be supplied in both paper copy and electronic format in PDF. Photographs are to be in colour, digital and date stamped.

Before the issue of an occupation certificate for the whole building, written correspondence must be obtained from Council attesting to this condition being appropriately satisfied, and be provided to the Principal Certifier.

Notes:

- If the dilapidation report required by this condition is not provided and damage is occasioned to public assets adjoining the site Council will deduct from security any costs associated with remedying, repairing or replacing damaged public infrastructure. Nothing in this condition prevents Council making any claim against security held for this purpose.

Condition Reason: To ensure that any damage to public infrastructure is identified and rectified prior to the occupation of the whole building.

<p>G. 8.</p>	<p>Works-As-Executed Certification of Stormwater Systems</p> <p>Before the issue of an occupation certificate for the whole of the building, and on the completion of construction work, stormwater drainage works are to be certified by a professional engineer with works-as-executed drawings supplied to the Principal Certifier detailing:</p> <ul style="list-style-type: none"> a) compliance with conditions of development consent relating to stormwater, b) that all below ground structures are fully tanked and subsoil drainage/seepage water is NOT collected and discharged into the kerb and gutter in accordance with the approved stormwater drawings, c) that any required stormwater treatment system have been constructed in accordance with the approved construction stormwater plans and that the system meets the water quality targets stipulated in the Council’s DCP, d) that only one stormwater outlet pipe to Council’s kerb inlet pit has been constructed, e) that the works have been constructed in accordance with the approved design, f) pipe invert levels and surface levels to Australian Height Datum, and g) contours indicating the direction in which water will flow over land should the capacity of the pit be exceeded in a storm event exceeding design limits. <p>Notes:</p> <ul style="list-style-type: none"> • The occupation certificate for the whole of the building must not be issued until this condition has been satisfied. <p>Condition Reason: To ensure the certification and ongoing maintenance of the stormwater system prior to the occupation of the whole building.</p>
<p>G. 9.</p>	<p>Amenity Landscaping</p> <p>Before the issue of any occupation certificate, all approved amenity landscaping (screen planting, soil stabilisation planting, etc.) and replacement/supplementary tree planting must be installed in accordance with the approved plans and documents and any relevant conditions of consent.</p> <p>Condition Reason: To ensure that the environmental impacts of the development are mitigated by approved landscaping prior to the occupation of the development.</p>
<p>G. 10.</p>	<p>Landscaping</p> <p>Before the issue of any occupation certificate, the Principal Certifier and Council must be provided with a works-as-executed landscape plan and certification from a qualified landscape architect/designer, horticulturist and/or arborist as applicable to the effect that the landscaping and replacement/supplementary tree planting works comply with this consent.</p> <p>Condition Reason: To ensure that all landscaping work is completed prior to occupation.</p>
<p>G. 11.</p>	<p>Arborists Documentation and Compliance Checklist – Prior to any occupation certificate</p> <p>Before the issue of any occupation certificate, the project arborist must provide written certification that all tree protection measures and construction techniques relevant to this consent have been implemented. Documentation for each site visit must include:</p>

- a) A record of the condition of trees to be retained prior to and throughout development.
- b) Recommended actions to improve site conditions and rectification of non-compliance.
- c) Recommendations for future works which may impact the trees.

All compliance certification documents must be kept on site by the site Supervisor.

As a minimum the following intervals of site inspections must be made:

Stage of arboricultural inspection and supervision	Compliance documentation and photos must include
Prior to the issue of any occupation certificate	Ensure all trees conditioned to be planted as part of this consent have been planted in accordance with the details prescribed in this consent.

Inspections and compliance documentation must be made by an arborist with AQF Level 5 qualifications.

Additional site visits must be made when required by site arborist and/or site foreman for ongoing monitoring/supervisory work.

Condition Reason: To ensure that all tree protection measures and construction techniques relevant to this consent are implemented.

G. 12. Arborists Documentation and Compliance Checklist – Prior to an occupation certificate for the whole building

Before the issue of any occupation certificate for the whole of the building, the project arborist must provide written certification that all tree protection measures and construction techniques relevant to this consent have been implemented.

Documentation for each site visit must include:

- a) A record of the condition of trees to be retained prior to and throughout development.
- b) Recommended actions to improve site conditions and rectification of non-compliance.
- c) Recommendations for future works which may impact the trees.

All compliance certification documents must be kept on site.

As a minimum the following intervals of site inspections must be made:

Stage of arboricultural inspection and supervision	Compliance documentation and photos must include
Before the issue of any occupation certificate for the whole of the building	<ul style="list-style-type: none"> • The project arborist must supervise the dismantling of tree protection measures • After all demolition, construction and landscaping works are complete the project Arborist must assess that the subject trees have been retained in the same condition and vigour. If changes to condition are identified the project Arborist must provide recommendations for remediation.

Inspections and compliance documentation must be made by an arborist with AQF Level 5 qualifications.

	<p>Additional site visits must be made when required by site arborist and/or site foreman for ongoing monitoring/supervisory work.</p> <p>Condition Reason: To ensure that all tree protection measures and construction techniques relevant to this consent are implemented.</p>
G. 13.	<p>Street Numbering</p> <p>Before the issue of any occupation certificate, the development must be provided with street and sole occupancy unit numbers determined by Council.</p> <p>Notes:</p> <ul style="list-style-type: none"> • Applications for the allocation of street and sole occupancy unit numbers must be made together with any application for a strata certificate or Torrens or community title subdivision certificate. Council will determine at its discretion in accordance with its policy street numbers and street addresses that best suit the public interest. <p>Condition Reason: To ensure that emergency services, utility services, and the general public are able to clearly and readily locate any property and to protect the integrity of street numbering and land information.</p>
G. 14.	<p>New Waste Services</p> <p>Before the issue of any occupation certificate, the required wastes services must be provided. This includes the purchase of all waste and recycling storage containers (bins and crates) from Council or otherwise in accordance with the approved Waste Management Plan.</p> <p>Condition Reason: To ensure waste services are provided prior to occupation.</p>
G. 15.	<p>Certification of Electric Vehicle Charging System</p> <p>Before the issue of any occupation certificate, certification by a suitably qualified person that the electric vehicle charger points and/or electric vehicle circuitry, has been installed in accordance with the construction certificate plans and specifications as required by Condition D.17 must be submitted to the satisfaction of the Principal Certifier.</p> <p>Condition Reason: To ensure the certification of the electric vehicle charging system.</p>

H. OCCUPATION AND ONGOING USE

H. 1.	<p>Maintenance of BASIX Commitments</p> <p>During the occupation and ongoing use, all BASIX commitments must be maintained in accordance with the BASIX Certificate No. 1377864M. This condition affects successors in title with the intent that environmental sustainability measures must be maintained for the life of development under this consent.</p> <p>Condition Reason: To ensure the approved environmental sustainability measures are maintained for the life of development.</p>
--------------	--

<p>H. 2.</p>	<p>Maintenance of Landscaping</p> <p>During the occupation and ongoing use, all landscaping must be maintained in general accordance with this consent.</p> <p>This condition does not prohibit the planting of additional trees or shrubs subject that they are native species endemic to the immediate locality.</p> <p>Notes:</p> <ul style="list-style-type: none"> • This condition also acknowledges that development consent is not required to plant vegetation and that over time additional vegetation may be planted to replace vegetation or enhance the amenity of the locality. • Owners must have regard to the amenity impact of trees upon the site and neighbouring land. Further, drought proof vegetation being native species endemic to the immediate locality is encouraged. Suggested native species endemic to the immediate locality are listed in the brochure “Local Native Plants for Sydney’s Eastern Suburbs” published by Woollahra, Waverley, Randwick and Botany Bay Councils. <p>Condition Reason: To ensure that the landscaping design intent is not eroded over time by the removal of landscaping or inappropriate exotic planting.</p>
<p>H. 3.</p>	<p>Ongoing Maintenance of the Stormwater Treatment System</p> <p>During the occupation and ongoing use, in accordance with this condition and any positive covenant, the person with the benefit of this consent must:</p> <ol style="list-style-type: none"> a) Permit stormwater to be treated by the System; b) Keep the system clean and free of silt rubbish and debris, c) Maintain renew and repair as reasonably required from time to time the whole or part of the system so that it functions in a safe and efficient manner. d) Carry out the matters referred to in paragraphs (b) and (c) at the Owners expense. e) Not make any alterations to the system or elements thereof without prior consent in writing of the Council and not interfere with the system or by its act or omission cause it to be interfered with so that it does not function or operate properly. f) Permit the Council or its authorised agents from time to time upon giving reasonable notice (but at any time and without notice in the case of an emergency) to enter and inspect the land with regard to compliance with the requirements of this covenant. g) Comply with the terms of any written notice issued by Council in respect to the requirements of this clause within the time stated in the notice. h) Where the Owner fails to comply with the Owner’s obligations under this covenant, permit the Council or its agents at all times and on reasonable notice at the Owner’s cost to enter the land with equipment, machinery or otherwise to carry out the works required by those obligations. <p>The owner:</p> <ol style="list-style-type: none"> a) Indemnifies the Council from and against all claims, demands, suits, proceedings or actions in respect of any injury, damage, loss, cost, or liability (Claims) that may be sustained, suffered, or made against the Council arising in connection with the performance of the Owner’s obligations under this covenant except if, and to the extent that, the Claim arises because of the Council’s negligence or default; and b) releases the Council from any Claim it may have against the Council arising in connection with the performance of the Owner’s obligations under this covenant except if, and to the extent that, the Claim arises because of the Council’s negligence or default.

	<p>Notes:</p> <ul style="list-style-type: none"> This condition is supplementary to the owner(s) obligations and Council's rights under any positive covenant. 								
	<p>Condition Reason: To ensure that owners are aware of maintenance requirements for their stormwater systems.</p>								
H. 4.	<p>Provision of Off-street Public and Visitor Parking</p> <p>During the occupation and ongoing use, in compliance with AS 2890.1: Parking facilities - Off-street car parking, unimpeded public access to off-street parking must be maintained as follows:</p> <table border="1"> <thead> <tr> <th>Use</th> <th>Number of spaces</th> </tr> </thead> <tbody> <tr> <td>Car Parking (residents)</td> <td>6</td> </tr> <tr> <td>Bicycle Parking</td> <td>4</td> </tr> <tr> <td>Motorbike Parking</td> <td>1</td> </tr> </tbody> </table> <p>A minimum of 1 carparking space must be allocated to each unit.</p> <p>Notes:</p> <ul style="list-style-type: none"> Where there is a potential for the trespass of private motor vehicles upon private parking servicing the owner of the site may seek to enter into a free parking area agreement with Council. Council may under such agreement enforce parking restrictions under section 650 of the Local Government Act 1993. Further information can be obtained from Council's Compliance Team by calling 9391 7000 or from the Office of Local Government at www.olg.nsw.gov.au or call 4428 4100. 	Use	Number of spaces	Car Parking (residents)	6	Bicycle Parking	4	Motorbike Parking	1
Use	Number of spaces								
Car Parking (residents)	6								
Bicycle Parking	4								
Motorbike Parking	1								
	<p>Condition Reason: To ensure adequate on-site parking is maintained.</p>								
H. 5.	<p>Parking Permits</p> <p>During the occupation and ongoing use, future tenants and residents of the proposed development will not be eligible for resident or visitor parking permits.</p>								
	<p>Condition Reason: To minimise the impact of the development upon on street car parking.</p>								
H. 6.	<p>Outdoor Lighting – Residential</p> <p>During the occupation and ongoing use, outdoor lighting must comply with AS/NZS 4282: Control of the obtrusive effects of outdoor lighting. The maximum luminous intensity from each luminare and threshold limits must not exceed the level 1 control relevant under tables in AS/NZS 4282.</p>								
	<p>Condition Reason: To protect the amenity of neighbours and limit the obtrusive effects of outdoor lighting.</p>								
H. 7.	<p>Noise Control</p> <p>During the occupation and ongoing use, the use of the premises must not give rise to the transmission of offensive noise to any place of different occupancy. Offensive noise is defined in the Protection of the Environment Operations Act 1997.</p>								

	<p>Notes:</p> <ul style="list-style-type: none"> • Council will generally enforce this condition in accordance with the Noise Guide for Local Government (www.epa.nsw.gov.au/your-environment/noise/regulating-noise/noise-guide-local-government) and the NSW Industrial Noise Policy (www.epa.nsw.gov.au/your-environment/noise/industrial-noise) published by the NSW Environment Protection Authority. Other State Government authorities also regulate the Protection of the Environment Operations Act 1997. • Useful links: <ul style="list-style-type: none"> - Community Justice Centres—free mediation service provided by the NSW Government www.cjc.nsw.gov.au. - NSW Environment Protection Authority— see “noise” section www.environment.nsw.gov.au/noise. - NSW Government legislation- access to all NSW legislation, including the Protection of the Environment Operations Act 1997 and the Protection of the Environment Noise Control Regulation 2017 is available at www.legislation.nsw.gov.au. - Australian Acoustical Society—professional society of noise related professionals www.acoustics.asn.au. - Association of Australian Acoustical Consultants—professional society of noise related professionals www.aaac.org.au. - Liquor and Gaming NSW—www.liquorandgaming.nsw.gov.au. <p>Condition Reason: To protect the amenity of the neighbourhood.</p>
<p>H. 8.</p>	<p>Noise from Mechanical Plant and Equipment</p> <p>During the occupation and ongoing use, the noise level measured at any boundary of the site at any time while the mechanical plant and equipment is operating must not exceed the background noise level. Where noise sensitive receivers are located within the site, the noise level is measured from the nearest strata, stratum or community title land and must not exceed background noise level at any time.</p> <p>The background noise level is the underlying level present in the ambient noise, excluding the subject noise source, when extraneous noise is removed. For assessment purposes the background noise level is the LA90, 15 minute level measured by a sound level meter.</p> <p>Notes:</p> <ul style="list-style-type: none"> • Words in this condition have the same meaning as in the Noise Policy for Industry (2017) www.epa.nsw.gov.au/your-environment/noise/industrial-noise/noise-policy-for-industry-(2017) and Noise Guide for Local Government (2013) www.epa.nsw.gov.au/your-environment/noise/regulating-noise/noise-guide-local-government <p>Condition Reason: To protect the amenity of the neighbourhood.</p>

SUBDIVISION WORK

I. BEFORE ISSUE OF A SUBDIVISION WORKS CERTIFICATE

<p>I. 1.</p>	<p>Electricity Substations – Dedication as Road and/or Easements for Access</p> <p>Before the issue of any subdivision certificate, if an electricity pillar and/or substation is required on the site the owner must dedicate to the appropriate energy authority (to its satisfaction), free of cost, an area of land adjoining the street alignment to enable an electricity pillar and/or substation to be established. The size and location of the electricity substation is to be in accordance with the requirements of the appropriate energy authority and Council. The opening of any access doors must not intrude onto the public road (footway or road pavement).</p>
---------------------	--

Documentary evidence of compliance, including correspondence from the network authority is to be provided to the Principal Certifier prior to issue of the construction certificate detailing energy authority requirements.

The Accredited Certifier must be satisfied that the requirements of the energy authority have been met prior to issue of the construction certificate.

Where an electricity substation is provided on the site adjoining the road boundary, the area within which the substation is located must be dedicated as public road. Where access is required across the site to access an electricity pillar and/or substation an easement for access across the site from the public place must be created upon the linen plans burdening the subject site and benefiting the Crown in right of New South Wales and any statutory corporation requiring access to the electricity pillar and/or substation.

Condition Reason: To ensure that the energy authority is provided with access to electricity pillars and/or substations.

J. BEFORE SUBDIVISION WORK COMMENCES

Nil.

K. BEFORE ISSUE OF A SUBDIVISION CERTIFICATE

Nil.

LAND SUBDIVISION

L. BEFORE ISSUE OF A SUBDIVISION CERTIFICATE

Nil.

STRATA SUBDIVISION

M. BEFORE ISSUE OF A STRATA CERTIFICATE

Nil.

Note: In accordance with the Woollahra Local Planning Panel Operational Procedures the votes are recorded on this planning matter.

For the Motion

Peter Brennan
Larissa Ozog
David Ryan
Malcolm Young

4/0

Against the Motion

Nil

ITEM No. D5
FILE No. DA255/2023/1
ADDRESS 374 Oxford Street, Paddington
PROPOSAL New fit out and new shopfront to the existing building and change of use to a licenced restaurant (Jimmy's Falafel) along with associated signage and mechanical exhausts

Note: The Chair, David Ryan declared a Significant Non-Pecuniary interest in this Item, as Mr Ryan's company, Gyde has provided and continues to provide consultant town planning services for several development projects (not including the subject site) on behalf of entities associated with the applicant/owner (Hemmes). Mr Ryan left the meeting during this item, did not participate in the debate and did not vote on the matter.

Note: David Ryan, Chair left the meeting and Peter Brennan, Expert assumed the Chair.

Reasons for Decision

The Panel has undertaken a site inspection, considered any submissions and reviewed the assessment report prepared by Council officers that addresses the relevant matters detailed in Section 4.15 of the Environmental Planning and Assessment Act 1979.

For the reasons generally in the assessment report, the Panel is satisfied that the application can be approved.

Resolved: Pursuant to Section 4.16 of the Environmental Planning and Assessment Act 1979

THAT the Woollahra Local Planning Panel, exercising the functions of Council, as the consent authority, is satisfied that the written request from the applicant under Part 4.6 of the Woollahra Local Environmental Plan 2014 to the Floor Space Ratio development standard under Clause 4.4 of Woollahra LEP 2014 has adequately addressed the relevant matters and the proposed development will be in the public interest because it is consistent with the relevant objectives of the particular standard and the zone. The Panel assumes the concurrence of the Secretary, Department of Planning, Industry and Environment.

AND

THAT the Woollahra Local Planning Panel, exercising the functions of Council, as the consent authority, grant development consent to Development Application No. 255/2023/1 for new fit out and new shopfront to the existing building and change of use to a licenced restaurant (Jimmy's Falafel) along with associated signage and mechanical exhausts on land at 374 Oxford Street Paddington, subject to the following conditions:

A. General Conditions

A.1 Conditions

Consent is granted subject to the following conditions imposed pursuant to section 4.16 of the *Environmental Planning and Assessment Act 1979* ("the *Act*") and the provisions of the *Environmental Planning and Assessment Regulation 2000* ("the *Regulation*") such conditions being reasonable and relevant to the development as assessed pursuant to section 4.15 of the *Act*.

Standard Condition: A1 (Autotext AA1)

A.2 Definitions

Unless specified otherwise, words have the same meaning as defined by the *Act*, the *Regulation* and the *Interpretation Act 1987* as in force at the date of consent.

Applicant means the applicant for this consent.

Approved Plans mean the plans endorsed by Council referenced by this consent as amended by conditions of this consent.

AS or **AS/NZS** means Australian Standard® or Australian/New Zealand Standard®, respectively, published by Standards Australia International Limited.

BCA means the Building Code of Australia as published by the Australian Building Codes Board as in force at the date of issue of any Construction Certificate.

Council means Woollahra Municipal Council

Court means the Land and Environment Court

Local native plants means species of native plant endemic to Sydney's eastern suburbs (see the brochure titled "Local Native Plants for Sydney's Eastern Suburbs" published by the Southern Sydney Regional Organisation of Councils).

Stormwater drainage system means all works, facilities and documentation relating to:

- the collection of stormwater,
- the retention of stormwater,
- the reuse of stormwater,
- the detention of stormwater,
- the controlled release of stormwater; and
- connections to easements and public stormwater systems.

Owner means the owner of the *site* and successors in title to the *site*.

Owner-builder has the same meaning as in the *Home Building Act 1989*.

PC means the Principal Certifier under the *Act*.

Principal Contractor has the same meaning as in the *Act*, or where a Principal Contractor has not been appointed by the Owner of the land being developed Principal Contractor means the Owner of the land being developed.

Professional engineer has the same meaning as in the *BCA*.

Public place has the same meaning as in the *Local Government Act 1993*.

Road has the same meaning as in the *Roads Act 1993*.

SEE means the final version of the Statement of Environmental Effects lodged by the Applicant.

Site means the land being developed subject to this consent.

Woollahra LEP means *Woollahra Local Environmental Plan 2014*

Woollahra DCP means *Woollahra Development Control Plan 2015*

Work for the purposes of this consent means:

- the use of land in connection with development,
- the subdivision of land,
- the erection of a building,
- the carrying out of any work,
- the use of any site crane, machine, article, material, or thing,
- the storage of waste, materials, site crane, machine, article, material, or thing,
- the demolition of a building,
- the piling, piercing, cutting, boring, drilling, rock breaking, rock sawing or excavation of land,
- the delivery to or removal from the *site* of any machine, article, material, or thing, or
- the occupation of the *site* by any person unless authorised by an occupation certificate.

Note: Interpretation of conditions - Where there is any need to obtain an interpretation of the intent of any condition this must be done in writing to Council and confirmed in writing by Council.
 Standard Condition: A2 (Autotext AA2)

A.3 Approved Plans and Supporting Documents

Those with the benefit of this consent must carry out all work and maintain the use and works in accordance with both the architectural plans to which is affixed a Council stamp “Approved” and supporting documents listed below as submitted by the Applicant unless modified by any following condition.

Where the plans relate to alterations or additions only those works shown in colour or highlighted are approved.

Reference	Description	Author/Drawn	Date(s)
01.01_DA (Rev M)	Plan – Proposed Basement	Llvstudio p/l	07.07.23
01.01 (Rev M)	Plan – Proposed Basement	Llvstudio p/l	07.07.23
01.02_DA (Rev M)	Plan – Proposed Ground Floor	Llvstudio p/l	28.06.23
01.02 (Rev M)	Plan – Proposed Ground Floor	Llvstudio p/l	28.06.23
01.03_DA (Rev E)	Plan – Existing Level One	Llvstudio p/l	31.05.23
01.04_DA (Rev A)	Plan – Proposed Roof	Llvstudio p/l	01.07.22
2.01_DA (Rev I)	Elevation – Proposed Shopfront	Llvstudio p/l	21.05.24
2.02_DA (Rev C)	Elevation – Proposed Rear	Llvstudio p/l	15.05.23
3.01_DA (Rev G)	Section – Proposed	Llvstudio p/l	07.07.23
3.02_DA (Rev D)	Section – Proposed	Llvstudio p/l	15.05.23
53.5504.R1B:MSC	Acoustic Report	The Acoustic Group	06/06/2023
Version 2	Contaminated Land - Remedial Action Plan (Stage 3)	Trinitas Group	05/04/2024
Version 2	Additional Contamination Assessment – Delineation	Trinitas Group	05/04/2024
20348	Traffic Response to RFI	McLaren Traffic Engineering	23 Feb 2024
0406r06v01	Traffic and Parking Impact Assessment	McLaren Traffic Engineering	10 Aug 2023
Jimmy’s Falafel 374 Oxford Street, Paddington	Plan of Management	Merivale	Submitted to Council on 10/11/2023
Attachment 1	Site Waste Minimisation and Management Plan	Hemmes Trading Pty Limited	

Note: Warning to Accredited Certifiers – You should always insist on sighting the original Council stamped approved plans. You should not rely solely upon the plan reference numbers in this condition. Should the Applicant not be able to provide you with the original copy Council will provide you with access to its files so you may review our original copy of the approved plan.

Note: These plans and supporting documentation may be subject to conditions imposed under section 4.17(1)(g) of the *Act* modifying or amending the development (refer to conditions which must be satisfied prior to the issue of any *Construction Certificate*.)
Standard Condition: A5 (Autotext AA5)

A.4 Ancillary Aspects of Development (section 4.17(2) of the Act)

The Owner must procure the repair, replacement or rebuilding of all road pavement, kerb, gutter, footway, footpaths adjoining the site or damaged as a result of work under this consent or as a consequence of work under this consent. Such work must be undertaken to Council's satisfaction in accordance with Council's *Specification for Roadworks, Drainage and Miscellaneous Works (2012)* unless expressly provided otherwise by these conditions at the Owner's expense.

Note: This condition does not affect the Principal Contractor's or any sub-contractors obligations to protect and preserve public infrastructure from damage or affect their liability for any damage that occurs.
Standard Condition: A8 (Autotext AA8)

A.5 No Underpinning Works

This development consent does NOT give approval to any works outside the boundaries of the subject property including any underpinning works to any structures on adjoining properties.

B. Conditions which must be satisfied prior to the demolition of any building or construction

B.1 Construction Certificate Required Prior to Any Demolition

Where demolition is associated with an altered portion of, or an extension to an existing building the demolition of any part of a building is "commencement of erection of building" pursuant to section 6.6 of the *Act*.

In such circumstance all conditions in Part C and Part D of this consent must be satisfied prior to any demolition work. This includes, but is not limited to, the issue of a Construction Certificate, appointment of a Principal Certifier, and Notice of Commencement under the *Act*.

Note: See *Over our Dead Body Society Inc v Byron Bay Community Association Inc* [2001] NSWLEC 125.
Standard Condition: B1 (Autotext BB1)

B.2 Identification of Hazardous Material

In accordance with Australian Standard AS2601: *The Demolition of Structures*, the Owner shall identify all hazardous substances located on the site including asbestos, polychlorinated biphenyls (PCBs), lead paint, underground storage tanks, chemicals, etc. per clause 1.6.1 of the Standard.

In this regard, **prior to the commencement of any work**, Council shall be provided with a written report prepared by a suitably qualified competent person detailing:

- all hazardous materials identified on the site,
- the specific location of all hazardous materials identified,
- whether the hazardous materials are to be removed from the site as part of the works to be undertaken, and
- safety measures to be put in place.

Note: This condition is imposed to protect the health and safety of all persons while works are being undertaken and to ensure all safety measures have been identified and are in place to protect all parties in the immediate vicinity of the site. Standard Condition: B6

B.3 Public Road Assets Prior to Any Work/Demolition

To clarify the condition of the existing public infrastructure prior to the commencement of any development (including prior to any demolition), the Applicant or Owner must submit to Council a full record of the condition of the public road infrastructure adjacent to the development site.

The report must be submitted to Council **prior to the commencement of any work** and include photographs showing current condition and any existing damage fronting and adjoining the site to the:

- road pavement,
- kerb and gutter,
- footway including footpath pavement and driveways,
- retaining walls within the footway or road, and
- drainage structures/pits.

The reports are to be supplied in both paper copy and electronic format in Word. Photographs are to be in colour, digital and date stamped.

If the required report is not submitted then Council will assume there was no damage to any infrastructure in the immediate vicinity of the site prior to the commencement of any work under this consent.

Note: If the Applicant or Owner fails to submit the asset condition report required by this condition and damage is occasioned to public assets adjoining the site, Council will deduct from security any costs associated with remedying, repairing or replacing damaged public infrastructure. Nothing in this condition prevents Council making any claim against security held for this purpose
Standard Condition: B7

B.4 Noise Control Objectives during Demolition Works

To assist in managing impacts of noise from the demolishing of the existing dwelling and outbuilding on residences and other sensitive land uses, it is recommended that the *NSW Department of Environment & Climate Change: Construction Noise Guideline* be applied to the site to provide a quantitative and qualitative assessment for evaluating performance and compliance of resultant noise from demolishing works of the existing dwelling and outbuilding. In particular reference is made to Table 2 of the *NSW Department of Environment & Climate Change: Construction Noise Guideline* which sets out management levels for noise at residences and other sensitive land uses.

C. Conditions which must be satisfied prior to the issue of any Construction Certificate

C.1 Modification of Details of the Development (section 4.17(1)(g) of the Act)

The approved plans and the Construction Certificate plans and specification, required to be submitted to the Certifying Authority pursuant to clause 139 of the *Regulation*, must detail the following amendments:

- a) The glazing panel at no. 374 Oxford Street is to be broken up into vertical bays, as was originally proposed to ensure an acceptable heritage outcome. Refer to Diagram 1 below.




Diagram 1: Required Window Design

- Woollahra DCP 2015, Chapter C1, Clause 1.3.8, Objective O1, Control C8
 - Woollahra DCP 2015, Chapter C1, Clause 1.3.8, *Commercial development in Oxford Street*, Objective 5, Control C3
 - Woollahra DCP 2015, Chapter C1, Clause 1.4.1, Objectives O4, O6, O7, O12
- b) The drawing set is to be amended/annotated to indicate that the materiality of the new rear wall at basement level is to be of a painted brick finish.
- Woollahra DCP 2015, Chapter C1, Clause 1.5.8, Objective O2, Controls C4, C5, Table 8
- c) The drawing set is to be amended/annotated to indicate that the new opening along the rear elevation of the building at basement level is to be a vertically proportioned door.
- Woollahra DCP 2015, Chapter C1, Clause 1.5.3, Controls C4, C5
- d) The drawing set is to be amended/annotated to indicate that the top hamper signage is flush to the external face of the shopfront where practicable, but in any case does not project more than 100mm.
- Woollahra DCP 2015, Chapter E7, Clause E7.3, Objectives O3, O4, O6, Control C8 (b)
- e) The drawing set is to be amended/annotated to indicate that the new gate along Victoria Street be of either metal or timber construction (only one can be nominated).
- Woollahra DCP 2015, Chapter C1, Clause 1.5.5, Objective O3, Control C17
 - Woollahra DCP 2015, Chapter C1, Clause 1.5.8, Objective O2 Controls C4, C5 and Table 8

Note: The effect of this condition is that it requires design changes and/or further information to be provided with the Construction Certificate drawings and specifications to address specific issues identified during assessment under section 4.15 of the *Act*.

Note: Clause 146 of the *Regulation* prohibits the issue of any Construction Certificate subject to this condition unless the Certifying Authority is satisfied that the condition has been complied with.

Note: Clause 145 of the *Regulation* prohibits the issue of any Construction Certificate that is inconsistent with this consent. Standard Condition: C4 (Autotext CC4)

C.2 Payment of Long Service Levy, Security, Contributions and Fees

The Certifying Authority must not issue any certificates under section 6.4 of the *Act* until provided with the original receipt(s) for the payment of all of the following levy, security, contributions, and fees prior to the issue of a Construction Certificate, Subdivision Certificate or Occupation Certificate, as will apply.

Description	Amount	Indexed	Council Fee Code
LONG SERVICE LEVY under <i>Building and Construction Industry Long Service Payments Act 1986</i>			
Long Service Levy www.longservice.nsw.gov.au/bci/levy/other-information/levy-calculator	Contact LSL Corporation or use online calculator	No	
SECURITY under section 4.17(6) of the <i>Environmental Planning and Assessment Act 1979</i>			
Property Damage Security Deposit -making good any damage caused to any property of the Council	\$61,045	No	T115
INSPECTION FEES under section 608 of the <i>Local Government Act 1993</i>			
Public Road/Footpath Infrastructure Inspection Fee	\$645	No	
Security Administration Fee	\$225	No	T16
TOTAL SECURITY, CONTRIBUTIONS, LEVIES AND FEES	\$61,915 plus any relevant indexed amounts and long service levy		

Building and Construction Industry Long Service Payment

The long service levy under section 34 of the *Building and Construction Industry Long Service Payment Act 1986*, must be paid and proof of payment provided to the Certifying Authority prior to the issue of any Construction Certificate. The levy can be paid directly to the Long Service Corporation or to Council. Further information can be obtained from the Long Service Corporation website www.longservice.nsw.gov.au or the Long Service Corporation on 131 441.

How must the payments be made?

Payments must be made by:

- cash deposit with Council,
- credit card payment with Council, or
- bank cheque made payable to Woollahra Municipal Council.

The payment of a security may be made by a bank guarantee where:

- the guarantee is by an Australian bank for the amount of the total outstanding contribution,
- the bank unconditionally agrees to pay the guaranteed sum to the Council on written request by Council on completion of the development or no earlier than 12 months from the provision of the guarantee whichever occurs first [NOTE: a time limited bank guarantee or a bank guarantee with an expiry date is not acceptable],
- the bank agrees to pay the guaranteed sum without reference to the Applicant or landowner or other person who provided the guarantee and without regard to any dispute, controversy, issue or other matter relating to the development consent or the carrying out of development in accordance with the development consent,
- the bank guarantee is lodged with the Council prior to the issue of the Construction Certificate, and
- the bank's obligations are discharged when payment to the Council is made in accordance with the guarantee or when Council notifies the bank in writing that the guarantee is no longer required.

How will the section 7.12 levy (formerly known as 94A levy) be indexed?

To ensure that the value the development levy is not eroded over time by increases in costs, the proposed cost of carrying out development (from which the development levy is calculated) will be indexed either annually or quarterly (see table above). Clause 3.13 of the Woollahra Section 94A Development Contributions Plan 2021 sets out the formula and index to be used in adjusting the levy.

Do you need HELP indexing the levy?

Please contact Council's Customer Service Team on ph 9391 7000. Failure to correctly calculate the adjusted development levy will delay the issue of any certificate issued under section 6.4 of the *Act* and could void any such certificate (eg Construction Certificate, Subdivision Certificate, or Occupation Certificate).

Deferred or periodic payment of section 7.12 levy (formerly known as 94A levy) under the Woollahra Section 94A Development Contributions Plan 202

Where the Applicant makes a written request supported by reasons for payment of the section 7.12 levy other than as required by clause 3.9, the Council may accept deferred or periodic payment. The decision to accept a deferred or periodic payment is at the sole discretion of the Council, which will consider:

- the reasons given,
- whether any prejudice will be caused to the community deriving benefit from the public facilities,
- whether any prejudice will be caused to the efficacy and operation of the Plan, and
- whether the provision of public facilities in accordance with the adopted works schedule will be adversely affected.

Council may, as a condition of accepting deferred or periodic payment, require the provision of a bank guarantee where:

- the guarantee is by an Australian bank for the amount of the total outstanding contribution,
- the bank unconditionally agrees to pay the guaranteed sum to the Council on written request by Council on completion of the development or no earlier than 12 months from the provision of the guarantee whichever occurs first [NOTE: a time limited bank guarantee or a bank guarantee with an expiry date is not acceptable],
- the bank agrees to pay the guaranteed sum without reference to the Applicant or landowner or other person who provided the guarantee and without regard to any dispute, controversy, issue or other matter relating to the development consent or the carrying out of development in accordance with the development consent,
- the bank guarantee is lodged with the Council prior to the issue of the Construction Certificate, and
- the bank's obligations are discharged when payment to the Council is made in accordance with the guarantee or when Council notifies the bank in writing that the guarantee is no longer required.

Any deferred or periodic payment of the section 7.12 levy will be adjusted in accordance with clause 3.13 of the Plan. The Applicant will be required to pay any charges associated with establishing or operating the bank guarantee. Council will not cancel the bank guarantee until the outstanding contribution as indexed and any accrued charges are paid.

Standard Condition: C5

C.3 Payment of S7.12 Contributions Levy

A payment of a levy authorised by section 7.12 of the Environmental Planning and Assessment Act 1979 must be paid prior to the issue of any Construction Certificate or Subdivision Works Certificate. The Principal Certifier is to be provided with the original receipt for payment under the Woollahra Section 7.12 Development Contributions Plan 2022.

A cost estimate report, no more than 3 months old, demonstrating the proposed cost of carrying out the development must be completed and submitted to Council for determination of the costs of work. This report must incorporate all approved modification applications. The costs and expenses of the proposed cost of development must be established in accordance with clause 208 of the Environmental Planning and Assessment Regulation 2021.

The cost estimate report must be in the form of:

- A cost summary report, prepared by the applicant or a suitably qualified person for a development up to \$749,999; or
- A quantity surveyor's report, for development over \$750,000.

The applicable levy rate is to be calculated using the summary schedule below.

Summary Schedule	
Development Cost	Levy Rate
• Up to and including \$100,000	Nil
• More than \$100,000 and up to and including \$200,000	0.5% of the cost
• More than \$200,000	1% of the cost

How must the payments be made?

Payments must be made by:

- Cash deposit with Council,
- Credit card payment with Council, or
- Bank cheque made payable to Woollahra Municipal Council.

Deferred or periodic payment of section 7.12 levy

Where the Applicant makes a written request supported by reasons for payment of the section 7.12 levy other than as required by clause 2.9, the Council may accept deferred or periodic payment. The decision to accept a deferred or periodic payment is at the sole discretion of the Council, which will consider:

- the reasons given,
- whether any prejudice will be caused to the community deriving benefit from the public facilities,
- whether any prejudice will be caused to the efficacy and operation of the Plan, and
- whether the provision of public facilities in accordance with the adopted works schedule will be adversely affected.

Council may, as a condition of accepting deferred or periodic payment, require the provision of a bank guarantee where:

- the guarantee is by an Australian bank for the amount of the total outstanding contribution,
- the bank unconditionally and irrevocably agrees to pay the guaranteed sum to the Council on written request by Council prior to the issue of an occupation certificate,
- a time limited bank guarantee or a bank guarantee with an expiry date is not acceptable,
- the bank agrees to pay the guaranteed sum without recourse to the applicant or landowner or other person who provided the guarantee and without regard to any dispute, controversy, issue or other matter relating to the development consent or the carrying out of development in accordance with the development consent, and
- the bank's obligations are discharged when payment to the Council is made in accordance with the guarantee or when Council notifies the bank in writing that the guarantee is no longer required.

Any deferred or periodic payment of the section 7.12 levy will be adjusted in accordance with clause 2.12 of the Plan. The Applicant will be required to pay any charges associated with establishing or operating the bank guarantee. Council will not cancel the bank guarantee until the outstanding contribution as indexed and any accrued charges are paid.

Do you need HELP indexing the levy?

Please contact Council's Customer Service Team on 02 9391 7000. Failure to correctly calculate the adjusted development levy will delay the issue of any certificate issued under section 6.4 of the Act and could void any such certificate (e.g. construction certificate, subdivision certificate, or occupation certificate).

This condition has been imposed to ensure any relevant contributions are paid.

C.4 Building Upgrade (Clause 64 of the Regulation)

Council considers, pursuant to clause 64 of the *Regulation*, that it is appropriate to require the existing building to be brought into total or partial conformity with the BCA because the measures contained in the building are inadequate:

- (i) to protect persons using the building, and to facilitate their egress from the building, in the event of fire, or
- (ii) to restrict the spread of fire from the building to other buildings nearby.

Accordingly, it is considered appropriate to require the existing building to be brought into total or partial conformity with the BCA and the Construction Certificate plans and specification required to be submitted to the Certifying Authority pursuant to clause 139 of the *Regulation* must detail building upgrade works required by this condition.

The Certifying Authority must be satisfied that such work, to be implemented as part of the development, will upgrade the building to bring it into compliance with the following provisions of the BCA as in force at the date of the Construction Certificate application:

- a) Parts D2 & D3, or the relevant Performance Requirements, of the BCA

Note: The Certifying Authority issuing the Construction Certificate has no power to remove the requirement to upgrade the existing building as required by this condition. Where this condition specifies compliance with performance requirements of the BCA the Certifying Authority, subject to their level of accreditation, may be satisfied as to such matters. Where this condition specifies compliance with prescriptive (Deemed-to-Satisfy) provisions of the BCA these prescriptive requirements must be satisfied and cannot be varied unless this condition is reviewed Part 8 Division 8.2 or amended under section 4.55 of the *Act*.

Note: This condition does not set aside the Certifying Authority's responsibility to ensure compliance with clause 143 of the *Regulation* in relation to Fire Protection and Structural Adequacy.

Note: AS 4655 *Guidelines for fire safety audits for buildings* (or any succeeding AS) should form the basis of any fire upgrade report.
Standard Condition: C10 (Autotext CC10)

C.5 Road and Public Domain Works

A separate application under Section 138 of the *Roads Act* 1993 is to be made to, and be approved by Council as the road authority, for the following infrastructure works prior to the issuing of any Construction Certificate. The infrastructure works must be carried out at the applicant's expense:

1. The existing Telstra pit is located within the vehicular crossing. As such, the applicant must consult and obtain written approval from Telstra confirming that satisfactory arrangement has been made for the relocation or retention of such pit. A copy of the approval letter shall be submitted to Council with this application,
2. The installation of stormwater outlet pipe across the nature strip must be made by using 150mm x 75mm galvanised rectangular hollow section (RHS) in accordance with Council's Specification for Roadworks, Drainage and Miscellaneous Works and to the satisfaction of Council's Assets Engineers,
3. The reinstatement of the existing crossing, kerb and gutter and road pavement to Council's Specification for Roadworks, Drainage and Miscellaneous Works and to the satisfaction of Council's Assets Engineers,
4. The submission of a certificate from a professional engineer (structural engineer), certifying the structural adequacy of the existing awning over Council's property,
5. Observe condition for the creation of positive covenant requirements,

Note: To ensure that this work is completed to Council's satisfaction, this consent by separate condition, may impose one or more Infrastructure Works Bonds.

Note: *Road* has the same meaning as in the *Roads Act* 1993.

Note: The intent of this condition is that the design of the road, footpaths, driveway crossings and public stormwater drainage works must be detailed and approved prior to the issue of any *Construction Certificate*. Changes in levels may arise from the detailed design of buildings, road, footpath, driveway crossing grades and stormwater. Changes required under *Roads Act 1993* approvals may necessitate design and levels changes under this consent. This may in turn require the applicant to seek to amend this consent.

Note: See condition K13 in *Section K. Advisings* of this Consent titled *Roads Act Application*.
Standard Condition: C13 (Autotext CC13)

C.6 Soil and Water Management Plan – Submission and Approval

The Principal Contractor or Owner-builder must submit to the Certifying Authority a soil and water management plan complying with:

- a) “*Do it Right On Site, Soil and Water Management for the Construction Industry*” published by the Southern Sydney Regional Organisation of Councils, 2001; and
- b) “*Managing Urban Stormwater - Soils and Construction*” 2004 published by the NSW Government (*The Blue Book*).

Where there is any conflict *The Blue Book* takes precedence.

The Certifying Authority must be satisfied that the soil and water management plan complies with the publications above prior to issuing any Construction Certificate.

Note: This condition has been imposed to eliminate potential water pollution and dust nuisance.

Note: The International Erosion Control Association – Australasia www.austieca.com.au lists consultant experts who can assist in ensuring compliance with this condition. Where erosion and sedimentation plans are required for larger projects it is recommended that expert consultants produce these plans.

Note: The “*Do it Right On Site, Soil and Water Management for the Construction Industry*” publication can be downloaded from www.woollahra.nsw.gov.au, and *The Blue Book* is available at www.environment.nsw.gov.au/stormwater/publications.htm.

Note: Pursuant to clause 161(1)(a)(5) of the *Regulation* an Accredited Certifier may be satisfied as to this matter.
Standard Condition: C25

C.7 Structural Adequacy of Existing Supporting Structures

A certificate from a professional engineer (structural engineer), certifying the adequacy of the existing supporting structure to support the additional loads proposed to be imposed by the development, must be submitted with the Construction Certificate application.

Note: This condition is imposed to ensure that the existing structure is able to support the additional loads proposed.

Standard Condition: C35 (Autotext CC35)

C.8 Professional Engineering Details

The Construction Certificate plans and specifications, clause 7 of the *Environmental Planning and Assessment (Development Certification and Fire Safety) Regulation 2021*, must include detailed professional engineering plans and/or specifications for all structural, electrical, hydraulic, hydrogeological, geotechnical, mechanical and civil work complying with this consent, approved plans, the statement of environmental effects and supporting documentation.

Detailed professional engineering plans and/or specifications must be submitted to the Certifying Authority with the application for any Construction Certificate.

Note: This does not affect the right of the developer to seek staged Construction Certificates.
Standard Condition: C36

C.9 Engineer Certification

This development consent does NOT give approval to any works outside the boundaries of the subject property including any underpinning works to any structures on adjoining properties.

Any structural design is not to incorporate any temporary or permanent underpinning works or ground anchors, bolts, etc which encroach outside the boundaries of the subject property. Engineer certification to this effect shall be submitted to the Certifying Authority prior to issue of any Construction Certificate.

C.10 Parking Facilities

The Construction Certificate plans and specifications required by clause 139 of the *Regulation*, must include detailed plans and specifications for all bicycle, car and commercial vehicle parking in compliance with AS2890.3:2015 *Parking Facilities - Bicycle Parking Facilities*, AS/NZS 2890.1:2004 : *Parking Facilities - Off-Street Car Parking* and AS 2890.2:2018 – *Off-Street Parking: Commercial Vehicle Facilities* respectively. Access levels and grades must comply with access levels and grade required by Council under the *Roads Act 1993*.

The Certifying Authority has no discretion to reduce or increase the number or area of car parking or commercial parking spaces required to be provided and maintained by this consent.

Standard Condition: C45 (Autotext: CC45)

C.11 Stormwater Discharge to Existing Stormwater Drainage System

Prior to issue of the Construction Certificate, the applicant must submit, for approval by the Certifying Authority, detailed stormwater management plans prepared by a chartered professional civil engineer, which include the following:

- a) The stormwater management plans must specify any components of the existing drainage system to be retained and certified to be in good condition and of adequate capacity to convey additional runoff and be replaced or upgraded if required.
- b) Detail the location of the existing stormwater drainage system including all pipes, inspection openings, surface drains, pits and their discharge location as well as any new stormwater drainage system.
- c) Detail any remedial works required to upgrade the existing stormwater drainage system.
- d) Internal stormwater drainage pipes and pits are to be designed for rainfall intensities up to and including the 1% AEP event if an unimpeded overland flow path to the street drainage system is not available. Design details and calculations must be included in the stormwater management plans.
- e) The discharge of stormwater from the site to the street kerb located within the frontage of the site. Only one stormwater outlet with a maximum discharge rate of 20 l/s in the 1% AEP storm event will be permitted. Full supporting calculations must be included in the stormwater management plans. The stormwater outlet pipe across the Council's property must have a minimum grade of 1% to comply with Council's DCP and AS3500.3.
- f) All below ground structures are to be fully tanked such that subsoil drainage/ seepage water is NOT discharged to the kerb and gutter to comply with Chapter E2.2.5 of the Council's DCP. Notation to this requirement must be clearly depicted on the drawings.
- g) Dimensions of all drainage pits and access grates must comply with AS3500.3 and Council's DCP.
- h) Interceptor drain(s) at the site boundary to prevent stormwater flows from the site crossing the footpath; and General compliance with the Woollahra DCP 2015 Chapter E2 – Stormwater and Flood Risk Management.

- i) General compliance with the Woollahra DCP 2015 Chapter E2 – Stormwater and Flood Risk Management.

The Stormwater Management Plan must also include the following specific requirements:

Layout plan

A detailed drainage plan at a scale of 1:100 based on drainage calculations prepared in accordance with the Australian Government publication, Australian Rainfall and Run-off, 2019 edition or most current version thereof. It must include:

- a) All pipe layouts, dimensions, grades, lengths and material specification.
- b) Location and dimensions of all downpipes.
- c) All invert levels reduced to Australian Height Datum (AHD).
- d) Location and dimensions of all drainage pits.
- e) Point and method of connection to Council's drainage infrastructure.
- f) Overland flow paths over impervious areas.

For any works to be carried out on Council's property, separate approval under section 138 of the *Roads Act 1993* must be obtained from Council for those works prior to the issue of any Construction Certificate.

All Stormwater Drainage System work within any road or public place must comply with Woollahra Municipal Council's *Specification for Roadworks, Drainage and Miscellaneous Works* (2012).

Note: Clause F1.1 of Volume 1 and Part 3.1.2 of Volume 2 of the BCA provide that stormwater drainage complying with AS/NZS 3500.3 Plumbing and drainage - Part 3: Stormwater drainage is deemed-to-satisfy the BCA. Council's specifications apply in relation to any works with any road or public place.

Note: The collection, storage and use of rainwater is to be in accordance with *Standards Australia HB230-2008 "Rainwater Tank Design and Installation Handbook"*.

Note: Stormwater Drainage Systems must not discharge to any Sewer System. It is illegal to connect stormwater pipes and drains to the sewerage system as this can overload the system and cause sewage overflows. For more information go to the Sydney Water website www.sydneywater.com.au/SW/plumbing-building-developing/index.htm or call 1300 082 746.

Note: Woollahra Municipal Council's *Specification for Roadworks, Drainage and Miscellaneous Works* dated January 2003 and the Woollahra DCP 2015 Chapter E2 – Stormwater and Flood Risk Management can be downloaded from Council's website www.woollahra.nsw.gov.au
Standard Condition: C49

C.12 Flood Protection

Before the issue of any construction certificate, the construction certificate plans and specifications required under clause 7 of the Development Certification and Fire Safety Regulation, must include a Flood Risk Management Plan on the basis of the Flood Planning Level (FPL).

Flood Warning:

- a) A permanent flood risk management plan shall be installed in an area frequented by the occupants such as the kitchen,

Flood Proof Material

- a) Flood compatible materials shall be used for all flood exposed construction.

Electricals

- a) All flood exposed electrical wiring and equipment shall be waterproofed,

Certification

- a) All flood protection measures shall be inspected and certified as fit for purpose after construction is complete by an engineer experienced in flood mitigation,

Flood protection is to comply with Woollahra DCP 2015, Part E General Controls for All Development, Chapter E2 –Stormwater and Flood Risk Management.

Note: The revised driveway profile, gradients and transitions must be in accordance with Australian Standard 2890.1, Part 1: Off-street car parking. The driveway profile submitted to Council must contain all relevant details: reduced levels, proposed grades and distances. Council will not allow alteration to existing reduced levels within the road or any other public place to achieve flood protection.

C.13 Waste Storage – Commercial

The *Construction Certificate* plans and specifications required by clause 139 of the Regulation, must make provision for:

- a) A dedicated and enclosed waste and recycling storage area behind the building line or within non-habitable areas of the building,
Standard Condition: C14

C.14 Light and Ventilation

The *Construction Certificate* plans and specifications, required to be submitted to the *Certifying Authority* pursuant to clause 139 of the *Regulation*, must detail all a lighting, mechanical ventilation or air-conditioning systems complying with Part F.4 of the *BCA* or clause 3.8.4 and 3.8.5 of the *BCA* Housing Provisions, inclusive of [AS 1668.1](#), [AS 1668.2](#) and [AS/NZS 3666.1](#). If an alternate solution is proposed then the *Construction Certificate* application must include a statement as to how the performance requirements of the *BCA* are to be complied with and support the performance based solution by expert *evidence of suitability*. This condition does not set aside the mandatory requirements of the *Public Health (Microbial Control) Regulation 2000* in relation to *regulated systems*. This condition does not set aside the effect of the *Protection of the Environment Operations Act 1997* in relation to offensive noise or odour.

Note: Clause 98 of the Regulation requires compliance with the *BCA*. Clause 145 of the *Regulation* prevents the issue of a *Construction Certificate* unless the *Accredited Certifier/Council* is satisfied that compliance has been achieved. Schedule 1, Part 3 of the *Regulation* details what information must be submitted with any *Construction Certificate*. It is the Applicant's responsibility to demonstrate compliance through the *Construction Certificate* application process. Applicants must also consider possible noise and odour nuisances that may arise. The provisions of the *Protection of the Environment Operations Act 1997* have overriding effect if offensive noise or odour arises from the use. Applicant's must pay attention to the location of air intakes and air exhausts relative to sources of potentially contaminated air and neighbouring windows and air intakes respectively, see section 2 and 3 of [AS 1668.2](#).

Standard Condition C59

C.15 Acoustic Certification of Mechanical Plant and Equipment

The *Construction Certificate* plans and specification required to be submitted pursuant to clause 139 of the *Regulation* must be accompanied by a certificate from a *professional engineer* (acoustic engineer) certifying that the noise level measured at any boundary of the site at any time while the proposed mechanical plant and equipment is operating will not exceed the *background noise level*. Where noise sensitive receivers are located within the site, the noise level is measured from the nearest strata, stratum or community title land and must not exceed *background noise level*, at any time.

The *background noise level* is the underlying level present in the ambient noise, excluding the subject noise source, when extraneous noise is removed. For assessment purposes the background noise level is the $L_{A90, 15 \text{ minute}}$ level measured by a sound level meter.

Where sound attenuation is required this must be detailed.

Note: Further information including lists of Acoustic Engineers can be obtained from:

1. **Australian Acoustical Society**—professional society of noise-related professionals ([www.acoustics.asn.au /index.php](http://www.acoustics.asn.au/index.php)).

2. **Association of Australian Acoustical Consultants**—professional society of noise related professionals (www.aaac.org.au).

Standard Condition: C62

C.16 Food Premises – Construction Certificate Plans and Specifications

The person with the benefit of this consent must submit to Council details for the construction and fit out of food premises. Such details must demonstrate compliance with the *Food Act 2003*, *Food Regulation 2015*; the *Food Standards Code* as published by Food Standards Australia and New Zealand and Australian Standard AS 4674-2004: *Construction and fit out of food premises*.

No *Construction Certificate* relating to the construction or fitout of food premises must be issued until Council's Environmental Health Officers' have advised in writing that the plans and specification are considered satisfactory.

The details for the construction and fit out of food premises, as considered satisfactory by Council's Environmental Health Officers' must form part of any *Construction Certificate*.

Note: The assessment of food premises fitout plans and specifications is subject to an adopted fee. The construction and fitout of food premises is not listed under clause 161 of the *Environmental Planning & Assessment Regulation 2000* as a matter that a *Certifying Authority* may be satisfied as to. Hence, the detailed plans & specifications must be referred to Council and be to Council's satisfaction prior to the issue of any *Construction Certificate* for such works.
Standard Condition: C65

C.17 Noise Control - Hydraulic Noise Control-Sound Insulation Rating of Services

That the requirements of the Building Code of Australia BCA Clause F5.6: ***Ducts, Hot and Cold Domestic Water, Stormwater, Soil and Waste Pipes***, which serves or passes through more than one sole occupancy unit must be separated from habitable rooms (other than a kitchen) in any other sole occupancy unit by a weighted sound reduction index + traffic noise spectrum adaptation term of not less than 40 if it is adjacent to a habitable room, and 25 if it is adjacent to a wet area (bathroom, laundry etc.) or kitchen.

Details are to be provided by the applicant clearly indicating how this requirement will be achieved in respect to controlling hydraulic noise emission to adjoining habitable rooms.

C.18 Noise Control - Acoustic Protection of adjoining residential units-Operation of Air Conditioning Plant

The applicant must ensure that the operation of the proposed Air Condition System and associated plant does not create interior noise intrusion and vibration to occur within any adjoining residential unit.

C.19 Ventilation - Kitchen Exhaust- Smoke & Odour Control

1. The discharge of air from the kitchen exhaust ventilation system(s) is considered an obnoxious discharge under Section 3.7 of Australian Standard 1668.2-1991. The ductwork serving the proposed kitchen exhaust system(s) shall be arranged vertically with a discharge velocity of not less than 5 m/s and be situated at least 1 m above the ridge of a pitched roof or 3 m above the flat of the building.
2. All exhaust air and spill air shall be discharged to atmosphere in such a manner as not to cause a danger or nuisance to occupants in the building, occupants of neighbouring buildings or members of the public.
3. The design, construction and installation of the kitchen exhaust hood(s) shall comply with the requirements of *Appendix E, 'Kitchen Exhaust Hoods' of AS 1668.2-1991* and *Appendix F, 'Capture of Emissions By Kitchen Exhaust Hoods' of AS 1668.2-1991*.
4. A *Smoke & Odour Impact Assessment Report* is to be prepared by a suitably qualified engineer detailing the design specification of the proposed kitchen exhaust system, including all smoke and odour inhibiting controls and filtering systems.
5. The *Construction Certificate* plans and specifications, required to be submitted to the *Certifying Authority* pursuant to clause 139 of the *Regulation*, must detail all the kitchen exhaust ventilation system(s), including all smoke and odour controls and filtering systems. Upon completion and prior to occupation of the premises, the kitchen exhaust ventilation system(s) shall be certified by a qualified engineer that the system(s) has been installed in accordance with AS 1668.1 and AS 1668.2 and the design specification as detailed in the *Smoke & Odour Impact Assessment Report*.

C.20 Ventilation - Internal Sanitary Rooms

All internal sanitary rooms and laundry facilities not provided with natural ventilation must be provided with a system of mechanical exhaust ventilation in accordance with *Table B1 Minimum Exhaust Ventilation Flow Rates of AS 1668.2-1991*. Details of any proposed mechanical ventilation system(s) being submitted with the Construction Certificate plans and specifications, required to be submitted to the Certifying Authority demonstrating compliance with AS 1668 Parts 1 & 2.

D. Conditions which must be satisfied prior to the commencement of any development work

D.1 Compliance with Building Code of Australia and insurance requirements under the [Home Building Act 1989](#)

For the purposes of section 4.17(11) of the *Act*, the following conditions are prescribed in relation to a development consent for development that involves any building work:

- a) that the work must be carried out in accordance with the requirements of the Building Code of Australia,
- b) in the case of residential building work for which the [Home Building Act 1989](#) requires there to be a contract of insurance in force in accordance with Part 6 of that Act, that such a contract of insurance is in force before any building work authorised to be carried out by the consent commences.

This condition does not apply:

- a) to the extent to which an exemption is in force under the *Home Building Regulation 2004*, or
- b) to the erection of a temporary building.

In this condition, a reference to the BCA is a reference to that code as in force on the date the application for the relevant Construction Certificate is made.

Note: This condition must be satisfied prior to commencement of any work in relation to the contract of insurance under the *Home Building Act 1989*. This condition also has effect during the carrying out of all building work with respect to compliance with the Building Code of Australia.

Note: All new guttering is to comply with the provisions of Part 3.5.2 of the Building Code of Australia.
Standard Condition: D1 (Autotext DD1)

D.2 Dilapidation Reports for Existing Buildings

Dilapidation surveys and dilapidation reports shall be conducted and prepared by a *professional engineer* (structural) for all buildings and/or structures that are located within the likely “zone of influence” of any excavation, dewatering and/or construction induced vibration as determined applicable by a Structural Engineer.

These properties to be assessed by the Structural Engineer must include (but is not limited to):

No. 372 & 378 Oxford Street

All required dilapidation reports must be completed and submitted to the *Certifying Authority* with a copy submitted to Council with the *Notice of Commencement* prior to the commencement of any *development work*.

Where excavation of the site will extend below the level of any immediately adjoining building the *principal contractor* or *owner builder* must give the adjoining building owner(s) a copy of the dilapidation report for their building(s) and a copy of the *notice of commencement* required by S81A(2) of the *Act* not less than two (2) days prior to the commencement of any work.

Note: The reasons for this condition are:

- To provide a record of the condition of buildings prior to development being carried out
- To encourage developers and its contractors to use construction techniques that will minimise the risk of damage to buildings on neighbouring land

Also refer to the Dilapidation Report Advising for more information regarding this condition

Standard Condition: D4 (Autotext DD4)

D.3 Adjoining Buildings Founded on Loose Foundation Materials

The Principal Contractor must ensure that a professional engineer determines the possibility of any adjoining buildings founded on loose foundation materials being affected by piling, piers or excavation. The professional engineer (geotechnical consultant) must assess the requirements for underpinning any adjoining or adjacent buildings founded on such soil on a case by case basis and the Principal Contractor must comply with any reasonable direction of the professional engineer.

Note: A failure by contractors to adequately assess and seek professional engineering (geotechnical) advice to ensure that appropriate underpinning and support to adjoining land is maintained prior to commencement may result in damage to adjoining land and buildings. Such contractors are likely to be held responsible for any damages arising from the removal of any support to supported land as defined by section 177 of the *Conveyancing Act 1919*.

Standard Condition: D6 (Autotext DD6)

D.4 Construction Management Plan

As a result of the site constraints, limited space and access a Construction Management Plan (CMP) is to be submitted to Council. Also, due to lack of on-street parking a Work Zone may be required during construction.

The Principal Contractor or Owner must submit an application for approval of the CMP by Council’s Traffic Engineer and pay all fees associated with the application.

The CMP must be submitted as a self-contained document that outlines the nature of the construction project and as applicable, include the following information:

- a) Detail the scope of the works to be completed including details of the various stages, e.g. demolition, excavation, construction etc. and the duration of each stage.
- b) Identify local traffic routes to be used by construction vehicles.
- c) Identify ways to manage construction works to address impacts on local traffic routes.
- d) Identify other developments that may be occurring in the area and identify ways to minimise the cumulative traffic impact of these developments. Should other developments be occurring in close proximity (500m or in the same street) to the subject site, the developer/builder is to liaise fortnightly with the other developers/builders undertaking work in the area in order to minimise the cumulative traffic and parking impacts of the developments.
- e) Detail how construction workers will travel to and from the site and parking arrangements for those that drive.
- f) Identify any proposed road closures, temporary traffic routes, loss of pedestrian or cyclist access or reversing manoeuvres onto a public road and provide Traffic Control Plans (TCPs) prepared by an accredited RMS Red or Orange card holder to manage these temporary changes.
- g) Detail the size (including dimensions), numbers and frequency of arrival of the construction vehicles that will service the site for each stage of works.
- h) Provide for the standing of vehicles during construction.
- i) If construction vehicles are to be accommodated on the site, provide a scaled drawing showing where these vehicles will stand and the vehicle swept path to show that these vehicles can access and egress the site in a forward direction (including dimensions and all adjacent traffic control devices, such as parking restrictions, pedestrian facilities, kerb extensions, etc.).
- j) If trucks are to be accommodated on Council property, provide a scaled drawing showing the location of any proposed Works Zone (including dimensions and all adjacent traffic control devices, such as parking restrictions, pedestrian facilities, kerb extensions, etc.).
- k) Show the location of any site sheds and any anticipated use of cranes and concrete pumps and identify the relevant permits that will be required.
- l) If a crane/s are to be accommodated on site, detail how the crane/s will be erected and removed, including the location, number and size of vehicles involved in the erection/removal of the crane/s, the duration of the operation and the proposed day and times, any full or partial road closures required to erect or remove the crane/s and appropriate Traffic Control Plans (TCPs) prepared by an approved RMS Red or Orange Card holder.
- m) Make provision for all materials, plant, etc. to be stored within the development site at all times during construction.
- n) State that any oversized vehicles proposed to operate on Council property (including Council approved Works Zones) will attain a Permit to Stand Plant on each occasion (Note: oversized vehicles are vehicles longer than 7.5m or heavier than 4.5T.)
- o) Show the location of any proposed excavation and estimated volumes.
- p) When demolition, excavation and construction works are to be undertaken on school days, all vehicular movements associated with this work shall only be undertaken between the hours of 9.30am and 2.30pm, in order to minimise disruption to the traffic network during school pick up and drop off times.
- q) Show the location of all Tree Protection (Exclusion) zones (Note: storage of building materials or access through Reserve will not be permitted without prior approval by Council).

Note: A minimum of eight weeks will be required for assessment. Work must not commence until the Construction Management Plan is approved. Failure to comply with this condition may result in fines and proceedings to stop work.

Standard Condition: D9 (Autotext: DD9)

D.5 Works (Construction) Zone – Approval and Implementation

A Works Zone may be required for this development. The Principal Contractor or Owner can apply for a works zone. If the works zone is approved the Principal Contractor or Owner must pay all fees for this Works Zone before it can be installed.


The Principal Contractor must pay all fees associated with the application and occupation and use of the road as a Works Zone. All Works Zone signs must have been erected by Council to permit enforcement of the Works Zone by Council's Rangers and NSW Police before commencement of any work. Signs are not erected until full payment of works zone fees.

Note: The Principal Contractor or Owner must allow not less than four to six weeks (for routine applications) from the date of making an application to the Traffic Committee (Woollahra Local Traffic Committee) constituted under the clause 22 of the *Transport Administration (General) Regulation 2000* to exercise those functions delegated by the Roads and Maritime Services under section 50 of the *Transport Administration Act 1988*.

Note: The enforcement of the works zone is at the discretion of Council's Rangers and the NSW Police Service. The Principal Contractor must report any breach of the works zone to either Council or the NSW Police Service.
Standard Condition: D10 (Autotext DD10)


D.6 Security Fencing, Hoarding (including 'Creative Hoardings') and Overhead Protection

Security fencing must be provided around the perimeter of the development site, including any additional precautionary measures taken to prevent unauthorised entry to the site at all times during the demolition, excavation and construction period. Security fencing must be the equivalent 1.8m high chain wire as specified in AS 1725.



Type A Hoarding

Where the development site adjoins a public thoroughfare, the common boundary between them must be fenced for its full length with a hoarding, unless the least horizontal distance between the common boundary and the nearest parts of the structure is greater than twice the height of the structure. The hoarding must be constructed of solid materials (chain wire or the like is not acceptable) to a height of not less than 1.8m adjacent to the thoroughfare.



Type B Hoarding


Where a development site adjoins a public thoroughfare with a footpath alongside the common boundary then, in addition to the hoarding required above, the footpath must be covered by an overhead protective structure and the facing facade protected by heavy-duty scaffolding, unless either:

- a) the vertical height above footpath level of the structure being demolished is less than 4.0m; or

- b) the least horizontal distance between footpath and the nearest part of the structure is greater than half the height of the structure.

The overhead structure must consist of a horizontal platform of solid construction and vertical supports, and the platform must:

- a) extend from the common boundary to 200mm from the edge of the carriageway for the full length of the boundary,
- b) have a clear height above the footpath of not less than 2.1m,
- c) terminate 200mm from the edge of the carriageway (clearance to be left to prevent impact from passing vehicles) with a continuous solid upstand projecting not less than 0.5m above the platform surface, and
- d) together with its supports, be designed for a uniformly distributed live load of not less than 7 kPa.



The Principal Contractor or Owner-builder must ensure that overhead protective structures are installed and maintained in accordance with the NSW “Code of Practice - Overhead Protective Structures 1995”. This is code available at

www.safework.nsw.gov.au/data/assets/pdf_file/0008/52883/Overhead-protective-structures-Code-of-practice.pdf

All Hoardings

Security fencing, hoarding and overhead protective structure must not obstruct access to utilities services including but not limited to man holes, pits, stop valves, fire hydrants or the like.

Hoardings on Public Land including ‘Creative Hoardings’

The Principal Contractor or Owner-builder must pay all fees associated with the application and occupation and use of the road (footway) for required hoarding or overhead protection. A creative hoarding (i.e. an approved artwork or historic image affixed to the hoarding) is required if the hoarding meets the criteria in Council’s Creative Hoardings Policy (adopted March 2020). The cost of printing and affixing the creative hoarding is the responsibility of the Principal Contractor or Owner-builder. The Creative Hoardings Policy can be downloaded from Council’s website www.woollahra.nsw.gov.au

Note: The Principal Contractor or Owner must allow not less than two (2) weeks from the date of making a hoarding application for determination. Any approval for a hoarding or overhead protection under the *Roads Act 1993* will be subject to its own conditions and fees.

Note: Council seeks to increase public art in the public domain by requiring artwork or historic images on hoardings located on public land. Under the Creative Hoardings Policy an application for a hoarding proposed on public land will require an approved artwork or historic image affixed to the hoarding if the hoarding meets the criteria in section 3 of the Policy:

- A. Hoardings proposed on land zoned B2 Local Centre, or B4 Mixed Use, or SP2 Infrastructure under Woollahra Local Environmental Plan 2014 AND erected for 8 weeks or more
OR
- B. Hoardings proposed on land located along a State classified road (regardless of the zone) AND erected for 8 weeks or more
OR
- C. Hoardings proposed in any other location than that referred to in A. and B. above AND erected for 12 weeks or more, except where:

- i. the capital investment value of the work to which the hoarding relates is less than \$1 million
- OR
- ii. the land is zoned R2 Low Density Residential
- OR
- iii. the land is zoned R3 Medium Density Residential and the hoarding located in a lane or street that does not have through traffic (eg a cul-de-sac or no through road).

Artwork and historic images for the hoardings are assessed and approved in accordance with the Creative Hoardings Policy. Details of the artwork or images proposed to be affixed to the hoardings must be submitted with Council's form "Application for a permit to use a footpath for the erection of a hoarding/scaffolding".

The Creative Hoardings Policy can be downloaded from www.woollahra.nsw.gov.au or for more information contact Council's Cultural Development Team.
Standard Condition: D11 (Autotext DD11)

D.7 Site Signs

The Principal Contractor or Owner-builder must ensure that the sign/s required by clauses 98A and 227A of the *Regulation* is/are erected and maintained at all times.

Clause 98A of the *Regulation* provides:

Erection of signs

- For the purposes of section 4.17(11) of the *Act*, the requirements of subclauses (2) and (3) are prescribed as conditions of a development consent for development that involves any building work, subdivision work or demolition work.
- A sign must be erected in a prominent position on any site on which building work, subdivision work or demolition work is being carried out:
 - a. showing the name, address and telephone number of the Principal Certifier for the work, and
 - b. showing the name of the principal contractor (if any) for any building work and a telephone number on which that person may be contacted outside working hours, and
 - c. stating that unauthorised entry to the work site is prohibited.
- Any such sign is to be maintained while the building work, subdivision work or demolition work is being carried out, but must be removed when the work has been completed.
- This clause does not apply in relation to building work, subdivision work or demolition work that is carried out inside an existing building that does not affect the external walls of the building.
- This clause does not apply in relation to Crown building work that is certified, in accordance with section 6.28 of the *Act*, to comply with the Building Code of Australia.

Clause 227A of the *Regulation* provides:

Signs on development sites

If there is a person who is the Principal Certifier or the Principal Contractor for any building work, subdivision work or demolition work authorised to be carried out on a site by a development consent or complying development certificate:

- Each such person MUST ensure that a rigid and durable sign showing the person's identifying particulars so that they can be read easily by anyone in any public road or other public place adjacent to the site is erected in a prominent position on the site before the commencement of work, and is maintained on the site at all times while this clause applies until the work has been carried out.

Note: Clause 227A imposes a penalty exceeding \$1,000 if these requirements are not complied with.
Note: If Council is appointed as the Principal Certifier it will provide the sign to the Principal Contractor or Owner-builder who must ensure that the sign is erected and maintained as required by clause 98A and clause 227A of the *Regulation*.
Standard Condition: D12 (Autotext DD12)

D.8 Toilet Facilities

Toilet facilities are to be provided, at or in the vicinity of the work site on which work involved in the erection or demolition of a building is being carried out, at the rate of one toilet for every 20 persons or part of 20 persons employed at the site.

Each toilet provided:

- a) must be a standard flushing toilet, and
- b) must be connected to a public sewer, or
- c) if connection to a public sewer is not practicable, to an accredited sewage management facility approved by the Council, or
- d) if connection to a public sewer or an accredited sewage management facility is not practicable, to some other sewage management facility approved by the Council.

The provision of toilet facilities in accordance with this condition must be completed before any other work is commenced.

In this condition:

accredited sewage management facility means a sewage management facility to which Division 4A of Part 3 of the *Local Government (Approvals) Regulation 1993* applies, being a sewage management facility that is installed or constructed to a design or plan the subject of a certificate of accreditation referred to in clause 95B of the *Local Government (Approvals) Regulation 1993*.

approved by the Council means the subject of an approval in force under Division 1 of Part 3 of the *Local Government (Approvals) Regulation 1993*.

public sewer has the same meaning as it has in the *Local Government (Approvals) Regulation 1993*.

sewage management facility has the same meaning as it has in the *Local Government (Approvals) Regulation 1993*.

Note: This condition does not set aside the requirement to comply with SafeWork NSW requirements.
Standard Condition: D13 (Autotext DD13)

D.9 Erosion and Sediment Controls – Installation

The Principal Contractor or Owner-builder must install and maintain water pollution, erosion and sedimentation controls in accordance with:

- a) The Soil and Water Management Plan if required under this consent;
- b) “*Do it Right On Site, Soil and Water Management for the Construction Industry*” published by the Southern Sydney Regional Organisation of Councils, 2001; and
- c) “*Managing Urban Stormwater - Soils and Construction*” 2004 published by the NSW Government (*The Blue Book*).

Where there is any conflict *The Blue Book* takes precedence.

Note: The International Erosion Control Association – Australasia (www.austieca.com.au/) lists consultant experts who can assist in ensuring compliance with this condition. Where Soil and Water Management Plan is required for larger projects it is recommended that this be produced by a member of the International Erosion Control Association – Australasia.

Note: The “Do it Right On Site, Soil and Water Management for the Construction Industry” publication can be downloaded from www.woollahra.nsw.gov.au and *The Blue Book* is available at www.environment.nsw.gov.au/stormwater/publications.htm

Note: A failure to comply with this condition may result in penalty infringement notices, prosecution, notices and orders under the *Act* and/or the *Protection of the Environment Operations Act 1997* **without any further warning**. It is a criminal offence to cause, permit or allow pollution.

Note: Section 257 of the *Protection of the Environment Operations Act 1997* provides inter alia that “the occupier of premises at or from which any pollution occurs is taken to have caused the pollution”

Warning: Irrespective of this condition any person occupying the site may be subject to proceedings under the *Protection of the Environment Operations Act 1997* where pollution is caused, permitted or allowed as the result of their occupation of the land being developed.
Standard Condition: D14 (Autotext DD14)

D.10 Building - Construction Certificate, Appointment of Principal Certifier, Appointment of Principal Contractor and Notice of Commencement (Part 6, Division 6.3 of the Act)

The erection of the building in accordance with this development consent must not be commenced until:

- a) A Construction Certificate for the building work has been issued by the consent authority, the Council (if the Council is not the consent authority) or an accredited Certifier, and
- b) The person having the benefit of the development consent has:
 - appointed a Principal Certifier for the building work, and
 - notified the Principal Certifier that the person will carry out the building work as an Owner-builder, if that is the case, and
- c) The Principal Certifier has, no later than 2 days before the building work commences:
 - notified the consent authority and the Council (if the Council is not the consent authority) of his or her appointment, and
 - notified the person having the benefit of the development consent of any critical stage inspections and other inspections that are to be carried out in respect of the building work, and
- d) The person having the benefit of the development consent, if not carrying out the work as an Owner-builder, has:
 - appointed a Principal Contractor for the building work who must be the holder of a contractor licence if any residential building work is involved, and
 - notified the Principal Certifier of any such appointment, and
 - unless that person is the Principal Contractor, notified the Principal Contractor of any critical stage inspections and other inspections that are to be carried out in respect of the building work, and
 - given at least 2 days' notice to the Council of the person's intention to commence the erection of the building.

Note: *building* has the same meaning as in section 1.4 of the *Act* and includes part of a building and any structure or part of a structure.

Note: *new building* has the same meaning as in section 6.1 of the *Act* and includes an altered portion of, or an extension to, an existing building.

Note: The commencement of demolition works associated with an altered portion of, or an extension to, an existing building is considered to be the commencement of building work requiring compliance with section 6.6(2) of the *Act* (including the need for a Construction Certificate) prior to any demolition work. See: *Over our Dead Body Society Inc v Byron Bay Community Association Inc* [2001] NSWLEC 125.

Note: Construction Certificate Application, PC Service Agreement and Notice of Commencement forms can be downloaded from Council's website www.woollahra.nsw.gov.au

Note: It is an offence for any person to carry out the erection of a *building* in breach of this condition and in breach of section 6.6(2) of the *Act*.

Standard Condition: D15 (Autotext DD15)

D.11 Notification of Home Building Act 1989 requirements

- a) For the purposes of section 4.17(11) of the *Act*, the requirements of this condition are prescribed as conditions of a development consent for development that involves any residential building work within the meaning of the *Home Building Act 1989*.
- b) Residential building work within the meaning of the *Home Building Act 1989* must not be carried out unless the Principal Certifier for the development to which the work relates (not being the Council) has given the Council written notice of the following information:
 - In the case of work for which a Principal Contractor is required to be appointed:

- the name and licence number of the Principal Contractor, and
 - the name of the insurer by which the work is insured under Part 6 of that Act,
 - In the case of work to be done by an Owner-builder:
 - the name of the Owner-builder, and
 - if the Owner-builder is required to hold an Owner-builder permit under that Act, the number of the Owner-builder permit.
- c) If arrangements for doing the residential building work are changed while the work is in progress so that the information notified under subclause (2) becomes out of date, further work must not be carried out unless the Principal Certifier for the development to which the work relates (not being the Council) has given the Council written notice of the updated information.
- d) This clause does not apply in relation to Crown building work that is certified, in accordance with section 6.28 of the *Act*, to comply with the Building Code of Australia.
Standard Condition: D17 (Autotext DD17)

D.12 Notice of Completion of Category 1 Remediation Work

On the completion of the remediation work, and before any building work commences, and as required under clause 4.14 of State Environmental Planning Policy (Resilience and Hazards) 2021, notice of completion of a category 1 remediation work must be given to the Council within 30 days after the completion of the work. This notice must be in accordance with clause 4.15 of State Environmental Planning Policy (Resilience and Hazards) 2021

Notes:

- **Category 1 remediation work** is defined in clause 4.8 of State Environmental Planning Policy (Resilience and Hazards) 2021.

This condition has been imposed to ensure a notice of completion of a category 1 remediation work is provided.

E. Conditions which must be satisfied during any development work

E.1 Compliance with BCA and Insurance Requirements under the *Home Building Act 1989*

For the purposes of section 4.17(11) of the *Act*, the following condition is prescribed in relation to a development consent for development that involves any building work:

- a) that the work must be carried out in accordance with the requirements of the Building Code of Australia (BCA),
- b) in the case of residential building work for which the *Home Building Act 1989* requires there to be a contract of insurance in force in accordance with Part 6 of that Act, that such a contract of insurance is in force before any building work authorised to be carried out by the consent commences.

This condition does not apply:

- a) to the extent to which an exemption is in force under clause 187 or 188, subject to the terms of any condition or requirement referred to in clause 187 (6) or 188 (4) of the *Regulation*, or
- b) to the erection of a temporary building.

In this clause, a reference to the BCA is a reference to that Code as in force on the date the application for the relevant Construction Certificate is made.

Note: All new guttering is to comply with the provisions of Part 3.5.2 of the Building Code of Australia.
Standard Condition: E1 (Autotext EE1)

E.2 Compliance with Australian Standard for Demolition

Demolition of buildings and structures must comply with Australian Standard AS 2601—2001: *The Demolition of Structures*.

Standard Condition: E2 (Autotext EE2)

E.3 Compliance with Construction Management Plan

All development activities and traffic movements must be carried out in accordance with the approved Construction Management Plan (CMP). All controls in the CMP must be maintained at all times. A copy of the CMP must be kept on-site at all times and made available to the Principal Certifier or Council on request.

Note: Irrespective of the provisions of the Construction Management Plan the provisions of traffic and parking legislation prevails.

Standard Condition: E3 (Autotext EE3)

E.4 Requirement to Notify about New Evidence

Any new information which comes to light during remediation, demolition or construction works which has the potential to alter previous conclusions about site contamination, heritage significance, threatened species or other relevant matters must be immediately notified to Council and the Principal Certifier.

Standard Condition: E4 (Autotext EE4)

E.5 Critical Stage Inspections

Critical stage inspections must be called for by the Principal Contractor or Owner-builder as required by the Principal Certifier, any PC service agreement, the *Act* and the *Regulation*.

Work must not proceed beyond each critical stage until the Principal Certifier is satisfied that work is proceeding in accordance with this consent, the Construction Certificate(s) and the *Act*.

Critical stage inspections means the inspections prescribed by the *Regulations* for the purposes of section 6.5 of the *Act* or as required by the Principal Certifier and any PC Service Agreement.

Note: The PC may require inspections beyond mandatory critical stage inspections in order that the PC be satisfied that work is proceeding in accordance with this consent.

Note: The PC may, in addition to inspections, require the submission of Compliance Certificates, survey reports or evidence of suitability in accordance with Part A2.2 of the BCA in relation to any matter relevant to the development.

Standard Condition: E5 (Autotext EE5)

E.6 Hours of Work –Amenity of the Neighbourhood

- a) No *work* must take place on any Sunday or public holiday.
- b) No *work* must take place before 7am or after 5pm any weekday.
- c) No *work* must take place before 7am or after 1pm any Saturday.
- d) The following *work* **must not** take place before 9am or after 4pm any weekday, or before 9am or after 1pm any Saturday or at any time on a Sunday or public holiday:
 - (i) piling,
 - (ii) piercing,
 - (iii) rock or concrete cutting, boring or drilling,
 - (iv) rock breaking,
 - (v) rock sawing,
 - (vi) jack hammering, or
 - (vii) machine excavation.

- e) No loading or unloading of material or equipment associated with the activities listed in part d) above must take place before 9am or after 4pm any weekday, or before 9am or after 1pm any Saturday or at any time on a Sunday or public holiday.
- f) No operation of any equipment associated with the activities listed in part d) above must take place before 9am or after 4pm any weekday, or before 9am or after 1pm any Saturday or at any time on a Sunday or public holiday.
- g) No rock excavation being cutting, boring, drilling, breaking, sawing, jack hammering or bulk excavation of rock, must occur without a 15 minute break every hour.

This condition has been imposed to mitigate the impact of work upon the amenity of the neighbourhood. Impact of work includes, but is not limited to, noise, vibration, dust, odour, traffic and parking impacts.

Note: The use of noise and vibration generating plant and equipment and vehicular traffic, including trucks in particular, significantly degrade the amenity of neighbourhoods and more onerous restrictions apply to these activities. This more invasive work generally occurs during the foundation and bulk excavation stages of development. If you are in doubt as to whether or not a particular activity is considered to be subject to the more onerous requirement (9am to 4pm weekdays and 9am to 1pm Saturdays) please consult with Council.

Note: Each and every breach of this condition by any person may be subject to a separate penalty infringement notice or prosecution.

Note: The delivery and removal of plant, equipment and machinery associated with wide loads subject to RMS and NSW Police restrictions on their movement outside the approved hours of work will be considered on a case by case basis.

Note: Compliance with these hours of work does not affect the rights of any person to seek a remedy to offensive noise as defined by the *Protection of the Environment Operations Act 1997*, the *Protection of the Environment Operations (Noise Control) Regulation 2017*.

Note: NSW EPA Noise Guide is available at www.epa.nsw.gov.au/noise/nqlg.htm
Standard Condition: E6 (Autotext EE6)

E.7 Public Footpaths – Safety, Access and Maintenance

The Principal Contractor or Owner-builder and any other person acting with the benefit of this consent must:

- a) Not erect or maintain any gate or fence swing out or encroaching upon the road or the footway.
- b) Not use the road or footway for the storage of any article, material, matter, waste or thing.
- c) Not use the road or footway for any *work*.
- d) Keep the road and footway in good repair free of any trip hazard or obstruction.
- e) Not stand any plant and equipment upon the road or footway.
- f) Provide a clear safe pedestrian route a minimum of 1.5m wide.
- g) Protect heritage listed street name inlays in the footpath which are not to be removed or damaged during development.

This condition does not apply to the extent that a permit or approval exists under the section 148B of the *Road Transport Act 2013*, section 138 of the *Roads Act 1993* or section 68 of the *Local Government Act 1993* except that at all time compliance is required with:

- a) Australian Standard AS 1742 (Set): *Manual of uniform traffic control devices* and all relevant parts of this set of standards.
- b) Australian Road Rules.

Note: Section 73 of the *Road Transport (Safety and Traffic Management) Act 1999* allows the NSW Police to close any road or road related area to traffic during any temporary obstruction or danger to traffic or for any temporary purpose.

Note: Section 138 of the *Roads Act 1993* provides that a person must not:

- erect a structure or carry out a work in, on or over a public road, or
- dig up or disturb the surface of a public road, or
- remove or interfere with a structure, work or tree on a public road, or
- pump water into a public road from any land adjoining the road, or

- connect a road (whether public or private) to a classified road, otherwise than with the consent of the appropriate roads authority.

Note: Section 68 of the *Local Government Act 1993* provides that a person may carry out certain activities only with the prior approval of the Council including:

- Part C Management of waste:
 - a. For fee or reward, transport waste over or under a public place
 - b. Place waste in a public place
 - c. Place a waste storage container in a public place.
- Part E Public roads:
 - a. Swing or hoist goods across or over any part of a public road by means of a lift, hoist or tackle projecting over the footway
 - b. Expose or allow to be exposed (whether for sale or otherwise) any article in or on or so as to overhang any part of the road or outside a shop window or doorway abutting the road, or hang an article beneath an awning over the road.
Standard Condition: E7 (Autotext EE7)

E.8 Tree Preservation

All persons must comply with the Woollahra DCP 2015, Chapter E3–Tree Management, other than where varied by this consent.

The DCP applies to any tree, with a height greater than 5 metres or a diameter spread of branches greater than 3 metres unless exempted by specific provisions. Works to be carried out within a 5 metre radius of any tree subject to the DCP require the prior written consent of Council.

General Protection Requirements

- a) There must be no excavation or *work* within the required Tree Protection Zone(s). The Tree Protection Zone(s) must be maintained during all development work.
- b) Where excavation encounters tree roots with a diameter exceeding 40mm excavation must cease. The Principal Contractor must procure an inspection of the tree roots exposed by a qualified arborist. Excavation must only recommence with the implementation of the recommendations of the qualified arborist or where specific instructions are given by Council's Tree Management Officer in strict accordance with such Council instructions.
- c) Where there is damage to any part of a tree the Principal Contractor must procure an inspection of the tree by a qualified arborist immediately. The Principal Contractor must immediately implement treatment as directed by the qualified arborist or where specific instructions are given by Council's Tree Management Officer in strict accordance with such Council instructions.

Note: Trees must be pruned in accordance with Australian Standard AS 4373 – 2007: *Pruning of Amenity Trees* and SafeWork NSW *Code of Practice: Amenity Tree Industry 1998*.
Standard Condition: E8 (Autotext EE8)

E.9 Maintenance of Environmental Controls

The Principal Contractor or Owner-builder must ensure that the following monitoring, measures and controls are maintained:

- a) erosion and sediment controls,
- b) dust controls,
- c) dewatering discharges,
- d) noise controls,
- e) vibration monitoring and controls,
- f) ablutions.

Standard Condition: E11

E.10 Support of Adjoining Land and Buildings

A person must not do anything on or in relation to the site (the supporting land) that removes the support provided by the supporting land to any other land (the supported land) or building (the supported building).

For the purposes of this condition, supporting land includes the natural surface of the site, the subsoil of the site, any water beneath the site, and any part of the site that has been reclaimed.

Note: This condition does not authorise any trespass or encroachment upon any adjoining or supported land or building whether private or public. Where any underpinning, shoring, soil anchoring (temporary or permanent) or the like is considered necessary upon any adjoining or supported land by any person the Principal Contractor or Owner-builder must obtain:

- the consent of the owners of such adjoining or supported land to trespass or encroach, or
- an access order under the *Access to Neighbouring Land Act 2000*, or
- an easement under section 88K of the *Conveyancing Act 1919*, or
- an easement under section 40 of the *Land and Environment Court Act 1979* as appropriate.

Note: Section 177 of the *Conveyancing Act 1919* creates a statutory duty of care in relation to support of land. Accordingly, a person has a duty of care not to do anything on or in relation to land being developed (the supporting land) that removes the support provided by the supporting land to any other adjoining land (the supported land).

Note: Clause 20 of the *Roads Regulation 2008* prohibits excavation in the vicinity of roads as follows: **“Excavations adjacent to road** - A person must not excavate land in the vicinity of a road if the excavation is capable of causing damage to the road (such as by way of subsidence) or to any work or structure on the road.” Separate approval is required under the *Roads Act 1993* for any underpinning, shoring, soil anchoring (temporary) or the like within or under any road. Council will not give approval to permanent underpinning, shoring, soil anchoring within or under any road.

Note: The encroachment of work or the like is a civil matter of trespass or encroachment and Council does not adjudicate or regulate such trespasses or encroachments except in relation to encroachments upon any road, public place, Crown land under Council’s care control or management, or any community or operational land as defined by the *Local Government Act 1993*.

Standard Condition: E13 (Autotext EE13)

E.11 Erosion and Sediment Controls – Maintenance

The Principal Contractor or Owner-builder must maintain water pollution, erosion and sedimentation controls in accordance with:

- the Soil and Water Management Plan required under this consent,
- “*Do it Right On Site, Soil and Water Management for the Construction Industry*” published by the Southern Sydney Regional Organisation of Councils, 2001, and
- “*Managing Urban Stormwater - Soils and Construction*” 2004 published by the NSW Government (*The Blue Book*).

Where there is any conflict *The Blue Book* takes precedence



Note: A failure to comply with this condition may result in penalty infringement notices, prosecution, notices and orders under the *Act* and/or the *Protection of the Environment Operations Act 1997* without any further warning. It is a criminal offence to cause, permit or allow pollution.

Note: Section 257 of the *Protection of the Environment Operations Act 1997* provides that “the occupier of premises at or from which any pollution occurs is taken to have caused the pollution”.

Warning: Irrespective of this condition any person occupying the site may be subject to proceedings under the *Protection of the Environment Operations Act 1997* where pollution is caused, permitted or allowed as the result of the occupation of the land being developed whether or not they actually cause the pollution.

Standard Condition: E15 (Autotext EE15)

E.12 Disposal of Site Water During Construction

The Principal Contractor or Owner-builder must ensure:

- a) Prior to pumping any water into the road or public stormwater system that approval is obtained from Council under section 138(1)(d) of the *Roads Act 1993*.
- b) That *water pollution*, as defined by the *Protection of the Environment Operations Act 1997*, does not occur as the result of the discharge to the road, public stormwater system or other place or any site water.
- c) That stormwater from any roof or other impervious areas is linked, via temporary downpipes and stormwater pipes, to a Council approved stormwater disposal system immediately upon completion of the roof installation or work creating other impervious areas.

Note: This condition has been imposed to ensure that adjoining and neighbouring land is not adversely affected by unreasonable overland flows of stormwater and that site water does not concentrate water such that they cause erosion and water pollution.

Standard Condition: E17 (Autotext EE17)

E.13 Check Surveys - boundary location, building location, building height, stormwater drainage system and flood protection measures relative to Australian Height Datum

The Principal Contractor or Owner-builder must ensure that a registered surveyor carries out check surveys and provides survey certificates confirming the location of the building(s), ancillary works, flood protection works and the stormwater drainage system relative to the boundaries of the site and that the height of buildings, ancillary works, flood protection works and the stormwater drainage system relative to Australian Height Datum complies with this consent at the following critical stages.

The Principal Contractor or Owner-builder must ensure that work must not proceed beyond each of the following critical stages until compliance has been demonstrated to the Principal Certifier's satisfaction:

- a) Upon the completion of foundation walls prior to the laying of any floor or the pouring of any floor slab and generally at damp proof course level.
- b) Upon the completion of formwork for floor slabs prior to the laying of any floor or the pouring of any concrete and generally at each storey.
- c) Upon the completion of formwork or framework for the roof(s) prior to the laying of any roofing or the pouring of any concrete roof.
- d) Upon the completion of formwork and steel fixing prior to pouring of any concrete for any ancillary structure, flood protection work, swimming pool or spa pool or the like.
- e) Upon the completion of formwork and steel fixing prior to pouring of any concrete for driveways showing transitions and crest thresholds confirming that driveway levels match Council approved driveway crossing levels and minimum flood levels.
- f) Stormwater drainage Systems prior to back filling over pipes confirming location, height and capacity of works.
- g) Flood protection measures are in place confirming location, height and capacity.

Note: This condition has been imposed to ensure that development occurs in the location and at the height approved under this consent. This is critical to ensure that buildings are constructed to minimum heights for flood protection and maximum heights to protect views and the amenity of neighbours.

Standard Condition: E20 (Autotext EE20)

E.14 Placement and Use of Skip Bins

The Principal Contractor or Owner-builder must ensure that all waste storage containers, including but not limited to skip bins, must be stored within the site unless:

- a) Activity Approval has been issued by Council under section 68 of the *Local Government Act 1993* to place the waste storage container in a public place; and
- b) where located on the road it is located only in a position where a vehicle may lawfully park in accordance with the Australian Road Rules.

Note: Waste storage containers must not be located on the footpath without a site specific activity approval. Where such site specific activity approval is granted a 1.5m wide clear path of travel is maintained free of any trip hazards.

Standard Condition: E21 (Autotext EE21)

E.15 Prohibition of Burning

There must be no burning of any waste or other materials. The burning of copper chrome arsenate (CCA) or pentachlorophenol (PCP) treated timber is prohibited in all parts of NSW.

All burning is prohibited in the Woollahra local government area.

Note: Pursuant to the *Protection of the Environment Operations (Clean Air) Regulation 2010* all burning (including burning of vegetation and domestic waste) is prohibited except with approval. No approval is granted under this consent for any burning.

Standard Condition: E22 (Autotext EE22)

E.16 Dust Mitigation

Dust mitigation must be implemented in accordance with "*Dust Control - Do it right on site*" published by the Southern Sydney Regional Organisation of Councils.

This generally requires:

- a) Dust screens to all hoardings and site fences.
- b) All stockpiles or loose materials to be covered when not being used.
- c) All equipment, where capable, being fitted with dust catchers.
- d) All loose materials being placed in bags before placing into waste or skip bins.
- e) All waste and skip bins being kept covered when not being filled or emptied.
- f) The surface of excavation work being kept wet to minimise dust.
- g) Landscaping incorporating trees, dense shrubs and grass being implemented as soon as practically possible to minimise dust.

Note: "*Dust Control - Do it right on site*" can be downloaded from Council's website www.woollahra.nsw.gov.au or obtained from Council's office.

Note: Special precautions must be taken when removing asbestos or lead materials from development sites. Additional information can be obtained from www.safework.nsw.gov.au and www.epa.nsw.gov.au. Other specific conditions and advice may apply.

Note: Demolition and construction activities may affect local air quality and contribute to urban air pollution. The causes are dust, smoke and fumes coming from equipment or activities, and airborne chemicals when spraying for pest management. Precautions must be taken to prevent air pollution.

Standard Condition: E23 (Autotext EE23)

E.17 Site Waste Minimisation and Management – Demolition

In order to maximise resource recovery and minimise residual waste from demolition activities:

- a) the provisions of the Site Waste Minimisation and Management Plan (SWMMP) are to be implemented at all times during the course of the work,
- b) an area is to be allocated for the storage of materials for use, recycling and disposal (giving consideration to slope, drainage, location of waterways, stormwater outlets, vegetation and access and handling requirements),
- c) provide separate collection bins and/or areas for the storage of residual waste,
- d) clearly 'signpost' the purpose and content of the bins and/or storage areas,
- e) implement measures to prevent damage by the elements, odour, health risks and windborne litter, and
- f) minimise site disturbance, limiting unnecessary excavation.

When implementing the SWMMP the Applicant must ensure:

- a) footpaths, public reserves and street gutters are not used as places to store demolition waste or materials of any kind without Council approval,
- b) any material moved offsite is transported in accordance with the requirements of the *Protection of the Environment Operations Act 1997*,
- c) waste is only transported to a place that can lawfully be used as a waste facility,
- d) generation, storage, treatment and disposal of hazardous waste and special waste (including asbestos) is conducted in accordance with relevant waste legislation administered by the NSW Environment Protection Authority, and relevant occupational health and safety legislation administered by SafeWork NSW, and
- e) evidence such as weighbridge dockets and invoices for waste disposal or recycling services are retained.

Note: Materials that have an existing reuse or recycling market should not be disposed of in a land fill. Reuse and recycling opportunities are decreased when asbestos is not carefully removed and segregated from other waste streams.

Standard Condition: E31 (Autotext EE31)

E.18 Site Waste Minimisation and Management – Construction

In order to maximise resource recovery and minimise residual waste from construction activities:

- a) the provisions of the Site Waste Minimisation and Management Plan (SWMMP) are to be implemented at all times during the course of the work,
- b) arrange for the delivery of materials so that materials are delivered 'as needed' to prevent the degradation of materials through weathering and moisture damage,
- c) consider organising to return excess materials to the supplier or manufacturer,
- d) allocate an area for the storage of materials for use, recycling and disposal (considering slope, drainage, location of waterways, stormwater outlets and vegetation),
- e) clearly 'signpost' the purpose and content of the storage areas,
- f) arrange contractors for the transport, processing and disposal of waste and recycling and ensure that all contractors are aware of the legal requirements for disposing of waste,
- g) promote separate collection bins or areas for the storage of residual waste,
- h) implement measures to prevent damage by the elements, odour and health risks, and windborne litter,
- i) minimise site disturbance and limit unnecessary excavation,
- j) ensure that all waste is transported to a place that can lawfully be used as a waste facility, and

- k) retain all records demonstrating lawful disposal of waste and keep them readily accessible for inspection by regulatory authorities such as Council, the NSW EPA or SafeWork NSW.

Standard Condition: E32 (Autotext EE32)

E.19 Asbestos Removal

All asbestos removal work must be carried out safely according to NSW work health and safety legislation.

Where hazardous material, including bonded or friable asbestos has been identified in accordance with the conditions in Section B above, and such material must be demolished, disturbed and subsequently removed, all such works must comply with the following criteria:

- a) Be undertaken by contractors who hold a current SafeWork NSW "demolition licence" and a current SafeWork NSW "Class A licence" for friable asbestos removal.
- b) Be carried out in accordance with the relevant SafeWork NSW codes of practice.
- c) No asbestos products may be reused on the site.
- d) No asbestos laden skip or bins shall be left in any public place.

Note: This condition is imposed to protect the health and safety of persons working on the site and the public

Standard Condition: E39

E.20 Classification of Hazardous Waste

Prior to the exportation of hazardous waste (including hazardous fill or soil) from the site, the waste materials must be classified in accordance with the provision of the *Protection of the Environment Operations Act 1997* and the NSW EPA *Waste Classification Guidelines, Part 1: Classifying Waste, 2014*.

Note: This condition is imposed to ensure that where hazardous waste will be removed from a site an asbestos licensed contractor can definitively determine where the waste may be legally taken for disposal.

Standard Condition: E40

E.21 Disposal of Asbestos and Hazardous Waste

Asbestos and hazardous waste, once classified in accordance with the hazardous waste classification condition above must only be transported to waste facilities licensed to accept asbestos and appropriate classifications of hazardous waste.

Note: This condition is imposed to ensure that asbestos and other hazardous waste is disposed of lawfully under the *Protection of the Environment Operations Act 1997* and relevant NSW EPA requirements.

Standard Condition: E41

E.22 Asbestos Removal Signage

Standard commercially manufactured signs containing the words "DANGER ASBESTOS REMOVAL IN PROGRESS" measuring not less than 400mm x 300mm are to be erected in prominent visible positions on the site when asbestos is being removed.

Note: This condition is imposed to ensure awareness of any hazard to the health and safety of persons working on the site and public.

Standard Condition: E42

E.23 Notification of Asbestos Removal

In addition to the requirements for licensed asbestos removalists to give written notice to SafeWork NSW all adjoining properties and those opposite the development site must be notified in writing of the dates and times when asbestos removal is to be conducted.

The notification is to identify the licensed asbestos removal contractor and include a contact person for the site together with telephone and facsimile numbers and email addresses.

Note: This condition has been imposed to ensure that local residents are informed and have adequate communication facilitated for incidents of asbestos removal.
Standard Condition: E43

E.24 Food Premises – Construction and Fitout

The Principal Contractor or Owner-builder must ensure that all construction and fitout of the food premises complies with the details for the food premises submitted to and considered satisfactory by Council's Environmental Health Officer but no less compliant than with the *Food Act 2003*, *Food Regulation 2015*, the *Food Standards Code* as published by Food Standards Australia and New Zealand and AS 4674-2004: *Construction and fit out of food premises*.

This condition has been imposed to protect public health and ensure that food premises are easily maintained in a clean condition fit for food preparation and consumption.
Standard Condition: E29 (Autotext EE29)

F. Conditions which must be satisfied prior to any occupation or use of the building (Part 6 of the Act and Part 8 Division 3 of the Regulation)

F.1 Occupation Certificate (section 6.9 of the Act)

A person must not commence occupation or use of the whole or any part of a new building (within the meaning of section 6.10 of the *Act*) unless an Occupation Certificate has been issued in relation to the building or part.

Note: New building includes an altered portion of, or an extension to, an existing building.
Standard Condition: F1 (Autotext FF1)

F.2 Commissioning and Certification of Systems and Works

The Principal Contractor or Owner-builder must submit to the satisfaction of the Principal Certifier works-as-executed (WAE) plans, Compliance Certificates and evidence of suitability in accordance with Part A2.2 of the BCA confirming that the works, as executed and as detailed, comply with the requirement of this consent, the *Act*, the *Regulations*, any relevant construction certificate, the BCA and relevant Australian Standards.

Works-as-executed plans, Compliance Certificates and evidence of suitability in accordance with Part A2.2 of the BCA must include but may not be limited to:

- a) Certification from the supervising professional engineer that the requirement of the Geotechnical/Hydrogeological conditions and report recommendations were implemented and satisfied during development work.
- b) All flood protection measures.
- c) All garage/car park/basement car park, driveways and access ramps comply with Australian Standard AS 2890.1: *Off-Street car parking*.
- d) All stormwater drainage and storage systems.
- e) All mechanical ventilation systems.
- f) All hydraulic systems.
- g) All structural work.
- h) All acoustic attenuation work.

- i) All waterproofing.
- j) Such further matters as the Principal Certifier may require.

Note: This condition has been imposed to ensure that systems and works as completed meet development standards as defined by the *Act*, comply with the BCA, comply with this consent and so that a public record of works as execute is maintained.

Note: The PC may require any number of WAE plans, certificates, or other evidence of suitability as necessary to confirm compliance with the *Act*, *Regulation*, development standards, BCA, and relevant Australia Standards. As a minimum WAE plans and certification is required for stormwater drainage and detention, mechanical ventilation work, hydraulic services (including but not limited to fire services).

Note: The PC must submit to Council, with any Occupation Certificate, copies of WAE plans, Compliance Certificates and evidence of suitability in accordance with Part A2.2 of the BCA upon which the PC has relied in issuing any Occupation Certificate.
Standard Condition: F7 (Autotext FF7)

F.3 Fire Safety Certificates

In the case of a ***final occupation certificate*** to authorise a person:

- a) to commence occupation or use of a new building, or
- b) to commence a change of building use for an existing building,

a *certifying authority* must be satisfied that a final fire safety certificate has been issued for the building.

In the case of an ***interim occupation certificate*** to authorise a person:

- a) to commence occupation or use of a partially completed *new building*, or
- b) to commence a change of building use for part of an existing building,

a *certifying authority* must be satisfied that a final fire safety certificate or an interim fire safety certificate has been issued for the relevant part of the building.

F.4 Food Premises - Inspection and Registration

Prior to the issue of any *Occupation Certificate* or occupation or use of any food premises:

- a) The *Principal Contractor* or *owner* must arrange an inspection of the fit out of the Food Premises by Council's Environmental Health Officer;
- b) A satisfactory final inspection must have been undertaken by Council's Environmental Health Officer; and
- c) The *owner* or *occupier* must have registered the Food Premises (Notification of conduct under section 100 of the *Food Act* 2003).

Note: Notification can be done on-line [at www.foodnotify.nsw.gov.au](http://www.foodnotify.nsw.gov.au)

Note: Inspections are subject to payment of the adopted inspection fee.

Note: Section 100 of the *Food Act* 2003 requires:

“100 Notification of conduct of food businesses

(1) The proprietor of a food business must not conduct the food business unless the proprietor has given written notice, in the approved form, of the information specified in the Food Safety Standards that is to be notified to the appropriate enforcement agency before the business is conducted. Maximum penalty: 500 penalty units in the case of an individual and 2,500 penalty units in the case of a corporation.”

Note: *Accredited Certifiers* are unable to issue *Compliance Certificates* in relation to compliance with the *Food Act* 2003, *Food Regulation* 2015; the Food Standards Code and the Australian Standard AS 4674-2004: *Construction and fit out of food premises*; since these are not matters which an *Accredited Certifier* can be satisfied in relation to under Clause 161 of the *Regulation*. This condition can only be satisfied following an inspection and sign off from Council's Environmental Health Officers. Standard Condition: F15

F.5 Maintenance of the Kitchen Exhaust

The proprietor(s) of the subject site shall enter into a contract agreement for the regular maintenance and cleaning of the odour control units and filtering systems. A copy of the contract agreement shall be made available to Council's Health Services Section prior to the occupation of the building.

G. Conditions which must be satisfied prior to the issue of any Subdivision Certificate

Nil.

H. Conditions which must be satisfied prior to the issue of the Occupation Certificate for the whole of the building

H.1 Removal of Ancillary Works and Structures

The Principal Contractor or Owner must remove from the land and any adjoining public place:

- a) the site sign,
- b) ablutions,
- c) hoarding,
- d) scaffolding, and
- e) waste materials, matter, article or thing.

Note: This condition has been imposed to ensure that all ancillary matter is removed prior to the issue of the Final Occupation Certificate.
Standard Condition: H12 (Autotext HH12)

H.2 Road Works (including footpaths)

The following works must be completed to the satisfaction of Council, in compliance with Council's *Specification for Roadworks, Drainage and Miscellaneous Works (2012)* unless expressly provided otherwise by these conditions at the Principal Contractor's or Owner's expense:

- a) stormwater pipes, pits and connections to public stormwater systems within the *road*,
- b) driveways and vehicular crossings within the *road*,
- c) removal of redundant driveways and vehicular crossings,
- d) new footpaths within the *road*,
- e) relocation of existing power/light pole,
- f) relocation/provision of street signs,
- g) new or replacement street trees,
- h) new footway verges, where a grass verge exists, the balance of the area between the footpath and the kerb or site boundary over the full frontage of the proposed development must be turfed. The grass verge must be constructed to contain a uniform minimum 75mm of friable growing medium and have a total cover of turf predominant within the street,
- i) new or reinstated kerb and guttering within the *road*, and
- j) new or reinstated road surface pavement within the *road*.

Note: Security held by Council pursuant to section 4.17(6) of the *Act* will not be release by Council until compliance has been achieved with this condition. An application for refund of security must be submitted with the Final Occupation Certificate to Council. This form can be downloaded from Council's website www.woollahra.nsw.gov.au or obtained from Council's customer service centre.
Standard Condition: H13 (Autotext HH13)

H.3 Covenant for Private Works on Council Property

A positive covenant, pursuant to section 88E of the *Conveyancing Act 1919*, must be created on the title of the subject property, providing for the indemnification of Council from any claims or actions, and the on-going maintenance of any private structures on or over Council property for which consent has been given, such as steps, retaining walls, access ways, overhang, balconies, awnings, signs and the like.

The wording of the Instrument must be in accordance with Council's standard format and the Instrument must be registered with the NSW Land Registry Services prior to the issuance of any Occupation Certificate. The property owner must reimburse all Council's expenses incurred in the drafting, negotiation and registration of the covenant

Note: The required wording of the Instrument can be downloaded from Council's website www.woollahra.nsw.gov.au. The PC must supply a copy of the WAE plans to Council together with the Occupation Certificate.

Note: The Occupation Certificate must be issued until this condition has been satisfied.
Standard Condition: H19 (Autotext HH19)

H.4 Works-As-Executed Certification of Stormwater Systems

Prior to issue of any Occupation Certificate, stormwater drainage works are to be certified by a chartered professional civil engineer with works-as-executed drawings prepared by a registered surveyor and submitted, for approval by the Principal Certifying Authority, certifying:

- a) compliance with conditions of development consent relating to stormwater,
- b) that subsoil drainage/seepage water is NOT collected and discharged into the kerb and gutter,
- c) that only one stormwater outlet pipe to kerb has been constructed within the frontage of the site,
- d) pipe invert levels and surface levels to Australian Height Datum, and
- e) contours indicating the direction in which water will flow over land should the capacity of the pit be exceeded in a storm event exceeding design limits.

Note: Occupation Certificate must not be issued until this condition has been satisfied.
Standard Condition: H20 (Autotext HH20)

I. Conditions which must be satisfied during the ongoing use of the development

I.1 Annual Fire Safety Statements (Class 1b to 9c buildings inclusive)

Each year, the owner of a building to which an *essential fire safety measure* is applicable must provide an *annual fire safety statement* to Council and the Commissioner of the NSW Fire Brigades. The *annual fire safety statement* must be prominently displayed in the building.

Standard Condition: I22

I.2 Operation in Accordance with Operational Traffic Management Plan

During the occupation and ongoing use:

- a) The delivery and waste collection operations shall be in accordance with the operational traffic management plan stated in Traffic Response to RFI, referenced 230667.02FB, prepared by McLaren Traffic Engineering and dated 23 February 2024.
- b) The delivery and waste collection vehicles attending the site must not impede safe access to the neighboring properties at all times.

I.3 Trading Hours

Trading hours are limited to:

a) **Monday to Sunday: 11am to 10pm.**

This condition has been imposed to mitigate amenity impacts upon the neighbourhood by commercial or retail trading including, but not limited to, external impacts associated with clients attending the site for business or otherwise.

Note: This condition does not apply to deliveries to, or dispatches from, the site of wholesale goods or internal activities that occur under the approved hours of use. General use and deliveries or dispatches may be restricted by hours of use conditions. This condition does not restrict the operation of noise pollution laws.

Standard Condition: I2

I.4 Extended Hours of Operation for Licensed Premises – Reviewable Condition

Reviewable Condition

The hours of operation for the indoor and outdoor areas of the licensed premises are extended as follows:

- From **(11am to 10pm)** as contained in **Condition I.3 to (11am to 12am (midnight))** Monday to Sunday.

This condition has been imposed to mitigate amenity impacts upon the neighbourhood.

Note: Council's consideration of the extended hours of operation of licensed premises will take into account:

- a) compliance of the premises in terms of security and its general management;
- b) the number and nature of substantiated complaints regarding the operation of the premises;
- c) compliance with the conditions of this consent; and
- d) any other matters considered relevant to the environmental evaluation of the premises.

Standard Condition: I4 (Autotext: I14)

I.5 Review of Extended Hours of Operation for Licensed Premises

Council will review the extended trading hours as referred to in **Condition I.4** generally as follows:

- a) one (1) year following the issue of any Occupation Certificate applicable to this application (if works are proposed) or the date of development consent (if no works are proposed),
- b) two (2) years following the first review, and
- c) each five (5) years thereafter.

This condition is a reviewable condition as referred to under section 4.17(10B-10D) of the Act.

This condition has been imposed to mitigate amenity impacts upon the neighbourhood.

Note: A review will only be undertaken if Council has satisfactory evidence to suggest the extended trading hours are unduly impacting on the amenity of the neighbourhood or NSW Police has requested a review.

Note: The review will be presented to the equivalent delegated decision making panel that determined the application and all stakeholders will be notified of the meeting.

Note: As a result of a review a reviewable condition may be changed.

Standard Condition: I5 (Autotext: I15)

I.6 Maximum Patron Capacity

The total number of patrons on the premises at any time shall not exceed **152** patrons.

Any person/s attending the premises for the purpose of 'takeaway' products/services will not be considered a 'patron' as detailed above, provided no food and or drink is consumed by those persons on the premises.

Standard Condition: I6 (Autotext: I16)

I.7 Signage to be Displayed – Licensed Premises

During the occupation and ongoing use, signage (in lettering not less than 15mm in height on a contrasting background) is to be erected in a prominent position near the principal entry to the premises in accordance with clause 73 of the Regulation.

The signage must state the following and may change from time to time due to reviewable conditions in accordance with the conditions of this consent:

"Approved hours of operation
Monday to Sunday: 11am – midnight
Approved patron capacity
152 patrons

Upon leaving please respect local residents by minimising noise."

This condition has been imposed to clearly identify the hours and patron capacity of the licensed premises.

I.8 Neighbourhood Amenity – Licensed Premises

The Management of the premises:

- a) Must ensure persons entering and leaving the premises do not crowd or loiter in the vicinity of the premises in such manner that pedestrian movement is obstructed or hindered.
- b) Must ensure that the manner in which the business of the premises is conducted and/or the behaviour of persons entering and leaving the premises does not cause undue disturbance to the amenity of the neighbourhood. In this regard, the Management shall be responsible for the control of noise and litter generated by persons and/or premises operations. If so directed by Council or by NSW Police, the Management is to employ private security staff to ensure that this condition is complied with.
- c) Must record in a Register full details of any disturbance complaint/s made by a person to Management or staff in respect to the manner in which the business of the premises is conducted and/or the behaviour of persons entering or leaving the premises. Such recording will include time, date, nature of the complaint/s and any complainant details if provided.
- d) Must respond to any disturbance complaint/s in a timely and effective manner. All actions undertaken by Management / staff to resolve such complaint/s shall be recorded in the Register.

This condition has been imposed to mitigate amenity impacts upon the neighbourhood.

Note: The lead agency for the enforcement of this condition is NSW Police.

Standard Condition: I10 (Autotext: I110)

I.9 Litter Patrols

Litter patrols are to be undertaken to collect and dispose of all litter and waste in the public areas adjacent to the licensed premises. Such patrols will take place intermittently during the hours of operation with the final patrol conducted at the cessation of trade.

A litter patrol Register must be maintained and kept on the premises at all times detailing date, time of patrol, staff member responsible, and Manager's signature.

This condition has been imposed to mitigate amenity impacts upon the neighbourhood.
Standard Condition: I11 (Autotext: II11)

I.10 Copies of Consents, Registers and Management Plans – Licensed Premises

A full copy of all current development consents (including approved plans) for the operation of the premises, any Registers required and any required Plan of Management must be kept on the premises and made available for inspection immediately upon request by Council, NSW Police and/or Liquor and Gaming NSW authorised officers.

Standard Condition: I12 (Autotext: II12)

I.11 Sale/Consumption of Liquor

Licensed Restaurant (On-Premises License)

- a) No liquor may be sold, supplied or consumed on the premises except with the approval and authorisation from Liquor and Gaming NSW.
- b) The primary use of the premises must be that of a restaurant with the provision of genuine meals, prepared upon the premises, to patrons seated at comfortable dining positions. This will include a seat and access to table / bench space generally in accordance with the approved plans
- c) Liquor may only be sold and/or supplied to patrons on the premises with or ancillary to a genuine meal.
- d) Patrons shall be seated whilst consuming liquor.
- e) The sale and/or supply of liquor must cease 15 minutes prior to the cessation of the respective hours of operation for the specified indoor and outdoor seating areas.
- f) No patron shall be permitted to take glasses or open containers of liquor off the premises.
- g) Management is responsible for ensuring the number of patrons in the premises does not exceed the approved capacity specified in **Condition I.6**.

This condition has been imposed to mitigate amenity impacts upon the neighbourhood.
Standard Condition: I14 (Autotext: II14)

I.12 Operation in Accordance with Plan of Management (POM)

- a) The operation and management of the premises shall be in accordance with the POM prepared by Merivale (Submitted to Council on 10/11/2023).
- b) The POM shall be filed with the Licensing Police of the Eastern Suburbs Police Area Command prior to the commencement of operations.
- c) The POM cannot be altered without the written consent of Council.

Standard Condition: I15 (Autotext: II15)

I.13 Garbage Collection

The garbage area must be maintained at all times to ensure that a breeding ground is not created for pests and must be capable of being easily and effectively cleaned.

All garbage containers must have tight fitting lids and be large enough or in sufficient numbers to contain all the waste produced by the business while awaiting the next removal from the premises.

This condition has been imposed to mitigate amenity impacts upon the neighbourhood.
Standard Condition: I16 (Autotext: II16)

I.14 Glass Sorting and Collection

Glass must not be emptied or transferred from one receptacle to another anywhere in a public place. All glass must be emptied/transferred within the premises and removed in containers.

No bottle or glass sorting, recycling or collection shall take place between 8.00pm and 8.00am Sunday to Friday and between 9.00pm Saturday and 10am Sundays and Public Holidays.

This condition has been imposed to protect the amenity of neighbouring residents.
Standard Condition: I17 (Autotext: II17)

I.15 Surveillance Cameras (CCTV)

Licensed Premises

The Management must maintain a closed-circuit television (CCTV) system on the premises. The CCTV system must comply with the following requirements:

- a) It must operate continuously from opening time until one hour after closing.
- b) It must record in digital format at a minimum of six frames per second.
- c) Any recorded image must specify the time and date of the image.
- d) The system's cameras must be located within the property and cover:
 - i) all entry and exit points of the premises,
 - ii) the footpath immediately adjacent to the premises, and
 - iii) all publicly accessible areas (other than toilets) on the premises, from floor level to a minimum height of two metres.
- e) CCTV recordings must be retained for at least 30 days.
- f) Management shall ensure the system is accessible by at least one member of staff at all times it is in operations, and
- g) Provide any recordings made by the system to Council or NSW Police within 24 hours of any request by an authorised officer to provide such recordings.

Note: The lead agency for enforcement is NSW Police.
Standard Condition: I18 (Autotext: II18)

I.16 NSW Police Requirements (Licensed Premises)

Incidents involving acts of violence

Immediately after the person in charge of the licensed premises becomes aware of an incident involving an act of violence causing an injury to a person on the premises, the person must:

- a) take all practical steps to preserve and keep intact the area where the act of violence occurred,
- b) retain all material and implements associated with the act of violence in accordance with the Crime Scene Preservation Guidelines issued by the NSW Police, and
- c) make direct and personal contact with the Eastern Suburbs Police Area Command and advise the Commander or delegate of the incident, and comply with any directions given by the Commander or delegate to preserve or keep intact the area where the violence occurred.

Safety and Security Measures

The following safety and security measures must be complied with:

- a) The entrance is to remain illuminated during all hours of trade past sunset until close.
- b) The licensed premises are to be supervised during all hours of trade.
- c) An incident register is to be utilised and maintained on a daily basis solely for the purpose of the ground floor restaurant during all hours of trade.

Designated Taxi Phone Service

A designated taxi phone line or similar service is to be located at the bar service area and maintained by management during all hours of trade and is to be implemented from the date of commencement of the restaurant use.

No Use of Strobes, Lasers or Flicker Lights

No strobes, lasers or flicking lights are to be employed to the restaurant area.

Note: The lead agency for enforcement is NSW Police.
Standard Condition: I19

I.17 Waste Collection – Commercial

General waste collection is to be undertaken ONLY between the hours of:
7.00am to 9.00pm Monday to Friday, and
8.00am to 8.00pm Saturday, Sunday and Public Holidays

This condition has been imposed to protect the amenity of neighbouring residents.
Standard Condition: I31 (Autotext: I131)

I.18 Storage and Handling of Flammable and Combustible Liquids

The storage and handling of flammable and combustible liquids must be in accordance with AS1940: *The storage and handling of flammable and combustible liquids*.

Note: This condition has been imposed to protect public safety.
Standard Condition: I38

I.19 Food Premises - Maintenance of Food Premises

During the occupation and ongoing use, the food premises must be maintained in accordance with the Food Act 2003, Food Regulation 2015; the Food Standards Code as published by Food Standards Australia and New Zealand and Australian Standard AS 4674: Construction and fit out of food premises.

Note: This condition has been imposed to protect public health.
Standard Condition: I41

I.20 Outdoor Lighting – Commercial

Outdoor lighting must comply with AS/NZS 4282:2019: *Control of the obtrusive effects of outdoor lighting*. The maximum luminous intensity from each luminare and threshold limits must not exceed the level 1 control relevant under tables in AS/NZS 4282:2019.

Note: This condition has been imposed to protect the amenity of neighbours and limit the obtrusive effects of outdoor lighting in public places.

Note: Council may consider, subject to an appropriate Section 4.55 Application, relaxation of this condition where it can be demonstrated, by expert report, that the level of lighting in the existing area already exceeds the above criteria, where physical shielding is present or physical shielding is reasonably possible.
Standard Condition: I50

I.21 Noise Control

The use of the premises must not give rise to the transmission of *offensive noise* to any place of different occupancy. *Offensive noise* is defined in the *Protection of the Environment Operations Act 1997*.

Note: This condition has been imposed to protect the amenity of the neighbourhood.

Note: Council will generally enforce this condition in accordance with the *Noise Guide for Local Government* (www.epa.nsw.gov.au/your-environment/noise/regulating-noise/noise-guide-local-government) and the *NSW Industrial Noise Policy* (www.epa.nsw.gov.au/your-environment/noise/industrial-noise) published by the NSW Environment Protection Authority. Other State Government authorities also regulate the *Protection of the Environment Operations Act 1997*.

Useful links:

Community Justice Centres—free mediation service provided by the NSW Government
www.cjc.nsw.gov.au.

NSW Environment Protection Authority— see “noise” section
www.environment.nsw.gov.au/noise.

NSW Government legislation- access to all NSW legislation, including the *Protection of the Environment Operations Act 1997* and the *Protection of the Environment Noise Control Regulation 2000* is available at www.legislation.nsw.gov.au.

Australian Acoustical Society—professional society of noise related professionals
www.acoustics.asn.au.

Association of Australian Acoustical Consultants—professional society of noise related professionals www.aaac.org.au.

Liquor and Gaming NSW—www.liquorandgaming.nsw.gov.au.
Standard Condition: I56

I.22 Maintenance of Sound Attenuation

Sound attenuation must be maintained in accordance with the *Acoustic Report, prepared by The Acoustic Group, dated 06/06/2023*.

I.23 Noise from Licensed Premises

The L_{A10} noise level emitted from the licensed premises shall not exceed the *background noise level* in any Octave Band Centre Frequency (31.5 Hz – 8k Hz inclusive) by more than 5dB(A) between 07:00 am and 12:00 midnight at the boundary of any affected residence.

The L_{A10} noise level emitted from the licensed premises shall not exceed the *background noise level* in any Octave Band Centre Frequency (31.5 Hz – 8k Hz inclusive) between 12:00 midnight and 07:00am at the boundary of any affected residence.

Notwithstanding compliance with the above, the noise from the licensed premises shall not be audible within any habitable room in any residential premises between the hours of 12:00 midnight and 07:00am.

Note: This condition has been imposed to protect the amenity of the neighbourhood.

Note: dB(A) is a value used for ‘A-weighted’ sound pressure levels ‘A’ frequency weighting is an adjustment made to approximate the response of the human ear.

Note: *licensed premises* means premises licensed under the *Liquor Act 2007*.

Note: For the purposes of this condition, the LA10 is the A-weighted sound pressure level that is exceeded for 10% of the time over which a given sound is measured.

Note: The *background noise level* is the underlying level present in the ambient noise, excluding the subject noise source, when extraneous noise is removed. For assessment purposes the background noise level is the L_{A90} level measured by a sound level meter over the applicable period.

Note: This condition reflects the minimum standard condition imposed by the former Casino Liquor and Gaming Control Authority. Liquor & Gaming NSW or the Independent Liquor & Gaming Authority may specify other standards in respect of the above condition under the *Liquor Act 2007*, and associated Regulations. Section 79 of the *Liquor Act 2007* provides an informal mechanism for complaints to be made (by residents, Police, local consent authorities and others) where the amenity of local neighbourhoods is unduly disturbed by the conduct of licensed premises including registered clubs (or their patrons). The Secretary of the Department of Industry is responsible for resolving such complaints and may impose temporary or permanent conditions on any licence. For more information go to Liquor and Gaming NSW website www.liquorandgaming.nsw.gov.au

Note: Interior noise levels of licensed premises which exceed safe hearing levels are not supported or condoned by Council.
Standard Condition: I58

I.24 Noise from Mechanical Plant and Equipment

The noise level measured at any boundary of the site at any time while the mechanical plant and equipment is operating must not exceed the *background noise level*. Where noise sensitive receivers are located within the site, the noise level is measured from the nearest strata, stratum or community title land and must not exceed *background noise level* at any time.

The *background noise level* is the underlying level present in the ambient noise, excluding the subject noise source, when extraneous noise is removed. For assessment purposes the background noise level is the $L_{A90, 15 \text{ minute}}$ level measured by a sound level meter.

Note: This condition has been imposed to protect the amenity of the neighbourhood.

Note: Words in this condition have the same meaning as in the *Noise Policy for Industry* (2017) [www.epa.nsw.gov.au/your-environment/noise/industrial-noise/noise-policy-for-industry-\(2017\)](http://www.epa.nsw.gov.au/your-environment/noise/industrial-noise/noise-policy-for-industry-(2017))

and *Noise Guide for Local Government* (2013) www.epa.nsw.gov.au/your-environment/noise/regulating-noise/noise-guide-local-government

Standard Condition: I59

I.25 Maintenance of the Kitchen Exhaust log

A logbook detailing the schedule maintenance and cleaning of the odour control units and filtering systems shall be kept on the premises at all times and be made available for viewing by Council's Environmental Health Officer's as required.

I.26 Access via Victoria Street

The rear access via Victoria Street shall be limited to use by staff as an emergency exit when required and for the purposes of waste management, deliveries and vehicle access as specified in this consent.

- There shall be no access or egress for restaurant customers except when required as an emergency exit.
- At all other times the access shall be for emergency purposes only.

This condition has been imposed to mitigate amenity impacts upon the neighbourhood.

J. Miscellaneous Conditions

Nil.

K. Advisings

K.1 Criminal Offences – Breach of Development Consent and Environmental Laws

Failure to comply with this development consent and any condition of this consent is a **criminal offence**. Failure to comply with other environmental laws is also a criminal offence.

Where there is any breach Council may without any further warning:

- a) Issue Penalty Infringement Notices (On-the-spot fines);
- b) Issue notices and orders;
- c) Prosecute any person breaching this consent; and/or
- d) Seek injunctions/orders before the courts to restrain and remedy any breach.

Warnings as to potential maximum penalties

Maximum penalties under NSW environmental laws include fines up to \$1.1 Million and/or custodial sentences for serious offences.

Warning as to enforcement and legal costs

Should Council have to take any action to enforced compliance with this consent or other environmental laws Council's policy is to seek from the Court appropriate orders requiring the payments of its costs beyond any penalty or remedy the Court may order.

This consent and this specific advice will be tendered to the Court when seeking costs orders from the Court where Council is successful in any necessary enforcement action.

Note: The payment of environmental penalty infringement notices does not result in any criminal offence being recorded. If a penalty infringement notice is challenged in Court and the person is found guilty of the offence by the Court, subject to section 10 of *the Crimes (Sentencing Procedure) Act 1999*, a criminal conviction is recorded. The effect of a criminal conviction beyond any fine is serious.

Standard Advising: K1 (Autotext KK1)

K.2 Dial Before You Dig



The Principal Contractor, Owner-builder or any person digging may be held financially responsible by the asset owner should they damage underground pipe or cable networks. Minimise your risk and dial 1100 Before You Dig or visit www.1100.com.au

When you contact Dial Before You Dig you will be sent details of all Dial Before You Dig members who have underground assets in the vicinity of your proposed excavation.

Standard Advising: K2 (Autotext KK2)

K.3 Builder's Licences and Owner-builders Permits

Section 6.6(2)(d) of the *Act* requires among other matters that the person having the benefit of the development consent, if not carrying out the work as an **owner-builder**, must appoint a Principal Contractor for residential building work who must be the holder of a contractor licence.

The Owner(s) must appoint the Principal Certifier. The Principal Certifier must check that the required insurances are in place before the commencement of building work. The Principal Contractor (builder) must provide the Owners with a certificate of insurance evidencing the contract of insurance under the *Home Building Act 1989* for the residential building work.

Note: For more information go to the NSW Fair Trading website
www.fairtrading.nsw.gov.au/housing-and-property/building-and-renovating
Standard Condition: K5 (Autotext KK5)

K.4 Building Standards - Guide to Standards and Tolerances

The Principal Certifier does not undertake detailed quality control inspections and the role of the Principal Certifier is primarily to ensure that the development proceeds in accordance with this consent, Construction Certificates and that the development is fit for occupation in accordance with its classification under the Building Code of Australia.

Critical Stage Inspections do not provide the level of supervision required to ensure that the minimum standards and tolerances specified by the "NSW Guide to Standards and Tolerances 2017" are achieved.

The quality of any development is a function of the quality of the Principal Contractor's or Owner-builder's supervision of individual contractors and trades on a daily basis during the development. The Principal Certifier does not undertake this role.

Council, as the Principal Certifier or otherwise, does not adjudicate building contract disputes between the Principal Contractor, contractors and the Owner.

Note: For more information on the *NSW Guide to Standards and Tolerances* go to the NSW Fair Trading website www.fairtrading.nsw.gov.au/housing-and-property/building-and-renovating/after-you-build-or-renovate/guide-to-standards-and-tolerances or call 133 220. Standard Condition: K6 (Autotext KK6)

K.5 SafeWork NSW Requirements

The *Work Health and Safety Act 2011* and subordinate regulations, codes of practice and guidelines control and regulate the development industry.

Note: For more information go to the SafeWork NSW website www.safework.nsw.gov.au or call 131 050. Standard Condition: K7 (Autotext KK7)

K.6 Dividing Fences

The erection of dividing fences under this consent does not affect the provisions of the *Dividing Fences Act 1991*. Council does not adjudicate civil disputes relating to the provision of, or payment for, the erection of dividing fences.

Note: Further information can be obtained from the NSW Civil and Administrative Tribunal www.ncat.nsw.gov.au/Pages/cc/Divisions/dividing_fences.aspx

Note: Community Justice Centres provide a free mediation service to the community to help people resolve a wide range of disputes, including dividing fences matters. Their service is free, confidential, voluntary, timely and easy to use. Mediation sessions are conducted by two impartial, trained mediators who help people work together to reach an agreement. Around 75% of mediations result in an agreement being reached. Mediation sessions can be arranged at convenient times during the day, evening or weekends. To contact the Community Justice Centres go to www.cjc.nsw.gov.au or call 1800 990 777.
Standard Advising: K10 (Autotext KK10)

K.7 Appeal

Council is always prepared to discuss its decisions and, in this regard, please do not hesitate to contact Valdis Aleidzans, Assessment Officer, on (02) 9391 7159.

However, if you wish to pursue your rights of appeal in the Land and Environment Court you are advised that Council generally seeks resolution of such appeals through a section 34 Conference, site hearings and the use of Court Appointed Experts, instead of a full Court hearing.

This approach is less adversarial, it achieves a quicker decision than would be the case through a full Court hearing and it can give rise to considerable cost and time savings for all parties involved. The use of the section 34 Conference approach requires the appellant to agree, in writing, to the Court appointed commissioner having the full authority to completely determine the matter at the conference.

Standard Condition: K14 (Autotext KK14)

K.8 Release of Security

An application must be made to Council by the person who paid the security for release of the securities held under section 4.17 of the *Act*.

The securities will not be released until a Final Occupation Certificate has been lodged with Council, Council has inspected the site and Council is satisfied that the public works have been carried out to Council's requirements. Council may use part or all of the security to complete the works to its satisfaction if the works do not meet Council's requirements.

Council will only release the security upon being satisfied that all damage or all works, the purpose for which the security has been held have been remedied or completed to Council's satisfaction as the case may be.

Council may retain a portion of the security to remedy any defects in any such public work that arise within 6 months after the work is completed.

Upon completion of each section of road, drainage and landscape work to Council's satisfaction, 90% of the bond monies held by Council for these works will be released upon application. 10% may be retained by Council for a further 6 month period and may be used by Council to repair or rectify any defects or temporary works during the 6 month period.

Note: The Refund of Security Bond Application form can be downloaded from www.woollahra.nsw.gov.au

Standard Condition: K15 (Autotext KK15)

K.9 Recycling of Demolition and Building Material

It is estimated that building waste, including disposable materials, resulting from demolition, excavation, construction and renovation, accounts for almost 70% of landfill. Such waste is also a problem in the generation of dust and the pollution of stormwater. Council encourages the recycling of demolition and building materials. Standard Condition: K17 (Autotext KK17)

K.10 Owner-builders

Under the *Home Building Act 1989* any property owner who intends undertaking construction work to a dwelling house or dual occupancy to the value of \$12,000 or over must complete an approved education course and obtain an owner-builder permit from NSW Fair Trading.

Note: For more information go to the NSW Fair Trading website www.fairtrading.nsw.gov.au or call 133 220. Standard Condition: K18 (Autotext KK18)

K.11 Pruning or Removing a Tree Growing on Private Property

The provisions of State Environmental Planning Policy (Vegetation in Non-Rural Areas) 2017 and the Woollahra Development Control Plan 2015 (DCP), Chapter E3 –Tree Management, may require that an application be made to Council prior to pruning or removing any tree. The aim is to secure the amenity of trees and preserve the existing landscape within our urban environment.

Before you prune or remove a tree, make sure you read all relevant conditions. You can obtain a copy of the Woollahra DCP from Council's website www.woollahra.nsw.gov.au or call Council on 9391 7000 for further advice. Standard Condition: K19 (Autotext KK19)

K.12 Dilapidation Report

Please note the following in relation to the condition for a dilapidation report:

- a) The dilapidation report will be made available to affected property owners on requested and may be used by them in the event of a dispute relating to damage allegedly due to the carrying out of the development.
- b) This condition cannot prevent neighbouring buildings being damaged by the carrying out of the development.
- c) Council will not be held responsible for any damage which may be caused to adjoining buildings as a consequence of the development being carried out.
- d) Council will not become directly involved in disputes between the developer, its contractors and the owners of neighbouring buildings.
- e) In the event that access for undertaking the dilapidation survey is denied the Applicant is to demonstrate in writing to the satisfaction of the Principal Certifier that all reasonable steps were taken to obtain access to the adjoining property. The dilapidation report will need to be based on a survey of what can be observed externally. Standard Advising: K23 (Autotext KK23)

K.13 Roads Act 1993 Application

Works or structures over, on or under public roads or footpaths are subject to sections 138, 139 and 218 of the *Roads Act 1993* and specifically:

- Construction of driveways and/or new or alterations to footpath paving
- Alteration and/or extension to Council drainage infrastructure
- Alteration and/or addition of retaining walls
- Pumping of water to Council's below ground stormwater system
- Installation of soil/rock anchors under the roadway
- Installation of Stormwater outlet pipes across the nature strip

An "Application to Carry Out Works in a Public Road" form must be completed and lodged, with the application fee, at Council's Customer Services. Detailed plans and specifications of all works (including but not limited to structures, road works, driveway crossings, footpaths and stormwater drainage etc) within existing roads, must be attached, submitted to and approved by Council under section 138 of the *Roads Act 1993*, before the issue of any Construction Certificate.

Detailed engineering plans and specifications of the works required by this condition must accompany the application form. The plans must clearly show the following:

- Engineering drawings (plan, sections and elevation views) and specifications of the footpath, driveways, kerb and gutter, new gully pit showing clearly the connection point of site outlet pipe(s). Note, the connection drainage lines must be as direct as possible and generally run perpendicular to the kerb alignment.
- Engineering drawings of the new drainage line to be constructed joining the new and existing drainage pits including services.

All driveways must include a design longitudinal surface profile for the proposed driveway for assessment. The driveway profile is to start from the road centreline and be along the worst case edge of the proposed driveway. Gradients and transitions must be in accordance with clause 2.5.3, 2.6 of AS 2890.1 – 2004, Part 1 – *Off-street car parking*. The driveway profile submitted to Council must be to (1:25) scale (for template checking purposes) and contain all relevant details: reduced levels, proposed grades and distances.

The existing footpath level and grade at the street alignment of the property must be maintained unless otherwise specified by Council. Your driveway levels are to comply with AS2890.1 and Council's Standard Drawings. There may be occasions where these requirements conflict with your development and you are required to carefully check the driveway/garage slab and footpath levels for any variations.

Note: Any adjustments required from the garage slab and the street levels are to be carried out internally on private property

Drainage design works must comply with the Woollahra DCP 2015 Chapter E2 – Stormwater and Flood Risk Management.

Temporary ground anchors may be permitted, in accordance with Council's "Rock Anchor Policy".

Services: Prior to any excavation works, the location and depth of all public utility services (telephone, cable TV, electricity, gas, water, sewer, drainage, etc.) must be ascertained. The Applicant shall be responsible for all public utility adjustment/relocation works, necessitated by the development work and as required by the various public utility authorities and/or their agents.

All public domain works must comply with the latest version of Council's "*Specification for Roadworks, Drainage and Miscellaneous Works*" unless expressly provided otherwise by these conditions. This specification and the application form can be downloaded from www.woollahra.nsw.gov.au.

Note: To ensure that this work is completed to Council's satisfaction, this consent by separate condition, may impose one or more Infrastructure Works Bonds.

Note: When an application under the *Roads Act* is required, then four (4) weeks is to be allowed for assessment.

Note: *road* has the same meaning as in the *Roads Act 1993*.

Note: The intent of this condition is that the design of the road, footpaths, driveway crossings and public stormwater drainage works must be detailed and approved prior to the issue of any Construction Certificate. Changes in levels may arise from the detailed design of buildings, road, footpath, driveway crossing grades and stormwater. Changes required under *Road Act 1993* approvals may necessitate design and levels changes under this consent. This may in turn require the Applicant to seek to amend this consent.

Standard Advising: K24 (Autotext KK24)

Note: In accordance with the Woollahra Local Planning Panel Operational Procedures the votes are recorded on this planning matter.

For the Motion

Peter Brennan
Larissa Ozog
Malcolm Young

Against the Motion

Nil

3/0

There being no further business the meeting concluded at 2.16pm.

We certify that the pages numbered 1 to 203 inclusive are the Minutes of the Woollahra Local Planning Panel (Electronic Meeting) Meeting held on 18 July 2024 and confirmed by all Panel members of the Woollahra Local Panel on 22 July 2024 as correct.

Chairperson

Secretary of Committee

Expert

Expert

Community Representative